



REPORT

Operation, Maintenance, and Surveillance (OMS) Manual

Giant Mine Remediation Project

Submitted to:

Public Services and Procurement Canada

Suite 1000, 9700 Jasper Avenue
Edmonton, Alberta T5J 4C3

Submitted by:

WSP Canada Inc.

1721 8th Street East, Saskatoon, Saskatchewan, S7H 0T4, Canada

+1 306 665 7989

Operation, Maintenance and Surveillance Manual (Version G)

Reference No. 18102211-863-R-Rev0-45000D

October 1, 2024



Document History

The Operation, Maintenance, and Surveillance (OMS) Manual should be reviewed on an annual basis and following any significant changes at the site to assess if the document is representative of the current condition and operation of the dams at the time of the review. Revisions to the manual should be undertaken within a reasonable timeframe (not to exceed six months) of changes should updates to the content be required. The version history of the OMS Manual is shown below. The most current revision of the OMS Manual supersedes all previous versions.

Revision No.	Revision Date	Revised by	Revision Notes
G	2024-10-01	WSP Canada Inc	Added new instrumentation installation in Northwest TCA dams, Mill Pond Structure, and B2 Dam Monitoring. Updated warning levels for instrumentation on Dam 1, Splitter Dyke, B2 Dam, and Northwest TCA Dams. Updated EPRP to align with Parsons EMSRP. Updated climate data (Appendix D). Removed Appendix F (Water Pond Elevations) in the last version and accordingly adjusted numbering of the appendices.
F	2023-11-06	WSP Canada Inc.	Updated seismic data for Site. Updated flood runoff volumes for the Northwest Pond, North Pond, Settling and Polishing Ponds based on inflow design flood. Updated pond storage volume versus water elevations for Settling and Polishing Ponds. Updated pond water level and corresponding warning levels in the Polishing Pond based on Dam 1 raise. Added instrumentation and displacement warning levels of for Splitter Dyke. Added Mill Pond Structure to surveillance. Updated environment protection and reporting and documentation for operations. Include instrumentation installed in April 2023. Updated water licence sampling and testing. Added an appendix on Responsibility of Updating OMS (Appendix A).
E	2022-07-22	Parsons Inc.	Updated dam classifications based on the 2020 Dam Break Analysis. Updated dam dimensions. Updated warning levels for B2 Dam piezometers. Updated pond level differential between the Polishing Pond and the Settling Pond associated with the Splitter Dyke.
D	2021-06-09	Golder Associates Ltd.	Include instrumentation installed in 2019 and 2020. Incorporated applicable recommendations from 2019 Dam Safety Review and 2020 Annual Geotechnical Inspection.
C	2019-09-04	Golder Associates Ltd.	Minor corrections to text.
B	2019-02-15	Golder Associates Ltd.	Incorporate client comments, organizational changes, 2018 inspection and drilling results.
A	2018-03-27	Golder Associates Ltd.	Reviewed and rewritten to comply with up-to-date standards, best practices, and regulations.
2006 Version 2	2006-10-12	Original by Golder Associates Ltd.	

Signature Page

The update of this OMS is a shared responsibility between Parsons (i.e., Main Construction Manager) and WSP (i.e., Geotechnical Consultant). The specific updating responsibility of each individual section is presented in Appendix A.

The review protocol for the OMS Manual is shown below.



Revised by:	Hung Vu, Engineer of Record WSP Canada Inc.	 Signature	October 1, 2024 Date
	Doug Hayes, Mine Manager Parsons Inc.	 Signature	October 02, 2024 Date
Reviewed by:	Reuben Makohoniuk, Environmental Manager Parsons Inc.	 Signature	Digitally signed by Reuben Makohoniuk Date: 2024.10.02 12:06:26 -06'00' Date
	Bradley Mueller, Site Operations Manager Public Services and Procurement Canada	 Signature	Digitally signed by: Mueller, Bradley DN: CN = Mueller, Bradley C = CA O = GC OU = PWGSC-TPSGC Date: 2024.10.02 14:47:03 -06'00' Date
	Carlos Philipovsky, Project Manager Public Services and Procurement Canada	 Signature	Digitally signed by: Philipovsky, Carlos DN: CN = Philipovsky, Carlos C = CA O = GC OU = PWGSC-TPSGC Date: 2024.10.02 14:28:35 -06'00' Date
Approved by:	Miguel Larivière, Engineering Manager Crown-Indigenous Relations and Northern Affairs Canada	 Signature	03 OCT 2024 Date
	Natalie Plato, Deputy Director Crown-Indigenous Relations and Northern Affairs Canada	 Signature	Digitally signed by Natalie Plato DN: OU=Giant Mine Remediation Project, O= CORNAC, CN=Natalie Plato, E=natalie.plato@rcanac -cra.gc.ca Reason: I have reviewed this document Location: Date: 2024.10.15 15:08:19-06'00' Foxit PDF Editor Version: 12.1.2 Date

Table of Contents

1.0 OBJECTIVE 1

2.0 DOCUMENT USER GUIDE 2

3.0 ROLES AND RESPONSIBILITIES 4

 3.1 Organization Chart 4

 3.2 Responsibilities and Contact Information of Formally Assigned Individuals 6

 3.3 Requirements for Competency and Training 9

 3.4 Site Personnel 10

 3.5 Responsibilities for Managing Change 10

4.0 SITE AND FACILITIES DESCRIPTION 11

 4.1 Site Overview 11

 4.2 Tailings Transportation and Deposition 13

 4.3 Access Roads and Security 13

 4.4 Dam Consequence Classification 13

5.0 SITE REFERENCE DATA 17

 5.1 Applicable Guidance and Regulatory Requirements 17

 5.2 Mine Operating Manuals 17

 5.3 Coordinate System and Maps 17

 5.4 Regulatory Framework for Dam Safety 18

6.0 SITE CONDITIONS 19

 6.1 Topography 19

 6.2 Geology 19

 6.3 Vegetation and Wildlife 19

 6.4 Climate 19

 6.5 Water Balance 20

 6.6 Permafrost 20

 6.7 Seismicity 21

7.0	OPERATIONS	22
7.1	Water Management	24
7.2	Water Treatment	26
7.3	Pond Storage Capacity	26
7.4	Flood Runoff Volume	30
7.5	Minimum Freeboards	31
7.6	Pond Water Levels and Warning Levels	32
7.6.1	Minimum Freeboard and Differential Water Level	32
7.6.2	Actions Corresponding to Warning Levels	35
7.6.3	Rate of Water Elevation Change	37
7.7	Environmental Protection	37
7.8	Change Management	37
7.9	Documentation	37
7.10	Reporting and Documentation	37
8.0	SURVEILLANCE	39
8.1	Objectives	39
8.2	Training Requirements	39
8.3	Surveillance Procedures	39
8.4	Visual Inspection	40
8.4.1	General Inspection Requirements	40
8.4.2	Specific Monitoring Requirements	43
8.4.2.1	Monitoring of Cracks	43
8.4.2.2	Dam 1 Thermosyphons	44
8.4.3	Warning Levels and Corresponding Actions	44
8.5	Instrumentation	47
8.5.1	Minimum Monitoring Frequency	48
8.5.2	Warning Level	49
8.5.2.1	Vibrating Wire Piezometers	50
8.5.2.2	Standpipe Piezometer Warning Levels	51

8.5.2.3	Thermistor String Warning Levels	52
8.5.2.4	Inclinometer and Shape Array Warning Levels	53
8.5.2.5	Displacement Monitoring Warning Levels	53
8.5.3	Actions Corresponding to Warning Levels.....	54
8.6	Water Sampling and Testing.....	56
8.7	Survey and Bathymetry	56
8.7.1	InSAR Monitoring	56
8.8	Weather Stations.....	57
8.9	Annual Geotechnical Inspections of Dams	57
8.10	Frequency of Dam Safety Reviews.....	57
8.11	Event-Driven Procedures	58
8.12	Trigger for Change of Operations	58
8.13	Documentation and Reporting	58
9.0	MAINTENANCE	60
9.1	Objectives.....	60
9.2	Inventory of Components Requiring Maintenance.....	60
9.3	Maintenance Schedule and Triggers	60
9.4	Routine and Preventative Maintenance	61
9.4.1	Access.....	61
9.4.2	Dams and Dykes.....	61
9.4.3	Spillways and Water Management Channels	62
9.4.4	Water Management and Treatment Equipment.....	62
9.4.5	Dam 1 Thermosyphon Maintenance.....	63
9.4.6	Event-Driven Maintenance.....	63
9.4.7	Documentation and Reporting	63
10.0	EMERGENCY PREPAREDNESS AND RESPONSE PLAN	64
10.1	Requirements of Legislation, Codes of Practice, Commitments, etc.....	64
10.2	Identification of all Jurisdictions, Agencies, and Individuals Involved in Preparedness and Response	64

10.3	Training Requirements	65
10.4	Public Relations Plan	65
10.5	Emergency Response Plans.....	65
10.5.1	Emergency Response Plan – Dam Failure.....	65
10.5.2	Other Emergency Response Plans	69
10.6	Incident Investigation Procedure.....	71
10.7	Call-out Procedure for Emergency Response	71
10.8	Exceedance of Caution Warning Levels and Corresponding Actions	71
10.9	Communication System and Procedures.....	73
10.10	Preventive and Remedial Responses for Different Failure Modes	73
10.11	Available Resources	75
10.12	Assessment for On-site and Off-site Effects	78
10.13	Emergency Preparedness and Response Plan Testing	78
REFERENCES		79

TABLES

Table 1: Individual's Responsibilities	7
Table 2: Required Proficiencies and Training	9
Table 3: Summary of Dam Consequence Classifications	14
Table 4: Frequency for Dam Safety Reviews	18
Table 5: Storage Volume with Water Elevation Data – Northwest Pond	27
Table 6: Storage Volume with Water Elevation Data – North Pond.....	28
Table 7: Storage Volume with Water Elevation Data – Polishing Pond and Settling Pond	29
Table 8: Design Runoff Volume.....	31
Table 9: Minimum Freeboard and Corresponding Water Levels	31
Table 10: Warning Level Descriptions – Minimum Freeboard and Pond Differential	32
Table 11: Warning Levels – Pond Water Elevation and Freeboard Criteria	33
Table 12: Warning Levels - Water Differential Criteria	33
Table 13: Actions for Corresponding to Pond Warning Levels	36
Table 14: Failure Modes and Identification	40
Table 15: Minimum Visual Inspection Frequencies	41

Table 16: Warning Level Descriptions: Visual Inspections.....	45
Table 17: Visual Inspection Warning Levels and Actions	46
Table 18: Summary of Number of Operational Geotechnical Instrumentation.....	48
Table 19: Minimum Instrumentation Readings Frequency.....	49
Table 20: Warning Level Descriptions: Instrument Readings	50
Table 21: Dam 1 Vibrating Wire Piezometer Warning Level Criteria	50
Table 22: B2 Dam Vibrating Wire Piezometer Warning Level Criteria.....	51
Table 23: Standpipe Piezometers to be Monitored on Original TCA and Mill Pond Structure.....	51
Table 24: Dam 1: Thermistor Warning Levels.....	52
Table 25: Northwest Tailings Containment Area: Thermistor Warning Levels.....	52
Table 26: Inclinator Warning Level Criteria	53
Table 27: Dam 1 Displacement Monitoring Warning Level Criteria	53
Table 28: B2 Dam Displacement Monitoring Warning Level Criteria	54
Table 29: B2 Dam Historical Displacement Monitoring Monuments	54
Table 30: Splitter Dyke Displacement Monitoring Warning Level Criteria.....	54
Table 31: Actions for Corresponding to Instrumentation Warning Levels.....	55
Table 32: Surveillance Reporting Requirements.....	58
Table 33: Actions for Exceedance of Caution Warning Levels	72
Table 34: Actions for Unusual Events	72
Table 35: Emergency Contact Information.....	73
Table 36: Preventive and Remedial Responses for Failure Modes	74
Table 37: Available Resources.....	76

FIGURES

Figure 1: Giant Mine Chain of Command.....	5
Figure 2: Overview of Giant Mine	12
Figure 3: Overview of Original TCA Dams at Giant Mine.....	15
Figure 4: Overview of Northwest TCA Dams at Giant Mine	16
Figure 5: Overview of Water Management Facilities at Giant Mine	23
Figure 6: Overview of Water Treatment at Giant Mine.....	25
Figure 7: Water Elevation Versus Storage Volume – Northwest Pond	27
Figure 8: Water Elevation Versus Storage Volume – North Pond	28
Figure 9: Water Elevation Versus Storage Volume – Polishing and Settling Ponds.....	30

Figure 10: Water and Infrastructure Elevations for Northwest Pond (not to scale) 33

Figure 11: Water and Infrastructure Elevations for Polishing Pond (not to scale)..... 34

Figure 12: Water and Infrastructure Elevations for Baker Creek (not to scale)..... 34

Figure 13: Water and Infrastructure Elevations for Mill Pond Structure and Baker Creek (not to scale) 34

Figure 14: Water and Infrastructure Elevations Dam 2 / North Pond (not to scale) 35

Figure 15: Water and Infrastructure Elevations for Settling Pond / Splitter Dyke (not to scale)..... 35

Figure 16: Dam 1 Thermosyphons Alignment 44

Figure 17: Emergency Response Plan – Dam Failure 66

Figure 18: Emergency Response Plan – Inundation Risk Areas 67

Figure 19: Emergency Response Plan – Road Blockade Points 68

Figure 20: Parsons Emergency Response Communications Plan for Giant Mine Remediation Project 70

Figure 21: Potential Borrow Site 77

APPENDICES

Appendix A
Responsibility of Updating OMS

Appendix B
Dam Geometry and Foundation

Appendix C
Dam Consequence Classifications

Appendix D
Climate Data

Appendix E
Water Balance

Appendix F
Inspection Forms

Appendix G
Instrumentation Installation Details and Instrument Calibration Certificates

List of Acronyms and Abbreviations

Acronym/Abbreviation	Definition
AEMP	Aquatic Effects Monitoring Program
AGI	Annual Geotechnical Inspection
AHCCD	Adjusted Historical Canadian Climate Data
CDA	Canadian Dam Association
CIRNAC	Crown-Indigenous Relations and Northern Affairs Canada
CRP	Closure and Reclamation Plan
CWEEDS	Canadian Weather Energy and Engineering Datasets
DBA	Dam Breach Analysis
DSR	Dam Safety Review
EEM	Environmental Effects Monitoring
EMSRP	Emergency Management and Spill Response Plan
EPRP	Emergency Preparedness and Response Plan
ERP	Emergency Response Plan
ETP	Effluent Treatment Plant
GMOB	Giant Mine Oversight Board
GMRP	Giant Mine Remediation Project
GNWT	Government of Northwest Territories
HDPE	High-density polyethylene
InSAR	Interferometric Synthetic Aperture Radar
MAC	Mining Association of Canada
MCM	Main Construction Manager
MDMER	Metal and Diamond Mining Effluent Regulations
MVLWB	Mackenzie Valley Land and Water Board
NHC	Northwest Hydraulic Consultants
NHWL	Non Hazard Waste Landfill
OMS	Operation, Maintenance, and Surveillance
PGA	Peak ground acceleration
PMF	Peak maximum flood
PMP	Probable maximum precipitation
PSPC	Public Services and Procurement Canada
RCMP	Royal Canadian Mounted Police
RFID	Radio Frequency ID
SAA	Shape Array Accelerometer
SOP	Standard Operating Procedure
SRK	SRK Consulting Ltd.
SWE	Snow Water Equivalent
TCA	Tailings Containment Area
UBC	Under Baker Creek
USSD	United States Society on Dams
UTM	Universal Transverse Mercator
VWP	Vibrating wire piezometer
WSCC	Workers' Safety and Compensation Commission

List of Units and Symbols

Unit	Definition
cm	centimetre
m ³	cubic metres
m ³ /day	cubic meters per day
m ³ /s	cubic meters per second
°C	degrees Celsius
ha	hectare
Hz	Hertz
in	inch
km	kilometer
kΩ	kilo-Ohm
kPa	kilo-Pascal
masl	meters above sea level
mbgs	meters below ground surface
m	metre
m/s	meters per second
m/s ²	meters per second squared
mbar	millibar (used for pressure)
mm	millimetres
Ω	Ohm
km ²	square kilometers
m ²	square meters
Symbol	Definition
≥	equal or greater than
≤	equal or less than
>	greater than
H:V	horizontal to vertical (used for slope angle)
<	less than
%	percent

1.0 OBJECTIVE

The objective of this Operations, Maintenance and Surveillance (OMS) Manual is to provide procedures for the operation, maintenance and surveillance of all dams associated with Tailings Containment Areas and the existing water treatment system at the Giant Mine, Yellowknife, Northwest Territories. Surface water dams, which are not associated with the Tailings Containment Areas, are also included in this document.

This document is not intended to provide design parameters or calculations. Reference should be made to the technical documents listed in this OMS Manual for details of design parameters and calculations.

2.0 DOCUMENT USER GUIDE

This document is organized as follows:

1) Section 3.0 – Roles and Responsibilities

Provides the organization structure for the management of Giant Mine along with named individuals, their responsibilities, and training requirements.

2) Section 4.0 – Site and Facilities Description

Provides an overview of the facilities at the Giant Mine including dam consequence classifications. Additional details, including dam history and construction details, are presented in Appendix B.

3) Section 5.0 – Site Reference Data

Provides reference data used at Giant Mine including regulatory requirements, relevant operating manuals, grid system, and compliance points.

4) Section 6.0 – Site Conditions

Provides a brief description of site conditions. Detailed climate data is presented in Appendix D Water balance information and typical water flow at the site facilities are presented in Appendix E

5) Section 7.0 – Operations

Provides details on how the facilities should be operated including the following:

- Water management and treatment requirements.
- Storage capacity of facility ponds.
- Maximum permissible pond water levels, and warning levels.

6) Section 8.0 – Surveillance

Provides surveillance requirements for the facilities including the following:

- Procedures for visual inspection, how often these should be conducted, and by whom. Standard inspection forms are provided in Appendix F.
- Procedures for reading geotechnical instrumentation, how often these should be read, and the establishment of warning levels.
- Requirements for sampling and testing as per water licence requirements.
- Requirements for conducting topographic and bathymetric surveys.
- Requirements for conducting annual dam inspections and required frequency for dam safety reviews (DSR).

7) Section 9.0 – Maintenance

Provides requirements for routine and preventive maintenance activities.

8) Section 10.0 – Emergency Preparedness and Response Plan (EPRP)

Provides procedures for identifying, preparing for, and responding to an on-site dam emergency, including the following:

- Identification of determined warning levels, and specific actions to be implemented should these levels be reached.
- Emergency contacts and call-out procedures.
- Preventative and remedial responses to incidents.
- Identification of possible resources to assist with incidents.

The update of this OMS is a shared responsibility between Parsons (i.e., Main Construction Manager) and WSP (i.e., Geotechnical Consultant). The specific updating responsibility of each individual section is presented in Appendix A.

3.0 ROLES AND RESPONSIBILITIES

3.1 Organization Chart

An organization chart identifying the organizations and individuals involved with the management of Giant Mine Tailings Containment Areas (TCAs) and surface water dams, and the chain of command is presented in Figure 1. Key staff for the owner, remediation contractor, subcontractors and external advisors are included.




Figure 1: Giant Mine Chain of Command

3.2 Responsibilities and Contact Information of Formally Assigned Individuals

The responsibilities and contact information of individuals with formally assigned roles in the operation, maintenance, and surveillance of the Giant Mine TCAs and Surface Water Dams are defined in Table 1.

Table 1: Individual's Responsibilities

Role		Name	Company	Responsibilities	Contact Numbers
Site Owner	Deputy Director	Natalie Plato	CIRNAC	Be available for consultation. Public relations communication. Awareness of their role in OMS Manual and EPRP.	Office: 867.669.2838 Mobile: 867.445.6499
	Engineering Manager	Miguel Larivière	CIRNAC	Be available for consultation. Public relations communication. Awareness of their role in OMS Manual and EPRP.	Office: 867.669.2435 Mobile: 867.444.9400
	Project Managers	Bradley Mueller	PSPC	Administration and management of contracts on behalf of CIRNAC, as it relates to Parsons. Awareness of their role in OMS Manual and EPRP.	Office: 867.766.8361 Mobile: 867.444.9282
		Carlos Philipovsky	PSPC	Administration and management of contracts on behalf of CIRNAC, as it relates to Parsons. Awareness of their role in OMS Manual and EPRP.	Office: 867.766.8304 Mobile: 867.445.3570
		Todd Rosadiuk	PSPC	Administration and management of contracts on behalf of CIRNAC, as it relates to Parsons. Awareness of their role in OMS Manual and EPRP.	Mobile: 780.267.9482
Main Construction Manager (MCM)	Mine Manager (TCA Responsible Person)	Doug Hayes	Parsons	Assist with routine and event-driven/special maintenance and inspections as outlined by this OMS Manual. TCA Responsible person. Awareness of their central role in OMS Manual and EPRP.	Office: 867.669.3715 Mobile: 867.688.1036 780.207.5259
	Environmental Manager	Reuben Makohoniuk	Parsons	Be available for consultation. Complete inspections, as assigned by the Mine Manager.	Office: 867.669.3725 Mobile: 603.818.8184
	Safety and Security Manager	Trever Amendt	Parsons	Be available for consultation. Awareness of their role in OMS Manual and EPRP.	Office: 867.669.3719
Surface Care and Maintenance Subcontractor	Project Manager	Robert Stewart	Forward	Be available for consultation.	Office: 867.444.8397 rstewart@outcomeinc.ca
	Superintendent	Morgan Perry	Forward	General observations weekly and scheduling. Complete weekly inspections, as assigned by the Mine Manager.	Office: 867.876.0255 mperry@forwardmining.ca
	Civil Technician (Surveyor)	Geadion Nyanzi	Forward	Complete routine surveying of dams and pond levels. Complete weekly inspections, as assigned by the Mine Manager.	Mobile: 437.868.0551
Effluent Treatment Plant Subcontractor	Supervisor	Derek White	BluMetric	Operation of the Effluent Treatment Plant on a seasonal basis	Mobile: 877.487.8436x330

Table 1: Individual's Responsibilities

Role		Name	Company	Responsibilities	Contact Numbers
Underground Care and Maintenance Subcontractor	Supervisor	Mardie Graham	Procon	Awareness of OMS Manual and their role in EPRP.	Mobile: 867.446.8885 mgraham@procongroup.com
	Supervisor	Walter Walker	Procon	Awareness of OMS Manual and their role in EPRP.	Office: 867.669.3717 Mobile: 867.445.3302
Site Security Subcontractor	Supervisor	Yaser Shakh	Scarlet Security	Be available for consultation. Complete routine security inspections of the dams, as assigned by the Mine Manager. Awareness of their role in EPRP.	Office: 867.873.3202 (ext. 401) Mobile: 867.222.3814
EOR Firm	EOR	Hung Vu	WSP	Be available for consultation, complete Annual Geotechnical Inspection (AGI) of Dams, participate in dam safety reviews, and risk assessments. Awareness of their role in the OMS Manual and EPRP.	Mobile: 306.260.4018
	Deputy EOR	Jason Song	WSP	Be available for consultation. Awareness of their role in the OMS Manual and EPRP.	Mobile: 403.479.6750
	Senior Advisor, Geotechnical and Hydrogeology	Mike Tremblay	WSP	Be available for consultation. Awareness of their role in the OMS Manual and EPRP.	Mobile: 306.222.1874
	Senior Advisor, Hydrology	Julien Lacrampe	WSP	Be available for consultation. Awareness of their role in the OMS Manual and EPRP.	Mobile: 780.913.4749
	Geotechnical Specialist	Ryan Downey	WSP	Review of routine instrumentation monitoring and surveying data.	Mobile: 306.914.7726
	Project Manager	Jacob Chan	WSP	Administration and management of contracts on behalf of WSP, as it relates to PSPC.	Mobile: 368.882.1132

3.3 Requirements for Competency and Training

Table 2 summarizes the minimum knowledge, competency, and training requirements for personnel involved in the operation, maintenance, and surveillance of the Giant Mine TCAs and Surface Water Dams.

The role of the TCA Responsible Person has been delegated to the Mine Manager by the Site Owner. Within the OMS Manual and EPRP, the title of Mine Manager is used as it is the common terminology used at Giant Mine. Due to the Mine Manager's workload, many of the routine tasks (e.g., weekly inspections, dam operations) have been delegated to Site Technical Staff (Parsons and Forward Mining staff).

WSP has been retained to provide Engineer of Record (EOR) services for tailings containment areas and surface water dams at the Giant Mine for 2024. Hung Vu, P.Eng., and Jason Song, P.Eng. will serve as EOR and deputy EOR, respectively.

Table 2: Required Proficiencies and Training

Roles	Minimum Knowledge and Competency Requirements	Training
Mine Manager (TCA Responsible Person)	- Detailed understanding of the responsibilities related to the dams, their safety, and applicable regulations. - An understanding of the significance of hazard and risk. - Detailed understanding of Giant Mine TCAs and B2 Dam operations, maintenance, and surveillance procedures in relation to OMS Manual. - Detailed understanding of EPRP in relation to the Giant Mine TCAs and B2 Dam. - Detailed understanding of regulatory requirements for various regulatory bodies in relation to AGIs and DSRs. - Understanding of dam design principles and construction techniques. - Understanding of abnormal and noncompliance conditions and protocol.	- OMS Manual - EPRP - Existing AGI reports - Existing DSR reports
Site Technical Staff (e.g., Parsons and Forward staff)	- Detailed understanding of Giant Mine TCAs and B2 Dam operations, maintenance, and surveillance procedures in relation to OMS Manual. - Detailed understanding of EPRP in relation to the Giant Mine TCAs and B2 Dam. - Understanding of dam design principles and construction techniques. - Understanding of abnormal and noncompliance conditions and protocol.	- OMS Manual - EPRP
Engineer of Record	- Experience commensurate with the consequence classification and complexity of the facility. - Registration as Professional Engineer in the Northwest Territories. - Has or is employed by a firm that holds a permit to practice engineering in the Northwest Territories. - Detailed understanding of dam safety regulatory responsibilities. - Detailed understanding of design, construction history, as well as applicable standards, criteria, and guidelines.	- OMS Manual - EPRP - Dam engineering - Applicable guidelines and regulations

Table 2: Required Proficiencies and Training

Roles	Minimum Knowledge and Competency Requirements	Training
PSPC and Forward Employees	- Understanding of contents of the OMS Manual. - Knowledge of specific risks as they apply to work areas in and around the pond.	OMS Manual
CIRNAC (Site Owner)	- Accountable for decisions related to management of TCAs and dams. - Needs to be aware of key outcomes of how risks are being managed. - Accountable and responsible for putting in place an appropriate management structure. - Assigns responsibility and appropriate budgetary authority for management of TCAs and dams.	- OMS Manual - EPRP - Applicable guidelines and regulations
Subcontractors	Knowledge of specific risks as they apply to work areas in and around the pond.	
External Consultants	Experience with specific role relevant to the Giant TCAs and Surface Water Dams.	- OMS Manual - EPRP

Note: OMS = Operation, Maintenance, and Surveillance; EPRP = emergency preparedness and response plan; AGI = Annual Geotechnical Inspection of Dams; DSR = dam safety review; TCA = tailings containment area.

3.4 Site Personnel

Typically, a total of 50 to 200 employees may be on site at any time. Roughly 50 people are full-time employees based on site year-round of which up to 12 are Parsons' staff. The remaining 150 employees are made up of employees that would work for one of the several subcontractors or consultants, and the exact number varies over time.

Employees and visitors to site must report to the site office located at the C-Dry building for check-in. There is a sign-in sheet and a tag-in board at C-Dry. The tag-in board uses photographic identification cards to monitor personnel present on site.

3.5 Responsibilities for Managing Change

The annual inspection of the facilities may identify needs for updates to the operation, maintenance, or surveillance of the facilities on site. The Mine Manager and Site Owner's MCM may also identify needs during the year.

The OMS Manual and all associated documents will be kept current with appropriate practices and procedures. It will be reviewed annually, at a minimum, by the required personnel (see the review protocol of the Signature Page). The Mine Manager will be responsible for ensuring that changes to the facility or within the management structure are reflected in the OMS Manual, approved, and distributed accordingly.

4.0 SITE AND FACILITIES DESCRIPTION

4.1 Site Overview

Giant Mine is an abandoned open pit and underground gold mine located within the City of Yellowknife boundary, approximately 1.5 kilometres (km) from the community of Ndilo and 9 km from the community of Dettah in the Northwest Territories. The mine has had several owners and operators since the first mining stakes were claimed in 1935 (Silke 2009).

The first tailings-retaining facility constructed at the site was the Original Tailings Containment Area (Original TCA), located to the northeast of the mill. Tailings were deposited within the Original TCA up until the late 1980s. Figure 2 shows the approximate footprints of the Original and Northwest TCAs.

Additional tailings storage was required and in 1988 construction of the Northwest Tailings Containment Area (Northwest TCA) was completed. Since 1988, the majority of the tailings were deposited in the Northwest TCA. Tailings production at the site ceased in 1999.

The main surface water features of the site are Yellowknife Bay and Baker Creek. Baker Creek, shown in Figure 2, generally runs from north to south, and is located to the west of the Original and Northwest TCAs.

Yellowknife Bay is located to the east of the site. In order to mine the B2 Pit (also known as Under Baker Creek Pit or UBC Pit), Baker Creek was diverted to its current location by the construction of the B2 Dam. Figure 2 shows the location of B2 Dam.

The Mill Pond is located west of C-Dry and east of Baker Creek. In the current stage, the Mill Pond retains surface runoff from the Developed Areas (e.g., C-Dry, Mill/Roaster Area). The retained water in the Mill Pond will be pumped to the Central Pond, then flowing to the North Pond.

According to the Canadian Dam Association (CDA) (2013) definition, Giant Mine is in the Closure-Active Care phase of the mine life. In the context of the site's Closure and Reclamation Plan (CRP), the site is currently in care and maintenance and active remediation started July 2021 (CIRNAC and GNWT 2021). The only operations at the facility are related to the management of surface water and water treatment on an annual basis which includes the use of the Northwest TCA, Original TCA, Mill Pond Structure, and B2 Dam and ongoing site remediation activities.

Additional minor dams on site are used on a temporary or seasonal basis and, as such, are not part of the overall management of the Giant Mine TCAs or year-round surface water management. These minor dams, shown in Figure 2, include the following:

- M&M Dam
- DWC Dam
- C1 Clay Borrow Dam

Additional details on the background, history, and construction of the individual dams are provided in Appendix B.




Figure 2: Overview of Giant Mine

4.2 Tailings Transportation and Deposition

During milling, the Giant Mine tailings were transported via pipeline as a slurry (mixture of crushed rock and water) and discharged from spigots located at the perimeter dams. Up until the mid-1970s deposition of tailings was considered to be inefficient during the winter months, as the cold climate and shallow depth of water in the TCAs resulted in ineffective sedimentation of solids and the formation of ice lenses (Geocon 1975). From about 1980, the depositional strategy relied upon having deeper water within the TCAs during the winter such that tailings could settle below ice, reducing the occurrence of ice lenses (Geocon 1975).

4.3 Access Roads and Security

Current access to the site from Yellowknife city centre is via a 5 km paved road, which is on GNWT Commissioner's Land. The access is along the former Northwest Territories' Highway 4 (aka Old Ingraham Trail). The old highway and haul roads remain serviceable and are accessible using light vehicles.

Site access is currently restricted to site personnel and approved individuals/companies with site clearance. The site has 24-hour security located at the entrance gate to Giant Mine. No parking will be available on-site for private vehicles effective April 1, 2023. Parsons is progressing to having a Radio Frequency Identification (RFID) system available for site-access.

4.4 Dam Consequence Classification

All dams have been assigned consequence classifications based on CDA (2013) guidelines. Dam classifications are a key factor in the assessment of dam monitoring needs. There are a total of 23 dams at the site that have a dam consequence classification between low and very high (Golder 2022a). There are no dams with the extreme classification.

Figure 3 shows the location of the Original TCA dams and Figure 4 shows the location of the Northwest TCA dams. For the locations of B2 Dam, Mill Pond Structure, and other surface water management dams, refer to Figure 2.

Table 3 provides a summary of the dam consequence classification for the dams at Giant Mine according to CDA (2013) guidelines. There are nine dams with a classification of very high to high and 14 dams with a classification of significant to low. Refer to Appendix C for a summary of the rationale supporting the current dam classifications.

Table 3: Summary of Dam Consequence Classifications

CDA (2013) Consequence Classification	Original TCA Dams	Northwest TCA Dams	Other Dams	Total Number
Very High	-	▪ Dam 21A ▪ Dam 21B ▪ Dam 21C	▪ B2 Dam	4
High	▪ Dam 1 ▪ Dam 2	▪ Dam 21D ▪ Dam 22A ▪ Dam 22B	-	5
Significant	▪ Dam 3 ▪ Dam 11	-	▪ Mill Pond Structure	3
Low	▪ Dam 3C & 3D ▪ Dam 4 ▪ Dam 5 ▪ Dyke 6 ▪ Dam 7 ▪ Dam 8 ▪ Dam 9 ▪ Dam 12 ▪ Splitter Dyke	-	▪ DWC Dam ▪ C1 Clay Borrow Dam	12
Not Applicable	▪ Dam 10	-	▪ M&M Dam	2

Source: Golder (2022a).

Note: - = no data (implies that no dams are currently classified).

Dam 10 and M&M Dam are no longer classified as dams following the 2019 Dam Safety Review (DSR) and 2020 Annual Geotechnical Inspection (AGI) (SRK 2020; Golder 2021a). The M&M Dam is monitored as a flood dyke.

Consequence classifications of four Original TCA dams (Dam 1, Dam 2, Dam 3, and Dam 11) and six Northwest TCA dams (Dams 21A through 21D, Dam 22A, and Dam 22B) are based on the results of Dam Breach Analysis (DBA). All other dam consequence classifications are based on high-level desktop reviews.




Figure 3: Overview of Original TCA Dams at Giant Mine




Figure 4: Overview of Northwest TCA Dams at Giant Mine

5.0 SITE REFERENCE DATA

5.1 Applicable Guidance and Regulatory Requirements

Applicable codes, guidelines, and regulations governing the Giant Mine TCAs and Surface Water Dams are listed below.

- Canadian Dam Association (CDA) Dam Safety Guidelines (2013 Edition) (CDA 2013)
- CDA Bulletin Application of Dam Safety Guidelines to Mining Dams (2019 Edition) (CDA 2019)
- CDA Technical Bulletin: Dam Safety Reviews (CDA 2016)
- Mining Association of Canada Guidelines (MAC 2021a, b)
- Mackenzie Valley Land and Water Board (MVLWB): Type A Water Licence (MV2007L8-0031) issued to Crown-Indigenous Relations and Northern Affairs Canada (CIRNAC) – Giant Mine Remediation Project (MVLWB 2021)

In addition, the Giant Mine Remediation Project, Water Management and Monitoring Plan. Version 4.0 (CIRNAC and GNWT 2023) is consulted for mine water and surface water management at the Site.

5.2 Mine Operating Manuals

Applicable Standard Operating Procedure (SOP) and operating manual in use at the Giant Mine:

- SOP# - ETP – 01: Giant Mine ETP Operating Manual – 2008 (Deton'Cho / Nuna 2008)
- SOP Ice Buildup and Freshet Management (Parsons 2022)

5.3 Coordinate System and Maps

The coordinate system at site is called the Giant Mine Remediation Project (GMRP) grid. This coordinate system is a truncated version of the UTM Zone 11, NAD83. In the GMRP coordinate system, elevations are referenced to mean sea level.

Details of the coordinate system used are provided in Ollerhead Ltd (2006). For reference, the following conversions are applicable when using the GMRP grid.

- To convert from UTM Zone 11, NAD83 (meters) to GMRP (metres)
 - Northings: $NGMRP = (NUTM \div 0.9998013) - 6901377.963$
 - Eastings: $EGMRP = (NUTM \div 0.9998013) - 600126.430$
- To convert from GMRP (meters) to UTM Zone 11, NAD83 (meters)
 - Northings: $NUTM = (NGMRP \times 0.9998013) + 6900006.660$
 - Eastings: $EUTM = (EGMRP \times 0.9998013) + 600007.182$

5.4 Regulatory Framework for Dam Safety

The Giant Mine is permitted under Type A Water Licence MV2007L8-0031. Overall, the Water Licence requires that:

...all structures intended to contain, withhold, divert, or retain Water or Wastes and which meet the definition of a Dam under the [CDA] Dam Safety Guidelines, are designed, constructed, maintained, and monitored to meet or exceed the [CDA] Dam Safety Guidelines.

Other specific requirements of Water Licence MV2007L8-0031 relevant to the OMS Manual include the following:

- The completion of an AGI during the summer months by a Professional Engineer. An AGI report must also be submitted to the MVLWB within 120 days of the completion of the AGI site visit.
- That DSRs be conducted of all structures that contain water or wastes, in accordance with the CDA (2013) Dam Safety Guidelines.

The CDA (2013) Dam Safety Guidelines recommend that a DSR be conducted every five to 10 years depending on the consequence of dam failure, as shown in Table 4. A DSR was completed in 2019 (SRK 2020), so the next DSR would be initiated sometime between 2024 and 2029, depending on the dam consequence classification.

Table 4: Frequency for Dam Safety Reviews

Dam Consequence Classification	Frequency	Dam ID
Extreme	Every five years	None
Very High	Every five years	B2 Dam, Dam 21A, 21B, 21C
High	Every seven years	Dam 1, 2, 21D, 22A, 22B
Significant	Every 10 years	Dam 3, Dam 11, Mill Pond Structure
Low	See note ⁽¹⁾	Dam 3C, 3D, 4, 5, 7, 8, 9, 12, Dyke 6, Splitter Dyke, DWC Dam, C1 Clay Borrow Dam

Notes: Dam 10 and M&M Dam do not have a consequence classification.

(1) A Dam Safety Review is not required for low-consequence dams. However, the consequences of failure should be reviewed periodically since they may change with downstream development. If the classification increases, a Dam Safety Review is required at that time.

6.0 SITE CONDITIONS

6.1 Topography

The Giant Mine site consists of undulating topography, with a central valley containing Baker Creek and Trapper Creek. Extensive areas of exposed bedrock are present on the higher ground, as well as minor surficial deposits in low-lying areas. The ridges on either side of Baker Creek are 10 to 20 m high and the slope angles are bedrock controlled. There is a thin layer of soil on most of the ridge slopes. Mining activity in the Baker Creek Valley has significantly altered the local topography and portions of the Baker Creek channel have been relocated several times throughout the history of operations.

6.2 Geology

The area around Giant Mine is composed mainly of mafic volcanic rocks (basalt and andesite) and intrusive equivalents (gabbro and diorite), known collectively as the Kam Group (John 1991).

The area was glaciated during the Pleistocene period resulting in outwash sand and gravel plains, eskers, and glacial lacustrine clays in the valleys. Bedrock is of Precambrian origin and consists predominantly of greywacke, slate, quartzite, arkose, argillite, and phyllite.

In general terms, sub-ground conditions are characterized by (after Geocon 1975):

- stratum of organics in the form of either muskeg, peat, or organic silt; over
- silty clay and, in some areas, followed by a stratum of silt with sand sometimes with trace clay; over
- a veneer of silty or sandy till; over
- bedrock.

6.3 Vegetation and Wildlife

The vegetation in the region is typical of the Taiga Shield Ecozone with its plains and hills of the Canadian Shield. The site contains stunted coniferous and deciduous stands, including black spruce, alders, willows, and tamarack in the fens and bogs and open, mixed woods of white spruce, balsam fir, and trembling aspen (after McGill 2017).

Wildlife of the Taiga Shield Ecozone includes barren-ground and some woodland caribou, moose, wolf, snowshoe hare, arctic fox as well as black and grizzly bear.

Representative bird species include arctic and red-throated loons, northern phalarope, tree sparrow, and grey-cheeked thrush.

6.4 Climate

Summary of climate information for the Giant Mine is presented here. For additional details see Appendix D.

- Climate data relevant to the Giant Mine area are available from the Environment Canada climate station at Yellowknife Airport (Station ID 2204101)
- The mean annual temperature is -4.7 degrees Celsius
 - The coldest month is typically January, with a mean temperature of -26.7 degrees Celsius.
 - The warmest month is typically July, with a mean temperature of 16.6 degrees Celsius.

- The annual total precipitation is 348 mm, including approximately 182 mm of rainfall and 166 mm of water equivalent snowfall.
 - The wettest month is August with approximately 46 mm of total precipitation.
 - The driest month is February with approximately 0 mm of total precipitation.
- The probable maximum precipitation for a 24-hour event (point PMP) is 328 mm.
 - Snowmelt typically occurs between March to May.
 - The mean annual lake evaporation is 397 mm.
- The prevailing winds are from the east.

6.5 Water Balance

Water balance models for the North Pond (which also collects surface water from the former South and Central Ponds) and Northwest Pond are presented in Appendix E.

These water balances provide average expected conditions for the North and Northwest Ponds.

The water balance for the Polishing and Settling Ponds is predominantly controlled by surface water treatment (inflows and outflows). A separate water balance has not been calculated for these ponds. Flows are tracked to the Effluent Treatment Plant (ETP) (from the Northwest Pond) and from the Polishing Pond to Baker Creek.

6.6 Permafrost

Recent and historical site investigations confirmed the presence of frozen ground beneath multiple dams on site. This frozen ground may be defined as permafrost depending on the ground temperature and the duration of sustained temperatures. Within this section, relevant permafrost definitions and an overview of known permafrost conditions at Giant Mine dams is provided.

Permafrost definitions relevant to the OMS include the following:

- **Permafrost:** where the ground temperature is at or below zero degrees Celsius during at least two consecutive winters and the intervening summer (Andersland and Ladanvi 2004).
- **Discontinuous permafrost:** which occurs when permafrost is present only in certain areas and covers less than 90 percent but more than 50 percent of the ground area.
- **Warm permafrost:** where ground temperatures are in the range of zero to -1 degrees Celsius (Geological Survey of Canada 1998).
- **Low salinity permafrost:** where the pore fluid contains salt (i.e., solids that are soluble in water) with a concentration of less than five parts per thousand (Hivon and Sego 1993).

Giant Mine is located within the discontinuous permafrost zone (Geological Survey of Canada 1998). Where encountered, in and around Yellowknife, it is typically warm and found in peat bogs where organic material contributed to and preserved the permafrost.

Geotechnical investigations completed between 2018 and 2020 encountered frozen ground beneath multiple dams on site. Subsequent ground temperature monitoring confirmed permafrost conditions. Dam specific summaries are provided below.

- **Dam 1:** Permafrost is located in the dam's foundation and ranges from zones of near total ice with very little soil, to frozen soil with minimal to no visible ice (Golder 2019). The permafrost was encountered mostly in a layer of silty clay. Measured ground temperatures in the permafrost zone have ranged between -0.1 to -0.3 degrees Celsius (Golder 2021b), which has been classified as warm permafrost. The salinity of the permafrost was found to be low, so although the permafrost is warm, much of the water is likely in a frozen state. In 2020, 38 passive thermosyphons were installed to reduce the temperature of the permafrost in key foundation locations (Golder 2021b).
- **Northwest TCA Dams** (Golder 2020b): Frozen soil was encountered at all dam foundations during a geotechnical investigation of the perimeter dams conducted in 2019. Measured ground temperatures typically ranged between -1 to -4 degrees Celsius in the frozen soil zones.
- **Mill Pond Structure** (Golder 2022d): Frozen soil conditions were observed in the central portion of the Mill Pond Structure, as well as in the downstream side near the south end of the structure. The frozen soils in the downstream side were observed to be deeper and less ice-rich than those in the central portion of the structure. The frozen soils were located within the native silty clay and described as containing ice lenses and layers of ice and soil with 50 percent or more ice by volume. An assessment based on the ice content of the frozen soils estimated that the equivalent ice thickness was up to 3 m at the borehole locations (WSP 2024a).

Site-specific data on the presence and extent of frozen soil in the foundations of dams and within the TCA boundaries, where encountered during geotechnical investigations, are provided in Appendix B.

6.7 Seismicity

According to the 2020 National Building Code of Canada seismic hazard calculator (NRC 2020), the values of peak ground acceleration (PGA) that is expressed as a ratio of gravitational acceleration (i.e., g) for the Giant Mine site are as follows:

- 1) 0.034 g for the 1-in-1,000-year event (five percent probability of exceedance 50 years).
- 2) 0.067 g for the 1-in-2,475-year event (two percent probability of exceedance in 50 years).

These PGA values were based on Site Class E conditions which were considered conservative due to the presence of near surface bedrock and rockfill material.

7.0 OPERATIONS

The Giant Mine is in the Closure-Active Care phase of the mine life. The only operations at the facility are related to the management of surface water and water treatment on an annual basis and ongoing closure and reclamation activities. The water management procedures are outline in the Water MMP (CIRNAC and GNWT 2023).

Water management and treatment structures at the site, as shown in Figure 5, include the following:

- Northwest TCA, in which Dam 22B has the lowest minimum crest elevation of the low permeability element and therefore controls water levels in the Northwest Pond.
- Original TCA, in which only the following dams retain water:
 - Splitter Dyke retains water in the Settling Pond.
 - Dam 1 retains water in the Polishing Pond.
 - Dam 2 retains water in the North Pond.
- B2 Dam diverts water in Baker Creek away from B2 Pit.
- Mill Pond Structure retains water in the Mill Pond.

Approximate total areas for combined tailings and water surface within the TCA ponds (excluding dams) are as follows (SRK 2005, WSP 2024a):

- Northwest Pond: 44 ha
- North Pond: 29 ha
- Central Pond: 13 ha
- South Pond: 9 ha
- Settling Pond: 4 ha
- Polishing Pond: 5 ha
- Mill Pond: 2 ha




Figure 5: Overview of Water Management Facilities at Giant Mine

7.1 Water Management

The following activities make up water management of the Giant Mine site:

- Water from the underground mine is pumped to the Northwest Pond for storage.
- Surface water runoff and direct precipitation are collected in the Northwest Pond.
- Surface water runoff and direct precipitation from the South and Central Ponds (which no longer retain a significant quantity of ponded surface water) flow by gravity to the North Pond where it is collected along with runoff and direct precipitation in the North Pond.
- Surface water runoff (contact water) is collected in the main building area around C-Shaft and conveyed to the Mill Pond. Water from the clay borrow area is also collected and conveyed to the Mill Pond. Mill Pond water is conveyed to the Central Pond.
- If required (i.e., storage volume reached) water from the North Pond is pumped to the Northwest Pond or treated directly at ETP.
- By mid to late June the Northwest Pond is normally near its storage capacity and water is pumped from the pond to the ETP for treatment.
- Following treatment, water is discharged into the Settling Pond, and then pumped to the Polishing Pond. Retention time within these ponds is controlled based on maintaining surface water levels within the Settling and Polishing Ponds (as presented in Section 7.6).
- Once discharge criteria are met, water is discharged via a siphon from the Polishing Pond to Baker Creek.
- Water flow in Baker Creek is diverted by B2 Dam, which prevents Baker Creek flow from entering into the B2 Pit.
- By the end of September, and termination of water treatment, the water elevation in the ponds is generally at their lowest.

An illustration of surface water management is presented in Figure 6. Emergency pumping requirements are as follows:

- High water volume in the Northwest Pond will be managed by pumping water from the pond into the Northwest Shaft and into the mine pool below 750 Level.
- Pond water level differential between the Polishing Pond and Settling Pond will be eliminated to mitigate the risk of Splitter Dyke failure. If this is not achievable (because current sludge elevation along the toe of the Splitter Dyke is higher than the current water level in the Polishing Pond), Settling Pond water level adjacent to the Splitter Dyke will be maintained as low as practicably possible.
- Water levels in the Settling Pond and Polishing Pond should be monitored daily during ETP operation. The Splitter Dyke should be visually inspected daily if zero pond level differential cannot be maintained.
- Parsons will increase the frequency of visual inspection of the Splitter Dyke to twice daily if the ETP is operated at increased pond level differential, higher than 0.2 m (Parsons RFI No.: RFI-0052-0001 Rev0).
- Water levels in the Mill Pond have been set to remain below the lowest interpreted elevation of the low permeability element in the structure.




Figure 6: Overview of Water Treatment at Giant Mine

7.2 Water Treatment

The Giant Mine ETP Operating Manual (i.e., SOP# - ETP – 01) must be consulted for details of operational practices for water treatment.

7.3 Pond Storage Capacity

Only the Northwest, North, Settling, and Polishing Ponds retain ponded water. Estimates of storage capacity with respect to elevation are presented here and are based on available topographic data. Comments in the tables denote the estimated total pond volume at the maximum permissible pond elevation and the point of overtopping (i.e., minimum elevation of the top of the low permeability element). Storage volumes should be verified as per the frequency presented in Section 8.7.

- The storage volume versus water elevation of Northwest Pond is shown in Table 5 and Figure 7.
- The storage volume versus water elevation of North Pond is shown in Table 6 and Figure 8.
- The storage volume versus water elevation of Polishing Pond and Settling Pond is shown in Table 7 and Figure 9.

The water level differential between the Polishing Pond and Settling Pond has been updated to maintain as low as practically possible. The storage volume was re-evaluated for the combined Polishing Pond and Settling Pond.

Discussion of the freeboard levels in each facility are provided in Section 7.5.

Table 5: Storage Volume with Water Elevation Data – Northwest Pond

Water Elevation (masl)	Approximate Pond Volume ⁽¹⁾ (m ³)
186.9	0
187.5	84
188.0	335
188.5	851
189.0	3,377
189.5	11,764
190.0	27,918
190.5	55,805
191.0	106,032
191.5	180,896
192.0	292,370
192.5	436,416
193.0	607,989
193.35 ⁽²⁾	740,671
193.5	800,837
194.0	1,012,532
194.25 ⁽³⁾	1,120,000

(1) Bathymetry survey conducted in 2019 (Golder 2020a).

(2) Maximum permissible pond elevation (minimum freeboard). Pond volume based on linear interpolation of 2019 bathymetry data.

(3) Minimum crest elevation of low permeability element at Dam 22 (Golder 2013). Pond volume estimated based on linear extrapolation of staged storage curve in Golder (2020a).


**Figure 7: Water Elevation Versus Storage Volume – Northwest Pond**

Table 6: Storage Volume with Water Elevation Data – North Pond

Water Elevation (masl)	Approximate Pond Volume ^(1,2) (m ³)
169.4	0
170.0	86
171.0	920
172.0	8,696
173.0	30,568
174.0	63,264
175.0	112,760
176.0	202,260
176.5	264,747 ⁽³⁾
177.0	327,234
178.0	465,298
179.0	611,228
180.0	764,975
180.03 ⁽⁴⁾	769,695
181.0	926,043
181.23 ⁽⁵⁾	959,910

- (1) Bathymetry survey conducted in 2019 (Golder 2020a).
 (2) Volumes shown were linearly interpolated from 2019 bathymetry survey (Golder 2020a).
 (3) Maximum effective volume if Polishing Pond is at maximum permissible pond elevation.
 (4) Minimum freeboard of Dam 2.
 (5) Minimum crest elevation of low permeability element (e.g., spill point).


**Figure 8: Water Elevation Versus Storage Volume – North Pond**

Table 7: Storage Volume with Water Elevation Data – Polishing Pond and Settling Pond

Water Elevation (masl)	Approximate Pond Volume (m³)
163.5	0
163.9	17
164.3	98
164.7	406
165.1	1,378
165.5	2,971
165.9	5,000
166.3	7,383
166.7	10,084
167.1	13,056
167.5	16,273
167.9	19,742
168.3	23,467
168.7	27,549
169.1	32,050
169.5	37,347
169.9	43,807
170.3	51,074
170.7	58,930
171.1	67,337
171.5	76,356
171.9	86,195
172.3	96,924
172.7	108,761
173.1	122,997
173.5	139,855
173.9	158,071
174.2	172,719
174.4	182,754
174.6	196,723
174.8 ⁽¹⁾	211,776
175	227,400
175.2	243,609
175.4	260,284
175.6	277,387
175.8	294,954
176	313,158
176.2 ⁽²⁾	332,076

Source: WSP (2023)

(1) Maximum permissible pond elevation (corresponding to minimum freeboard).

(2) Minimum crest elevation of low permeability element (e.g., spill point).




Figure 9: Water Elevation Versus Storage Volume – Polishing and Settling Ponds

7.4 Flood Runoff Volume

Design hydrographs were analyzed by routing the design intensity-duration-frequency data using the sub-watershed and terrain characteristics for each pond area. It was determined that the spring storm events govern for storage capacity requirements, assuming no active water management operations such as pumping during the events (WSP 2023). Based on the CDA Guidelines (CDA 2013):

- The inflow design flood (IDF) event for Dam 1 (retains Polishing Pond and Settling Pond) and Dam 2 (retains North Pond) are 33% between the 1000-year and the probable maximum flood (PMF) events.
 - The Central and South Ponds discharge into the North Pond and were assessed under the same IDF event to provide total expected runoff volumes for the North Pond.
- The IDF event for the Mill Pond Structure was between the 100-year and 1000-year flood events (i.e., 500-year event).
- The IDF event for Dam 21 (Northwest Pond) is 67% between the 1000-year and the PMF events.

The resulting flood runoff volumes are presented in Table 8.

Table 8: Design Runoff Volume

Location	Governing Storm	Runoff Volume (m ³)	Reference
Northwest Pond	Spring (2/3 between the 1000-year and PMF)	165,500	WSP 2023
North Pond ⁽¹⁾	Spring (1/3 between the 1000-year and PMF)	129,500	WSP 2023
Combined Settling and Polishing Pond		72,000	WSP 2023
Mill Pond Structure Pond	Spring (between 100-year and 1000-year events)	59,900	WSP 2024a

(1) Includes surface water runoff from the South Pond and Central Pond of the Original TCA.

PMF = probably maximum flood.

When B2 Dam was rehabilitated in 2007, it was designed to retain a 1-in-500-year flood event (SRK 2008), which predicted a flow of 25 m³ per second in Baker Creek (NHC 2007). Based on updated flood estimates and a 2018 dam crest survey, the B2 Dam appeared to be able to retain at least a 1-in-1,000-year flood event (Golder 2017a, 2018). B2 Dam was not rehabilitated to retain a PMF flow as the B1 Pit would be flooded before the B2 Dam would be overtopped (SRK 2008).

7.5 Minimum Freeboards

This section details the minimum freeboards established for the water retaining dams. Freeboard is defined here as the vertical distance between the still water level and the top of the impervious core of a dam or dyke. Minimum water freeboards for ponds were calculated based on the PMF inflows presented in Table 8 and the estimated wave runup caused by a 1-in-2-year return event wind acting perpendicular to the dam crest. Freeboard values are calculated using the approach set out in CDA (2013) guidelines.

Pond levels typically fluctuate throughout the year with the minimum pond level typically observed immediately following annual water treatment and the maximum water level observed during the spring freshet.

Minimum freeboards and corresponding water level for the Northwest, North, Settling, and Polishing Ponds, and the Mill Pond are shown in Table 9.

Table 9: Minimum Freeboard and Corresponding Water Levels

Parameter	Northwest Pond	North Pond	Settling Pond and Polishing Pond	Mill Pond	Notes
Minimum freeboard (m)	0.9	1.2	1.4	n/d	Calculated as inflow design flood plus wave runup.
Lowest dam crest elevation (masl)	194.25	181.14	176.40	164.10	Lowest dam crest elevation from available survey.
Lowest elevation of low permeability core (masl)	194.25	181.14	176.20	160.30	Elevation at which water is retained by low permeability core.
Maximum permissible water level (masl)	193.35	179.94	174.80	160.30	Water elevation corresponding to minimum freeboard.

n/d = not designated.

Notes: Dam crest elevation and low permeability core elevation were based on 2022 survey for Northwest Pond and North Pond, and Dam 1 raise construction records for Settling and Polishing Ponds. The Mill Pond lowest crest elevation is based on 2023 as-built survey records and the low permeability element elevation is based on historic borehole records and stratigraphic information (WSP2024a).

The following dams have a minimum freeboard of 1.0 m: Dam 3 to Dam 9, Dam 11, Dam 12, Dyke 6. The minimum freeboard for B2 Dam was estimated to be 0.9 m at the B2 Dam (Golder 2021a). This is based on the minimum estimated top of liner (165.6 m) and the design flood elevation of 164.7 m (1-in-500-year, NHC 2007). Unlike the ponds, the freeboard at B2 Dam does not consider wave height due to its relatively short fetch length.

7.6 Pond Water Levels and Warning Levels

Pond water levels at Giant Mine have restrictions based on one or more of the following:

- Minimum freeboard requirements, as outlined in Section 7.5.
- Differential water level, with the maximum and minimum permissible water levels in one pond dependent on the water level in another pond.
- Rate of water elevation change.

In Section 7.6.1, context for differential water level restrictions is described and the warning levels for both minimum freeboard and differential water elevations is provided. In Section 7.6.2, actions corresponding to warning levels being exceeded are provided. In Section 7.6.3, restrictions for the rate of water elevation change, which is only for the Polishing Pond, is described.

7.6.1 Minimum Freeboard and Differential Water Level

In addition to the freeboard requirements outlined in Section 7.5, maximum and minimum water levels for the North Pond and Settling Pond are also dependent on the water level in the Polishing Pond at any given time. This results in maximum operating levels in these facilities that are necessary to provide the minimum freeboards determined in Section 7.5. These restrictions are based on measures that have been established to control seepage through Dam 2 and minimize the risk of the Splitter Dyke failure.

Three levels of warning have been established for the Giant Mine for management of pond water levels related to minimum freeboard and differential water elevations. The warning levels and their descriptions are provided in Table 10.

Table 10: Warning Level Descriptions – Minimum Freeboard and Pond Differential

Warning Level	Colour Code	Description
Normal		Water reached an elevation or differential that is typical and within historical precedent. No additional monitoring or actions required.
Notification		Water reached an elevation or differential that is greater than is typical, but within historical precedent. Additional monitoring and/or action may be required.
Caution		Water reached an elevation or differential that is greater than the historical precedent. Additional monitoring and/or actions are required.

The selected warning levels for minimum freeboard (i.e., maximum pond elevation) for the Northwest Pond, Polishing Pond, Baker Creek at B2 Dam, and the Mill Pond are presented in Table 11 and visually in Figure 10 to Figure 13. These ponds are controlled by the minimum freeboard requirements and have no differential water level restrictions. For action to respond to the warning levels, refer to Table 13 in Section 7.6.2. If the caution level is exceeded, refer to Table 33, which will require immediate action and may include the implementation of the Emergency Response Plan (ERP).

Table 11: Warning Levels – Pond Water Elevation and Freeboard Criteria

Water Source	Criteria			
	Type (elevation or freeboard)	Normal	Notification	Caution
Polishing Pond	Elevation (masl)	≥ 172.9 to ≤ 174.4	> 174.4 to ≤ 174.7	> 174.7 to ≤ 174.8
	Freeboard (m)	≤ 3.3 to ≥ 1.8	< 1.8 to ≥ 1.5	< 1.5 to ≥ 1.4
Northwest Pond	Elevation (masl)	≥ 189.6 to ≤ 192.4	> 192.4 to ≤ 192.9	> 192.9 to ≤ 193.35
	Freeboard (m)	≤ 4.65 to ≥ 1.85	< 1.85 to ≥ 1.35	< 1.35 to ≥ 0.9
Baker Creek at B2 Dam	Elevation (masl)	≥ 163.4 to ≤ 163.8	> 163.8 to ≤ 164.0	> 164.0 to ≤ 164.7
	Freeboard (m)	≤ 2.2 to ≥ 1.8	< 1.8 to ≥ 1.6	< 1.6 to ≥ 0.9
Mill Pond	Elevation (masl)	n/d	n/d	160.3

n/d = not designated.


The selected warning levels for the North Pond (Dam 2) and the Settling Pond (Splitter Dyke) water level differential, with respect to the water level in the Polishing Pond, are presented in Table 12 and visually illustrated in Figure 14 and Figure 15. For actions to respond to the warning levels, refer to Table 13. If the caution level is exceeded, refer to Table 33, which will require immediate action and may include the implementation of the ERP.

Table 12: Warning Levels - Water Differential Criteria

Water Source	Water Differential Criteria (m)			
	Dam/Dyke	Normal	Notification	Caution
North Pond ⁽¹⁾	Dam 2	≤ 1.0	> 1.0 to ≤ 1.7	> 1.7
Settling Pond ⁽²⁾	Splitter Dyke	0	Not available	Not available

(1) Differential implies that North Pond water elevation is greater than that of the Polishing Pond.

(2) Water level differential between Settling Pond and Polishing Pond shall be maintained as low as practically possible (Golder 2022b).

**Figure 10: Water and Infrastructure Elevations for Northwest Pond (not to scale)**




Figure 11: Water and Infrastructure Elevations for Polishing Pond (not to scale)




Figure 12: Water and Infrastructure Elevations for Baker Creek (not to scale)




Figure 13: Water and Infrastructure Elevations for Mill Pond Structure and Baker Creek (not to scale)




Figure 14: Water and Infrastructure Elevations Dam 2 / North Pond (not to scale)




Figure 15: Water and Infrastructure Elevations for Settling Pond / Splitter Dyke (not to scale)

7.6.2 **Actions Corresponding to Warning Levels**

In Section 7.6.1, warning levels have been established for pond water elevations and differentials. In Table 13, actions that correspond to the exceedance of either the notification or caution warning levels are provided. If the caution warning level is exceeded, refer to Table 33 in Section 10.8. This is a more serious scenario as the ERP may potentially need to be initiated.

Table 13: Actions for Corresponding to Pond Warning Levels

Warning Level	Event Criteria	Actions by Site Technical Staff	Actions by Mine Manager (TCA Responsible Person)	Actions by Site Owner (CIRNAC and PSPC)	Actions by Engineer of Record
Notification	Water Elevations - Water level in Northwest Pond: - Less than or equal to 192.9 m - Greater than 192.4 - Water level in Polishing Pond: - Less than or equal to 174.7 m - Greater than 174.4 m - Water level in Baker Creek at B2 Dam: - Less than or equal to 164.0 m - Greater than 163.8 m Pond Differentials - Dam 2: - Water level in North Pond ≥ Polishing Pond: +1.0 to +1.7 m - Water level in North Pond ≤ Polishing Pond: -1.0 m to -1.7 m - Splitter Dyke - Water level differential between Settling Pond and Polishing Pond shall be maintained as low as practically possible	- Perform and record daily visual inspection. - Measure water levels in North, Polishing, Settling, Mill Pond and Northwest Ponds and determine capacity to receive water. - Set up pumps and pipelines to enable transfer of water from ponds or if not available to underground.	- Notify Engineer of Record for guidance. - Notify Site Owner. - Perform visual inspection. - Be available for consultation. - Be prepared to notify stakeholders and neighboring communities.	Be available for consultation.	Be available for consultation.
	Water Elevations - Water level in Northwest Pond: - Less than or equal to 193.35 m - Greater than 192.9 - Water level in Polishing Pond - Less than or equal to 174.8 m - Greater than 174.7 - Water level in Baker Creek at B2 Dam: - Less than or equal to 164.7 m - Greater than 164.0 m - Water level in Mill Pond - Greater than 160.3 Pond Differentials - Dam 2: - Water level in North Pond ≥ Polishing Pond: >+1.7 m - Water level in North Pond ≤ Polishing Pond: <-1.7 m - Splitter Dyke - Water level differential between Settling Pond and Polishing Pond shall be maintained as low as practically possible	- Perform and record visual inspection. Inspection to be filed as special inspection and separate to routine inspections. - Measure water levels in North, Polishing, Settling, Mill Pond, and Northwest Ponds and determine capacity to receive water. - Set up pumps and pipelines to enable transfer of water from ponds or if not available to underground.	- Notify Engineer of Record for guidance. - Notify Site Owner. - Perform visual inspection. - Be available for consultation. - Be prepared to notify stakeholders and neighboring communities. - Be prepared to evacuate underground.	Be available for consultation.	Be available for consultation.

7.6.3 Rate of Water Elevation Change

No restriction is currently applied for changes in water elevation within the Polishing Pond, North Pond and Northwest Pond.

7.7 Environmental Protection

A monitoring program exists to conduct surface water, groundwater, mine water, and effluent monitoring at the Site. Effluent and water monitoring at the Site, including quality assurance and quality control (QA/QC) measures, is conducted to meet the requirements of the Type A Water Licence MV2007L8-0031 issued by the Mackenzie Valley Land and Water Board (MVLWB 2021), as well as the federal Metal and Diamond Mining Effluent Regulations (MDMER) and the Environmental Effects Monitoring (EEM) program. Additional effluent and water monitoring is completed through the Operational Monitoring Program (OMP). Refer to the Standard Operating Procedures and QA/QC Plan for Effluent and Water Sampling Rev 3.0 (CIRNAC and GNWT 2022).

Operational samples are collected by the ETP operator and submitted to a local lab on a four-hour turn-around-time. These are collected daily, and the results compared to the allowable discharge limits. Monitoring of critical dams is undertaken daily. Visual monitoring for potential dam seepage is undertaken as part of the visual dam inspection. Water bodies adjacent to the dams are visually monitored for turbidity during the visual dam inspection. Any turbidity observed is follow-up with water quality sampling.

7.8 Change Management

The Mine Manager will be responsible for ensuring that any changes in operations or within management are reflected in the OMS Manual and subsequently reviewed, approved, and distributed accordingly. The Parsons' Surface Superintendent will be fully conversant in all requirements of the OMS Manual. Any change in Parsons project personnel will trigger a review of the potential impact on this OMS manual. Any significant change in Parsons personnel or changes in site conditions shall result in an update to the OMS Manual. As the GMRP work progresses all project work that will potentially impact dam conditions shall be informed to the EOR.

7.9 Documentation

The OMS Manual and all associated documents will be kept current with appropriate practices and procedures and, at a minimum, reviewed annually by the required personnel. Electronic copies of the OMS Manual and all inspection reports will be kept on the Parsons SharePoint site.

7.10 Reporting and Documentation

Records of yearly water inputs are to be provided by the water treatment subcontractor to the Mine Manager. Records include the following:

- Water volume discharged to the aquatic environment.
- Volumes of seepage pumped from sumps or other structures.
- Water elevations in the North, Settling, Polishing, Mill Pond, and Northwest Ponds.
- Water volumes pumped from the underground workings.
- Water volumes transferred from the North Pond to the Northwest Pond.
- Water volumes transferred from Dam 3 Sumps A and B, Dam 1 Sump, and Dam 22B Sump.

- Water treated at the ETP.
- Water volumes transferred from the Northwest Pond to ETP.
- Water volumes transferred from the North Pond to ETP.
- Water volumes transferred from the Mill Pond to the Central Pond.
- Water volumes from the ETP to the Settling and Polishing Ponds.
- Water quality sampling results.
- Water volumes collected and transferred from NHL.

Records are to be provided to the Mine Manager for storage at the Giant Mine offices and electronically on a secure server. A summary of data should be provided to the EOR monthly during the ETP operation.

8.0 SURVEILLANCE

8.1 Objectives

A surveillance program is implemented to assess the current performance of the facilities relative to their intended purpose.

The objective of the surveillance program is to confirm adequate performance of the facility, including containment, stability, and operational function, by observing, measuring, and recording data relative to potential failure modes and specific operational controls.

8.2 Training Requirements

No specific training for OMS Manual and EPRP awareness has been completed. The training requirements for the personnel involved in tailings management are listed in Section 3.3. When awareness training is completed, the Mine Manager should document attendees and keep the training records. It will be the responsibility of the Mine Manager to ensure workers new to dam safety management have undergone OMS Manual and EPRP awareness training. Desk top drills related to the EPRP will be conducted on an annual basis.

8.3 Surveillance Procedures

A program of regular periodic surveillance is required to ensure that the facilities are performing adequately and that any problems are detected so that necessary corrective actions can be implemented in a timely manner. The following surveillance procedures will be conducted.

- Visual monitoring by site staff (Section 8.4).
- Reading of geotechnical instruments (Section 8.5).
- Sampling and testing in accordance with the water licence (Section 8.6).
- Survey and bathymetry (Section 8.7).
- Collection of climate data from weather station (Section 8.8).
- Annual Geotechnical Inspections (Section 8.9).
- Dam Safety Reviews to be conducted in accordance with CDA (2013), based on dam classification (Section 8.10).
- Event-driven geotechnical inspections are to be arranged following any extreme weather or seismic events, including extreme wind, rainfall, or earthquakes (Section 8.11).
- Incident-driven inspections are to be arranged to investigate underlying causes of spills, equipment failures or unavailability, or similar incidents that affect the performance of the water management system (Section 8.12).

The Mine Manager is responsible for the implementation of all visits conducted on site.

8.4 Visual Inspection

Routine visual inspections are a key part of the surveillance of the dams. In Section 8.4.1, an overview of the general inspection requirements is provided, such as minimum monitoring frequency and documentation, as well as general guidance on potential key observations for inspectors to be aware of. In Section 8.4.2, specific inspection requirements for monitoring of cracks and the Dam 1 thermosyphon are described.

In Section 8.4.3, warning levels that could be triggered based on observations from the visual inspections are listed, along with corresponding actions are provided.

8.4.1 General Inspection Requirements

Table 14 outlines the different failure modes applicable to the facilities at Giant Mine and visual observations which may indicate potential failure.

Table 14: Failure Modes and Identification

Failure Mode	Conditions Related to Possible Increased Risk of Potential Failure Mode
Overtopping	- high water elevation - blockage of water management structures (culverts, ditches, pumps, pipelines, channels, spillways and diversions) - extreme meteorological event (precipitation, wind, and wave action) - dam settlement, sinkholes - excessive accumulation of solids (e.g., sludge build-up in Settling Pond)
Instability	- cracking - dam settlement - slope movement (as detected by settlement plates and survey monuments) - dam bulging - increase in water levels in the dam (piezometers) - increased seepage - erosion - seismic event
Piping	- sediment laden seepage (e.g., cloudy visual appearance) - wet spots at downstream dam toe or on downstream slope - sinkholes, onset of sudden and new depressions in tailings impoundment

Documented visual monitoring of the dams and facilities will be carried out. Table 15 summarizes the minimum frequency for visual inspection of the dams, organized by their current CDA consequence classification.

Daily inspections may be completed by Site Security or other staff as delegated by the Mine Manager. Weekly inspections are completed by Site Technical Staff (e.g., Environmental Manager, Mine Technician). Monthly inspections are performed by the Mine Manager. Daily, weekly and monthly inspection forms are found in Appendix F.

Table 15: Minimum Visual Inspection Frequencies

CDA Classification	Locations of Dam	Dam Name	Minimum Inspection Frequency		
			Daily	Weekly	Monthly
Very High	Other	B2 Dam	X	X	X
	Northwest TCA	Dam 21A	X	X	X
		Dam 21B	X	X	X
		Dam 21C	X	X	X
High	Original TCA	Dam 1	X	X	X
		Dam 2	X	X	X
	Northwest TCA	Dam 21D	X	X	X
		Dam 22A	X	X	X
		Dam 22B	X	X	X
Significant	Original TCA	Dam 3		X	X
		Dam 11		X	X
	Other	Mill Pond Structure		X	X
Low	Original TCA	Dam 3C		X	X
		Dam 3D		X	X
		Dam 4		X	X
		Dam 5		X	X
		Dyke 6		X	X
		Dam 7		X	X
		Dam 8		X	X
		Dam 9		X	X
		Dam 12		X	X
		Splitter Dyke	X ⁽¹⁾	X	X
	Other	DWC Dam			X
		C1 Clay Borrow Dam			X
Not Applicable	Original TCA	Dam 10			
	Other	M&M Dam ⁽²⁾			

TCA = tailings containment area

(1) Daily inspection during ETP operations if zero differential water elevation is not maintained.

(2) Inspection before and after spring freshet (e.g., in April and late May) and around winter freeze-up (e.g., October).

Documentation required from the inspections includes the completed inspection form and a photographic record. The level of detail required for the inspection of each dam is dependent on the consequence classification and size of the dam (i.e., inspection of very high consequence, large dams should take longer and provide more detail than significant consequence, small dams). The Mine Manager is responsible for ensuring visual inspections are completed and that completed inspections are reviewed.

Should any conditions be identified which indicate a possible increased risk of a potential failure (Table 14) or if a warning level is reached, the Mine Manager and the EOR should be informed immediately.

The results of the following inspections should be forwarded to the EOR within one month of the date they were completed:

- Monthly inspections by Mine Manager
- Weekly inspections at the following times:
 - Last two inspections prior to the onset of freshet.
 - First two inspections following the end of the freshet.
 - Last two inspections prior to the commencement of annual water treatment.
 - All inspections while water treatment is in process.
 - Last two inspections prior to freeze-up.

The Mine Manager and EOR will review the information and may be required to take further action or implement the EPRP (Section 10.0) based on the information provided in the inspections.

All general inspections involve a brief assessment of facilities, dams, and all water management structures. All inspections should cover the tasks noted below. Additional requirements for weekly and monthly inspections are detailed in the forms in Appendix F.

- Observation of water levels, with immediate reporting when warning levels are exceeded.
- Observation of dam crests for any evidence of significant slope instability, cracking, sloughing, or slides.
- Observation of seepage at the downstream toe or on the downstream slope of the dams along with a visual description of the appearance of the seepage (e.g., sediment laden or clear). If seepage appears sediment laden (e.g., cloudy), the Mine Manager and EOR are to be notified immediately.
- Observation of erosion on the dam profile (crest, downstream, and upstream slopes and toes).
- Observation and recording of any deterioration of the access roads; deterioration would include:
 - Any indications of instability (e.g., potholes, slumping, or cracks) in the road or the supporting fills below the road.
 - Any accumulations of debris or other materials on the road or paths.
- Observation of any blocked or eroded water courses.

If seepage is observed through the dams or there are any indications of dam movement, the EOR should be informed immediately, and a site visit arranged.

Inspections should provide an assessment of both the upstream and downstream faces of the dams. Upstream slope inspections entail observations of:

- any water ponding against the face
- any water seeping from the face, wet spots
- any indication of cracking on the face
- any distortion or displacement of the face

Downstream slope inspection includes observing the following:

- indication of cracking in the dam fill
- areas of local subsidence in the dam fill
- areas of water ponding
- areas of accumulation of fines or other unsuitable materials
- areas of vegetation growth

8.4.2 Specific Monitoring Requirements

Within this subsection, specific instructions for the monitoring of cracks and the Dam 1 thermosyphons are described.

8.4.2.1 Monitoring of Cracks

Any identified cracks should be monitored to assess their ongoing condition. Inspection records should document the following:

- Number of cracks present on a dam
- Crack lengths
- Crack orientations
- Crack widths
- Crack depth
- Method of identifying specific cracks

Any observations of new cracks should be recorded in inspection forms and these cracks demarcated by use of stakes, spray paint, or other means of identification. The new crack location(s) are to be surveyed for documentation.

8.4.2.2 Dam 1 Thermosyphons

Thirty-eight inclined passive thermosyphons were installed in a row at Dam 1 during remediation works completed in 2020 (Golder 2021b). The location of the thermosyphon row is shown in Figure 16. The thermosyphons were installed to extract heat from the foundation of Dam 1 to induce freeze-back of the permafrost to limit the settlement of the dam.

The thermosyphons are to be visually inspected as part of the routine inspections of Dam 1. Inspections are to identify if thermosyphons appear damaged or require maintenance. If damage is observed, report it to the Mine Manager (Section 9.4.5 provides further maintenance instructions). Also, inspections should note if ponded water or accumulation of snow are observed near the thermosyphons as this may affect thermal performance.



Figure 16: Dam 1 Thermosyphons Alignment

8.4.3 Warning Levels and Corresponding Actions

Three levels of warning have been established for visual inspection observations. In Table 16 the warning levels and their descriptions are provided.

Warning level events are provided in Table 17, along with corresponding actions. The quantities and descriptions provided are approximate. If any abnormal observations are made or conditions appear to be changing rapidly with time, the Mine Manager should be notified, even if some of the thresholds do not appear to be exceeded.

If observations are noted that exceed those of the caution levels, or that water is overtopping a dam, refer to Table 33 in Section 10.8 for actions, some of which may trigger the implementation of the ERP.

Table 16: Warning Level Descriptions: Visual Inspections

Warning Level	Colour Code	Description
Normal		No visual observation of any new deformation features (e.g., cracks, sloughs), erosion, water elevation, or seepage. If any observations, they were within values previously documented.
Notification		An observation of a new deformation feature, erosion, water elevation, or seepage. The observed scale and/or location is such that it is unlikely to be an early indicator of a potential failure mode.
Caution		Observation of a new deformation feature, erosion, water elevation, or seepage, or an existing observation that is increasing in size or severity. The observed scale and/or location is such that it may be an early indicator of a potential failure mode.

Table 17: Visual Inspection Warning Levels and Actions

Warning Level	Event Criteria	Actions by Site Technical Staff	Actions by Mine Manager (TCA Responsible Person)	Actions by Site Owner (CIRNAC and PSPC)	Actions by Engineer of Record
Notification	- cracks (<50 mm wide) - settlement (<0.3 m) - bulging - erosion but localized and/or not in a location that is critical to dam containment (e.g., downstream toe) - clear water observed seeping through or at toe of dams or dykes - vandalism	- Perform and record visual inspection. Inspection to be filed as special inspection and separate to routine inspections. - Survey deformation or settlement feature(s). - Determine extent of potential failure mode. - Inform Mine Manager of findings.	- Notify Consulting Engineer of Record for guidance. - Notify Site Owner. - Perform visual inspection. - Be available for consultation.	Be available for consultation.	Be available for consultation.
Caution	- cracks (>50 mm wide) - settlement (>0.3 m) - bulging - erosion that is widespread and/or in a location that is critical to water containment (e.g., low permeability material) - cloudy water observed seeping through or at toe of dams or dykes - vandalism	- Perform and record visual inspection. Inspection to be filed as special inspection and separate to routine inspections. - Determine extent of potential failure mode. - Inform Mine Manager of the findings.	- Notify Consulting Engineer of Record for guidance. - Notify Site Owner. - Perform visual inspection. - Be available for consultation. - Be prepared to evacuate underground.	- Be available for consultation. - Be prepared to notify stakeholders.	Be available for consultation.

8.5 Instrumentation

Several types of geotechnical instrumentation are installed at the dams. The types of instruments, and their intended use for monitoring the dam and/or its foundation, are described below:

- Vibrating Wire Piezometers (VWP): used to measure pore-water pressures and groundwater elevations.
- Standpipe Piezometers (SPZ): used to measure pore-water pressures and groundwater elevations. At some locations, the SPZs were blocked, likely with ice.
- Thermistor Strings (TH): used to measure ground temperatures.
- Inclinator Casings (INC): used to measure horizontal subsurface displacements.
- Shape Array Accelerometers (SAA): used to measure horizontal subsurface displacements.
- Displacement monitoring locations: to measure displacement of the dams using conventional surveying techniques. Monitoring locations consist of one of the three types, as listed in the following bullets.
 - Survey Monuments (SM): measure horizontal and vertical displacement. Consist of metal rod hammered into the ground surface.
 - Settlement Plates (SP): measure vertical displacement. Consists of a metal rod affixed to a metal plate. Metal plate was installed below ground surface, either during construction (e.g., B2 Dam) or during drilling of a borehole (e.g., Dam 1).
 - Settlement Anchors (SA): measure vertical displacement at depths. Consists of a metal rod affixed to metal spikes. Metal spikes were installed into the borehole several metres below ground surface.

Table 18 provides a list of the number of operational geotechnical instruments at each dam. For as-built information, refer to Appendix G (e.g., installed coordinates and elevations, calibration certificates).

Within Subsection 8.5.1, the minimum instrumentation reading frequency for the instruments is provided. In Subsection 8.5.2, warning levels for the instruments are provided.

Table 18: Summary of Number of Operational Geotechnical Instrumentation

Area of Dam	Dam Identification	Number of Instruments				
		Vibrating Wire (VWP)	Standpipe Piezometer (SPZ)	Thermistor (TH)	Inclinometer (INC) or Shape Array (SAA)	Displacement Monitoring
Original TCA	Dam 1	4	-	5	1	8
	Dam 2	-	5	-	-	-
	Dam 3	-	3	-	-	-
	Dam 4	-	4	-	-	-
	Dam 5	-	1	-	-	-
	Dam 11	-	2	1	-	-
	Splitter Dyke	-	-	-	-	6
Northwest TCA ⁽¹⁾	Dam 21A	-	-	1	-	-
	Dam 21B	-	-	2	-	-
	Dam 21C	-	-	2	-	-
	Dam 21D	-	-	1	2	-
	Dam 22A	-	-	2	-	-
	Dam 22B	-	-	2	-	-
Other	B2 Dam	7	-	-	-	34
	Mill Pond Structure	-	4	-	-	-

Note:

- = no data (implies that specific instruments are not currently installed).

- (1) New instrumentation installation and retrofitting completed in December 2023 (WSP 2024b). Instruments installed on the NW TCA have been updated in the table.

8.5.1 Minimum Monitoring Frequency

Table 19 provides the minimum reading frequency for each type of instrument, organized by the dam in which it was installed. Instrument readings are to be physically or digitally recorded, followed by digital entry into a spreadsheet or database. The Mine Manager is responsible of arranging and ensuring for the completion of instrument monitoring and recording of information.

Readings should be forwarded to the EOR as part of ongoing monitoring and for inclusion in the AGI of Dams report.

Table 19: Minimum Instrumentation Readings Frequency

Area of Dam	Dam Identification	Minimum Reading Frequency ⁽¹⁾				
		Vibrating Wire (VWP)	Standpipe Piezometer (SPZ)	Thermistor (TH)	Inclinometer (INC) or Shape Array (SAA)	Displacement Monitoring
Original TCA	Dam 1	Weekly	-	Weekly	Monthly	Weekly
	Dam 2	-	Monthly	-	-	-
	Dam 3	-	Monthly	-	-	-
	Dam 4	-	Monthly	-	-	-
	Dam 5	-	Monthly	-	-	-
	Dam 11	-	Monthly	Monthly	-	-
	Splitter Dyke	-	-	-	-	Weekly/Monthly ⁽²⁾
Northwest TCA	Dam 21A	-	Monthly	Monthly	-	-
	Dam 21B	-	Monthly	Monthly	-	-
	Dam 21C	-	-	Monthly	-	-
	Dam 21D	-	-	Monthly	Monthly	-
	Dam 22A	-	-	Monthly	-	-
	Dam 22B	-	-	Monthly	-	-
Other	B2 Dam	Weekly	-	-	-	Monthly ⁽³⁾
	Mill Pond Structure	-	Monthly	-	-	

- = no data (implies that specific instruments are not installed).

(1) The listed minimum reading frequency is the data collection frequency when dataloggers are installed for the instruments (e.g., dataloggers are installed at Dam 1 and NW TCA dams for VWP's and Thermistors, recording readings at 12-hour frequency).

(2) Monthly during ETP non-operation, weekly during ETP operation.

(3) Historical survey monuments will be surveyed after the Spring Freshet and prior to winter freeze up. New prisms are to be surveyed monthly.

8.5.2 Warning Level

Three levels of warning have been established for the Giant Mine for instrument readings. In Table 20 the warning levels and their descriptions are provided.

Table 20: Warning Level Descriptions: Instrument Readings

Warning Level	Colour Code	Description
Normal		Readings are within a range and/or demonstrated trend that is typical and within historical precedent.
Notification		Readings have a level and/or demonstrated a trend that differs from that previously established by available monitoring results.
Caution		Readings have exceeded a level and/or demonstrated a trend that is beyond that previously established by available monitoring results.

In the following subsections, the instrument warning levels and corresponding actions are provided and organized by the instrument type. Generally, the warning levels for the instrumentation were selected with judgement and based on the precedent and trends set with available monitoring data, unless noted otherwise.

8.5.2.1 Vibrating Wire Piezometers

VWPs are located at Dam 1 and B2 Dam. Warning levels are provided in Table 21 for Dam 1 and Table 22 for B2 Dam.

Dam 1

For Dam 1, warning levels are based on the precedent set by readings and are expressed as an overall hydraulic head elevation. Warning levels have not been designated for instruments that are no longer functional or frozen. For actions corresponding to notification and caution warning levels, refer to Table 31. If caution warning levels are exceeded, refer to Table 33 in Section 10.8.

Table 21: Dam 1 Vibrating Wire Piezometer Warning Level Criteria

Piezometer Identification	Total Head Readings Warning Levels (masl)		
	Normal	Notification	Caution
D1-SD-02	≥164.1 to ≤166.4	>166.4 to ≤167.1	>167.1 to ≤168.5
D1-SD-03	≥154.3 to ≤154.6	>154.6 to ≤156.6	>156.6 to ≤165.7
D1-SD-05	≥162.3 to ≤163.1	>163.1 to ≤164.1	>164.1 to ≤166.9
D1-SD-06D	≥153.3 to ≤153.7	>153.7 to ≤155.2	>155.2 to ≤171.7

B2 Dam

Warning levels presented in Table 22 are based on the measured water pressures at the piezometers.

The caution level is slightly greater than the maximum recorded total head at the piezometer location. The notification level is set to be 0.5 m lower than the caution level, except for piezometer PZ-7. The notification level for PZ-7 is set to be 0.2 m lower than its caution level (Golder 2022c).

For actions corresponding to notification and caution warning levels, refer to Table 31. If caution warning levels are exceeded, refer to Table 33 in Section 10.8.

Table 22: B2 Dam Vibrating Wire Piezometer Warning Level Criteria

Vibrating Wire Piezometer	Total Head Reading Warning Levels (masl)		
	Normal	Notification	Caution
PZ-1	≤165.5	>165.5 to ≤166.0	>166.0 to ≤166.5
PZ-2	≤164.3	>164.3 to ≤164.8	>164.8 to ≤160.0
PZ-3	≤164.0	>164.0 to ≤164.5	>164.5 to ≤165.5
PZ-4	≤163.5	>163.5 to ≤164.0	>164.0 to ≤165.5
PZ-5	≤163.0	>163.0 to ≤163.5	>163.5 to ≤165.5
PZ-6	≤162.2	>162.2 to ≤162.7	>162.7 to ≤165.5
PZ-7	≤164.0	>164.0 to ≤164.2	>164.2 to ≤164.7

8.5.2.2 Standpipe Piezometer Warning Levels

Standpipe piezometers (SPZ) were installed at some of the Original TCA dams and Northwest TCA dams in 2019. Frozen standpipes at the Northwest TCA dams and Dam 1 were retrofitted in 2023 (WSP 2024b). Standpipes were also installed at the Mill Pond Structure in 2021 (Golder 2022d). Table 23 presents the standpipes currently functioning which are not frozen. No warning levels have been designated at this time.

Table 23: Standpipe Piezometers to be Monitored on Original TCA and Mill Pond Structure

Dam	Borehole Identification
Dam 2	D2-SD19-23
	D2-SD19-24
	D2-SD19-25
	D2-SD19-26
	D2-SD19-27
Dam 3	D3-SD19-28
	D3-SD19-29
	D3-SD19-31
Dam 4	D4-SD19-01
	D4-SD19-02
	D4-SD19-03B
	D4-SD19-04
Dam 5	D5-SD19-05B
Dam 11	D11-SD19-19
	D11-SD19-20
Mill Pond	BC-BH21-17
	MPB-BH21-18
	MPB-BH21-23
	B1-BH21-02

8.5.2.3 Thermistor String Warning Levels

Several thermistor strings (TH) have been installed at the dams to monitor subsurface temperatures, typically in locations where frozen soil was encountered during drilling.

Table 24 and Table 25 list the warning levels for select thermistors and their nodes that are installed at Dam 1 and the Northwest TCA dams. The following warning levels have only been selected for thermistors and nodes that were installed within permafrost or that have shown frozen soil conditions since installation. Levels were set based on available monitoring data and to identify trends of warming ground temperatures in the permafrost. Warming of the permafrost, which could indicate changing seepage conditions and/or the potential for deformation, thus requiring additional monitoring and/or actions. Warning levels have not been assigned for thermistors and/or nodes that are in material that does not currently meet the definition of permafrost.

Table 24: Dam 1: Thermistor Warning Levels

Dam Identification	Borehole Identification	Thermistor Nodes Installed in Permafrost		Warning Level for Maximum Temperature Reading (°C)		
		Node No.	Depth (mbgs)	Normal	Notification	Caution
Dam 1	D1-SD-10	3 to 12	9.7 to 22.7	≤-0.1	n/d	>-0.1 to <0
	D1-SD-12	10 to 14	15.8 to 19.8	≤-0.1	n/d	>-0.1 to <0
	D1-SD13	7 to 14	11.1 to 18.1	≤-0.1	n/d	>-0.1 to <0
	D1-SD-16	9 to 14	15.5 to 20.5	≤-0.1	n/d	>-0.1 to <0
	D1-SD-19	14	16.2	≤-0.1	n/d	>-0.1 to <0

Notes: mbgs = metres below ground surface, n/d = not designated.

For Dam 1, warning levels have not been designated for some of the thermistors. These thermistors provide redundancy and additional information on the overall thermal regime of Dam 1 foundation.

Table 25: Northwest Tailings Containment Area: Thermistor Warning Levels

Dam Identification	Borehole Identification	Thermistor Nodes Installed in Permafrost		Warning Level for Maximum Temperature Reading (°C)		
		Node No.	Depth (mbgs)	Normal	Notification	Caution
Dam 21A	D21A-SD19-32	14 to 16	8.0 to 11.0	≤-0.5	>-0.5 to ≤-0.1	>-0.1 to <0
Dam 21C	D21C-SD19-18	14 to 16	13.8 to 15.1	≤-0.5	>-0.5 to ≤-0.1	>-0.1 to <0
Dam 21D	D21D-SD19-13	12 to 15	6.2 to 10.7	≤-0.5	>-0.5 to ≤-0.1	>-0.1 to <0
Dam 22B	D22B-SD19-08	12 to 15	11.0 to 15.5	≤-0.5	>-0.5 to ≤-0.1	>-0.1 to <0

Note: mbgs = metres below ground surface; n/d = not designated.

For the Northwest TCA thermistors, the warning levels have been set for nodes installed in fine grain material where frozen conditions have been observed. The warning levels have been set to be conservative and to provide an early trigger of any measured warming trends.

8.5.2.4 Inclinometer and Shape Array Warning Levels

Inclinometer casing warning levels are included in Table 26. Warning levels are based on the maximum cumulative horizontal displacement at regular depth intervals. For actions corresponding to notification and caution warning levels, refer to Table 31. If caution warning levels are exceeded, refer to Table 33 in Section 10.8.

Table 26: Inclinometer Warning Level Criteria

Inclinometer Identification	Overall Measurement of Horizontal Displacement (mm)		
	Normal	Notification	Caution
D1-SD-05	≤30	>30 to ≤100	>100 to ≤200
D21D-SD19-11	≤30	>30 to ≤100	>100 to ≤200
D21D-SD19-12	≤30	>30 to ≤100	>100 to ≤200

8.5.2.5 Displacement Monitoring Warning Levels

The displacement monitoring warning levels are presented in Table 27 for Dam 1, Table 28 for B2 Dam, and Table 30 for Splitter Dyke. For actions corresponding to notification and caution warning levels, refer to Table 31. If caution warning levels are exceeded, refer to Table 33 in Section 10.8.

Table 27: Dam 1 Displacement Monitoring Warning Level Criteria

Location on Dam	Instrument		Criteria for Vertical Movement in One-year Period (mm)		
	Identification	Type	Normal	Notification	Caution
Downstream Toe	SP3	SP	≤30	>30 to ≤150	>150 to ≤250
Downstream Bench	D1-SD-08	SA	≤80	>80 to ≤150	>150 to ≤200
Crest	D1-SD-23	SA	≤30	>30 to ≤100	>100 to ≤150
Upstream Slope	T22-01	SM	≤50	>50 to ≤100	>100 to ≤200
	T22-02	SM	≤50	>50 to ≤100	>100 to ≤200
	T22-03	SM	≤50	>50 to ≤100	>100 to ≤200
	T22-04	SM	≤50	>50 to ≤100	>100 to ≤200
	T22-05	SM	≤50	>50 to ≤100	>100 to ≤200

SA = settlement anchor, SM = survey monument, SP = settlement plate.

Survey prisms were installed on the B2 Dam in June 2024 to improve accuracy of vertical survey results and efficiency of survey methods. The historical survey monuments are presented in Table 29 which are to be monitored as a redundancy check as specified in Section 8.5.1.

Table 28: B2 Dam Displacement Monitoring Warning Level Criteria

Location on Dam	Instrument		Criteria for Vertical Movement in One-year Period (mm)		
	Identification	Type	Normal	Notification	Caution
Upstream Crest	B2RP01	SM	<50	>50 to ≤80	>80 to ≤150
	B2RP02	SM	<50	>50 to ≤80	>80 to ≤150
Downstream Toe	B2RP03	SM	<30	>30 to ≤100	>100 to ≤200
	B2RP04	SM	<30	30 to ≤100	>100 to ≤200

SM = survey monument.

Table 29: B2 Dam Historical Displacement Monitoring Monuments

Location on Dam	Instrument	
	Identification	Type
Downstream Toe	S01 to S06	SP
	S27 to S34	SM
Upstream Crest	S07 to S12	SM
	S13 to S20	SP
Upstream Toe	S21 to S23	SP

SM = survey monument, SP = settlement plate.

Table 30: Splitter Dyke Displacement Monitoring Warning Level Criteria

Location on Dyke	Instrument		Criteria for Vertical Movement in One-year Period (mm)		
	Identification	Type	Normal	Notification	Caution
Downstream Slope	T1, T3, T5	SM	≤200	>200 to ≤250	>250 to ≤350
Upstream Slope	T2, T4, T6	SM	≤200	>200 to ≤250	>250 to ≤350

SM = survey monument.

8.5.3 Actions Corresponding to Warning Levels

In Section 8.5.2, warning levels have been established for instrument readings. In Table 31, actions that correspond to the exceedance of either the notification or caution warning levels are provided.

If caution warning levels are exceeded, refer to Table 33 in Section 10.8. This is a more serious scenario, as the ERP may potentially need to be initiated.

Table 31: Actions for Corresponding to Instrumentation Warning Levels

Warning Level	Event Criteria	Actions by Site Technical Staff	Actions by Mine Manager (TCA Responsible Person)	Actions by Site Owner (CIRNAC and PSPC)	Actions by Engineer of Record
Notification	Refer to the following tables: - Table 21 and Table 22 for Dam 1 and B2 Dam vibrating wire piezometers - Table 24 and Table 25 for Original and Northwest TCA thermistors - Table 26 for Dam 1 inclinometers - Table 27, Table 28, and Table 30 for Dam 1, B2 Dam, and Splitter Dyke displacement monitoring locations	- Perform and record visual inspection. Inspection to be filed as special inspection and separate to routine inspections. - Record an additional reading within 12 hours. - Inform Mine Manager of findings.	- Perform visual inspection if requested by the Engineer of Record. - Be available for consultation.	Be available for consultation.	- Notify Site technical staff and Mine Manager of reading. - Request additional reading and visual inspections. - Be available for consultation.
Caution	Refer to the following tables: - Table 21 and Table 22 for Dam 1 and B2 Dam vibrating wire piezometers - Table 24 and Table 25 for Original and Northwest TCA thermistors - Table 26 for Dam 1 inclinometers - Table 27, Table 28, and Table 30 for Dam 1, B2 Dam, and Splitter Dyke displacement monitoring locations	- Perform and record visual inspection. Inspection to be filed as special inspection and separate to routine inspections. - Increase monitoring to every six hours. - Inform Mine Manager of the findings.	- Perform visual inspection. - Be available for consultation. - Be prepared to evacuate underground and affected areas.	- Be available for consultation. - Be prepared to notify stakeholders and neighboring communities	- Notify Site technical staff, Mine Manager, and Site Owner of the reading. - Request additional reading and visual inspections. - Be available for consultation.

8.6 Water Sampling and Testing

The details of the water sampling and testing program are provided in the Standard Operating Procedures and QA/QC Plan for Effluent and Water Sampling Rev 3.0 (CIRNAC and GNWT 2022). It outlines the routine monitoring of surface water, mine water, and groundwater that is completed at the Site daily, weekly, monthly, quarterly, or seasonally depending on the regulatory and operational requirements. The monitoring schedule is developed each year once the start date for treated effluent discharge from the ETP is known.

The Standard Operating Procedures and QA/QC Plan for Effluent and Water Sampling Rev 3.0 (CIRNAC and GNWT 2022) describes the sampling requirements for surface water, mine water, and groundwater monitoring under the SNP, MDMER/EEM, and OMP programs, as well as the AEMP if relevant. Where sample locations fall under more than one program (e.g., a station is both an SNP and an AEMP station), the relevant programs are indicated.

Stations associated with the ETP that are sampled for compliance with the Water Licence and/or MDMER/EEM during discharge are SNP 43-1 (treated effluent; SNP and MDMER/EEM), SNP 43-11 (reference area; SNP and MDMER/EEM), and Baker Creek Exposure Point (exposure area; MDMER/EEM).

Treated effluent from the effluent treatment plant (ETP) is discharged into Baker Creek during open-water conditions, usually over a two- to three-month period between July and September unless higher water conditions at the Site necessitate an earlier/extended discharge period. Effluent discharge typically begins after 1 July each year to avoid the spring spawning period for Arctic Grayling except for during high-water conditions that necessitate early discharge (e.g., June). Treated effluent is tested for compliance with the Effluent Quality Criteria (EQC) defined in the Water Licence (MV2007L8-0031) as well as MDMER discharge limits before it is released into Baker Creek, which then flows into Yellowknife Bay in Great Slave Lake.

Further ETP operational samples, submitted for arsenic analysis on a 4-hour turn-around-time, are taken by the ETP Operator on a daily basis. These results are compared to the allowable discharge requirements and adjustments to the treatment process can be made if concentrations approach the caution level.

Water sampling and testing is also required by the Type A Water Licence (MVLWB 2021).

8.7 Survey and Bathymetry

A topographic survey of the dam crests of Dam 1, Splitter Dyke, Dam 2, B2 Dam, Mill Pond Structure, and the Northwest TCA dams is carried out annually to check the dam crest elevations and determine potential changes in water levels for the next operating year. Additional surveys may be required should conditions be observed to change significantly or higher than normal operating elevations of water within the dams.

Bathymetric surveys will be carried out as required by ongoing observations and recommendations from the EOR or if conditions change. These surveys will be used to recalibrate the water storage capacity estimates of the ponds. The most recent bathymetric survey was completed in 2019 in support of closure design studies (Golder 2020a).

8.7.1 InSAR Monitoring

The use of Interferometric Synthetic Aperture Radar (InSAR) has been used to monitor displacement of the Original TCA dams, Northwest TCA dams, B2 Dam and the Mill Pond Structure. InSAR data and reports are to be issued on a monthly basis between April and October when ground conditions are free of obstructions (i.e., snow).

8.8 Weather Stations

Climate data should be downloaded regularly by the Environmental Manager or their designate to monitor conditions in comparison with the long-term average data (Appendix D). This information should be forwarded to the EOR to assist in determining trends that may influence oversight of the water management systems.

Observations of air temperature, rainfall, and snowfall are available publicly for Yellowknife Airport. These observations can be obtained from Environment Canada (<https://www.canada.ca/en/services/environment/weather.html>). Further details on weather stations are presented in Appendix D.

To improve the credibility of the Yellowknife Airport data for the precipitation at Giant Mine, climate data should be corrected by the EOR or designate by applying the rainfall and snowfall weighting and under-catch factors that are identified in Appendix D.

For early alerts of possible extreme events, the Environmental Manager should subscribe to the Weather Network weather alert service, (<https://www.theweathernetwork.com/us>) or similar and check the Environment Canada website for public weather alerts (https://weather.gc.ca/warnings/index_e.html) on a regular basis. Should an extreme event alert be received, the Environmental Manager will inform the Mine Manager and EOR and carry out an inspection prior to and following the event to assess any potential effect to the dams/facilities.

Rainfall data at Yellowknife Airport should be collected from Environment Canada following any heavy rainfall warning issued between April and September. Environment Canada defines heavy rainfall as 7 mm per hour or more.

If total rainfall during any 24-hour period exceeds 50 mm, which is approximately equivalent to a 1-in-10-year daily rainfall event (Table D-5, Appendix D), an inspection should be scheduled as soon as practical.

8.9 Annual Geotechnical Inspections of Dams

As part of requirements for annual water licence reporting to MVLWB, the dams at Giant Mine are to be inspected annually, during the summer months by a Professional Engineer (MVLWB 2021). Although not explicitly stated in the Water Licence, an implied requirement is that the Professional have geotechnical experience in dams and engineered structures that are located in areas of permafrost. This has been termed AGI of Dams (but is known as Dam Safety Inspection in other jurisdictions).

The AGI of Dams includes comprehensive review of the facilities and their management systems. This inspection will be completed by the EOR or a designated person.

8.10 Frequency of Dam Safety Reviews

The CDA (2013) Dam Safety Guidelines recommends that a DSR be conducted every five to 10 years depending on the dam consequence. The frequency for the dams at Giant Mine is included in Table 4.

As the last DSR was conducted in 2019 (SRK 2020), the next DSR would be initiated sometime between 2024 and 2029, depending on the dam consequence classification.

8.11 Event-Driven Procedures

In addition to the routine and periodic inspections, special inspections may be required after unusual or significant seismic or climatic events (and during if possible). Significant climatic events include heavy rainfall and spring freshet floods.

Giant Mine staff should carry out the special inspections after significant events and the EOR should be notified of the findings. If there are any concerns with areas, facilities, or dams, then the Mine Manager will arrange to bring in the EOR for further inspections and review.

Unusual events are defined in the ERP (Table 34 in Section 10.8) along with required actions.

8.12 Trigger for Change of Operations

The Giant Mine is in the Closure-Active Care phase of the mine life. The only operations at the facility are related to the management and treatment of surface water and ongoing closure and reclamation works.

Ongoing surveillance is intended to detect any unusual conditions that could signify potential issues with the site, as described in Section 8.4. If any unusual conditions are observed, the Mine Manager must be informed immediately. Depending on the nature and severity of the condition observed, the EOR may be contacted and/or the EPRP may be initiated. The decision to execute the EPRP will only be made once an incident exists (e.g., possible failure or failure of a dam) and there is a serious risk to facilities and/or downstream stakeholders (e.g., release of water and/or tailings).

8.13 Documentation and Reporting

Surveillance reporting must be documented, and records maintained. If an important issue arises from an inspection, the Mine Manager should be notified immediately. The Mine Manager will contact the EOR if necessary. Required surveillance reports are presented in Table 32.

Table 32: Surveillance Reporting Requirements

Surveillance Report	Report Provided To	Frequency of Reporting
Daily visual inspection sheets (photographs should be filed, if taken)	Mine Manager	Immediately following inspection
	Environmental Manager	
	Engineer of Record	Within one week of inspection
Weekly visual inspection sheets	Mine Manager	Immediately following inspection
	Environmental Manager	
	Engineer of Record	Within one week of inspection
Monthly inspection sheets and photographic records	Engineer of Record	Within one month of inspection
Records of instrument readings	Mine Manager	Within one week of inspection
	Environmental Manager	
	Engineer of Record	
Annual Geotechnical Inspection Report	Mackenzie Valley Land and Water Board (MVLWB)	Within 120 days following the completion of the site visit
Annual Water Licence Report	MVLWB	Annually by March 31 for the previous operating period

Table 32: Surveillance Reporting Requirements

Surveillance Report	Report Provided To	Frequency of Reporting
Dam Safety Reviews	Mine Manager	Copy of final report provided to EOR within one month of completion
	Engineer of Record	
Special inspection due to extreme weather or seismic events	Mine Manager	Immediately following inspection
	Environmental Manager	Within 24 hours of inspection
	Engineer of Record	
Memorandum for each geotechnical inspection completed by the Engineer of Record	Mine Manager	Within one month of inspection

Hard copies of all documents produced in the reporting process are to be stored at the project offices with electronic copy on a secure server.

Inspection reports are to be maintained by Forward Mining at its site office at the Giant Mine site and electronically on a secure server.

Observations made during inspections must be catalogued in field books. Photocopies/electronic copies of the used pages of the field books should be made for safekeeping. Copies of field notes or field books should be stored at the site offices of the person making the inspection when not in use.

The inspection records must include specific reference to seepage (or lack thereof) at each of the dams inspected. Quantitative estimates of the seepage should be made with reference to the location of the seepage (if any).

As a requirement of the water licence (MVLWB 2021), an annual report must be submitted by March 31 of every year. The report must include all the data and information required by the Surveillance Network Program described in the water licence. It is the responsibility of the Mine Manager to prepare these annual reports, which would include the summary tables prepared by the Environmental Manager. The Mine Manager is responsible for submitting copies to Public Services and Procurement Canada (PSPC), who then provide reports to CIRNAC. Submittal of reports to the MVLWB is the responsibility of CIRNAC.

9.0 MAINTENANCE

9.1 Objectives

Maintenance is important to keep the facilities in a safe condition and for the effective management of ponded water. It is the responsibility of the Mine Manager to ensure that the facilities are properly maintained.

The objectives of the maintenance program are to:

- Identify and describe critical parts of the facility.
- Address routine, predictive/preventative, and event-driven maintenance.
- Address operating and surveillance observations for all components of the facility.

9.2 Inventory of Components Requiring Maintenance

The following components of the Giant Mine TCAs and surface water dams may require maintenance over the facility's lifetime.

- access roads
- dams
- dykes
- Mill Pond Structure
- water management systems and channels
- water management and treatment equipment
- water treatment ponds
- spillways
- pumps and pipe systems

9.3 Maintenance Schedule and Triggers

The facilities should be subject to a regular maintenance program.

The Mine Manager for Giant Mine should have sufficient personnel or access to a contractor in close proximity to the Site to perform necessary repairs to infrastructure. These repairs would be planned tasks to address issues identified during the regular inspections (Section 8.4) or inspections due to extreme weather or reported sudden change in conditions (Section 8.11).

Contractors in Yellowknife who have experience with earthworks and who could be contacted are as follows:

- ACE Enterprise Ltd, 151 Enterprise Drive, 867.920.2082
- RTL Construction, 350 Old Airport Road, 867.873.6271
- Nahanni Construction Ltd, 100 Nahanni Drive, 867.873.2975
- Weatherby Trucking Ltd, Highway 3, km 331.5, 867.873.9801
- Forward Mining LP, 5204 Franklin Avenue, 867.874.3243

9.4 Routine and Preventative Maintenance

Maintenance requirements for the facilities and dams are provided here. In addition to the requirements established in this section additional requirements will be established on an annual basis as part of AGI reporting.

9.4.1 Access

Site access roads, including roads from offices and workshops to dams and facilities, should be maintained. In addition, the condition of the access road to the site should also be monitored. Any observed road deterioration or damage during site visits should be recorded and arrangements made for repairs to be carried out.

The maintenance program may normally include regrading of the gravel site access roads and dust control as needed. It is not anticipated that extensive work would be required. If work should be required on the main site access road, it may be necessary to coordinate with MVLWB prior to initiating work.

Some locations on site have specific vehicle access restrictions, which are:

- Dyke 6 – All vehicle activity should stay at least 15 m away from the slope crest in the area of failure of Dyke 6. Maintain a barricade with appropriate signage to communicate the restriction.
- Dam 12 – Prevent vehicle activity on Dam 12 and maintain a barricade to the dam with appropriate signage to communicate the restriction.

9.4.2 Dams and Dykes

Maintenance work required on the dam and dyke structures to control seepage, settlement, and erosion should be carried out as needed and comprise the following activities.

General

- Regrade dam crests and replace granular road surfacing material to maintain crest design profiles.
- Replace and regrade fill materials lost on the downstream face and road surface (such as may be eroded by rainfall runoff).
- Place dam fill to maintain dam crest elevations. The placement of additional fill is intended to preserve dam crest elevations but does not mitigate the need to investigate and determine causes of historic observed settlement. Fill should not be placed without consultation with the EOR.
- Replace and regrade fill materials lost on the pond side slope and regrade the adjacent road.
- Direct seepage away from dam toes, where a sump or other infrastructure is not already in use.
- Consult the EOR prior to any excavation or earthworks in and around the dams (e.g., excavation of tailings upstream of Dam 12 for use in underground stabilization work).

Dam 1

- Prior to snowmelt, remove all snow from the Dam 1 crest, downstream slope, and abutments to minimize the quantity of snow melt that could potentially infiltrate.
- During the spring freshet, divert surface water runoff away from the dam to minimize infiltration of water.

- Pumping infrastructure should be available to remove any ponded water observed on the dam crest. Typically occurs during the spring freshet but could be required at any other time.

Ongoing removal of vegetation is required, to prevent the growth of larger trees and the damage to the dams that could occur in the event of treefall.

9.4.3 Spillways and Water Management Channels

To maintain the efficiency of spillways and water management channels, the following activities should be undertaken.

General

The conveying capacity of spillways and channels must be maintained. The spillways should be kept clean of any blockages (such as from soil material or vegetation).

A reserve of clay (e.g., C1 Clay Borrow Area) should be on site to form a clay plug at spillways, if needed. This material should be placed in spillways or elsewhere only under the direction of the EOR.

Dyke 6

- The spillway across the crest of dyke is to be inspected after each intense rainfall event and spring freshet.
- Inspect the drainage pipe located upstream (Central Pond) during routine inspections. Remove any debris or tailings from the intake to avoid impeding the flow of water into the North Pond.
- Inspect the surface water sumps located upstream (Central Pond) during routine inspections. Minimize the quantity of ponded water as the dyke was not constructed to retain water.

DWC Dam

Inspect plastic screen, paving stones, and steel mesh as part of routine inspections. Remove debris from screens frequently to prevent the screens or inlet pipe from blockages.

9.4.4 Water Management and Treatment Equipment

To maintain the efficiency of water management and treatment operations, water management equipment should be kept in a well-maintained condition. Examples of such equipment include, but are not limited to, the following:

- pumps
- valves
- pipe and/or hose
- water treatment plant instruments
- holding tanks
- mixers, etc.

A supply of critical spares for operation of the ETP should be maintained on site. Further details on water treatment are contained in the Giant Mine ETP Operating Manual (i.e., SOP# - ETP – 01).

9.4.5 Dam 1 Thermosyphon Maintenance

In the sections below, routine and emergency maintenance tasks for the thermosyphons are summarized. These are required to maintain the thermosyphons in good working condition. Refer to the thermosyphon suppliers recommended maintenance for further details (Arctic Foundations of Canada 2020).

Routine Maintenance

- Any snow accumulation surrounding the radiator fin(s) should be removed, but in a manner that does not damage the unit.
- Maintain the ground surface surrounding the thermosyphon row so that all runoff water drains away from the thermosyphons. Depressions should be filled such that water does not pond or pool near the thermosyphons.
- Measure radiator temperature at the start of each winter season. Temperatures can be measured using a contact thermometer or thermal imaging camera. Functioning thermosyphons will display radiator temperatures a few degrees warmer than ambient air.

Emergency Maintenance

If damage to the thermosyphons or leaks from casing are observed during routine inspections, the following steps are to be implemented:

- Determine the cause of the damage if possible and make provisions to preclude additional damage.
- Determine by inspection if the pressure integrity of the damaged unit has been compromised. If so, this is to be recorded and the Mine Manager is to be notified immediately.
- If release of gas is observed, keep out of the area and control access to the location until the release has stopped. Once the gas has stopped, plug the hole or (if the hole is not identifiable) cover the area to prevent moisture ingress.
- If damage occurs to the thermosyphons, the manufacturer is to be contacted to arrange for repair/replacement.

9.4.6 Event-Driven Maintenance

After a special inspection triggered by an event, event-driven maintenance may be required. These requirements will be determined by the Mine Manager and/or EOR following the inspection. The maintenance should be completed as soon as required, as indicated by the Engineer.

9.4.7 Documentation and Reporting

Maintenance reports/records are to be produced and should be maintained by Forward Mining. Copies of these documents should be provided to the EOR within one month of completion.

Construction or installation of any new features (for example instrumentation) should also be documented in a construction record report by the contractor completing the works. Copies of these reports should be provided to the Mine Manager and EOR following completion.

All records will be maintained by Forward Mining at their offices and electronically on a secure server.

10.0 EMERGENCY PREPAREDNESS AND RESPONSE PLAN

The Emergency Preparedness and Response Plan (EPRP) is the overall framework for those involved with the TCAs and dams at Giant Mine to be ready to respond to an emergency. Preparedness covers pro-active measures that can be implemented and practiced such that in the event of an emergency, the procedures can be executed promptly.

If an emergency appears to be imminent, Section 10.5 provides the EERP. This provides procedures in direct response to dam failure where water and/or tailings may be released.

Giant Mine is a closed facility under active care and maintenance, with no current or scheduled mining activities planned. There are currently no automated warning systems in place at the site specifically related to dam safety. Site personnel are present on site on a full-time basis. Inspection of the facilities occurs as described in Section 8.4. Personnel are trained to respond to specific changes in site conditions.

10.1 Requirements of Legislation, Codes of Practice, Commitments, etc.

The requirements related to this EPRP and applicable Codes of practice are listed below:

- CDA Dam Safety Guidelines (CDA 2013): Section 4.0 Emergency Preparedness
- Application of Dam Safety Guidelines to Mining Dams (CDA 2019)
- MAC Guidelines (MAC 2021a, b)

10.2 Identification of all Jurisdictions, Agencies, and Individuals Involved in Preparedness and Response

Depending on the emergency related to the Giant Mine TCAs, an emergency response could involve the following jurisdictions, agencies, and individuals.

- Emergency responders:
 - Off-site (fire/ambulance/RCMP)
 - On-site Site Security subcontractor
- Main Construction Manager (Parsons) and their various subcontractors with responsibilities for:
 - Mine Manager (Parsons)
 - TCA Responsible Person (Parsons)
 - Site Personnel (various subcontractors)
- Site Owner
 - CIRNAC
 - PSPC officials
- Engineer of Record (or another geotechnical consultant)
- Regulatory, Project oversight, and stakeholder parties
 - MVLWB

- Government of Northwest Territories (GNWT)
- City of Yellowknife
- Giant Mine Oversight Board (GMOB)
- Workers' Safety and Compensation Commission (WSCC)
- First Nations community leaders

10.3 Training Requirements

Personnel are to read and comply with the following documents:

- 1) Operation, Maintenance, and Surveillance Manual for Giant Mine Tailings Containment Areas and B2 Dam (this document).
- 2) Other operational manuals, as required and presented in Section 5.2.

If personnel complete any specific training that relates to the OMS Manual, EPRP, or dam safety management, this should be documented within the OMS Manual.

10.4 Public Relations Plan

All public relations are the responsibility of CIRNAC. Parsons' Emergency Management and Spill Response Plan (EMSRRP) (Parsons 2024) states that all media inquiries are to be directed to CIRNAC. If any unexpected media report to the Site, they are to be referred to the Mine Manager, who will direct them to CIRNAC.

10.5 Emergency Response Plans

If it appears that a dam safety emergency is imminent, where the release of water and/or tailings is possible, go immediately to Section 10.5.1. For all other ERPs, refer to Section 10.5.2.

10.5.1 Emergency Response Plan – Dam Failure

If the release of water and/or tailings appears possible, the Mine Manager, in consultation with the EOR, will initiate the ERP for Dam Failure. The Mine Manager will become the Incident Commander. Refer to Section 10.5.2 for Parsons (2024) framework for Emergency Response Communications.

Figure 17 presents the emergency response plan for the ERP for Dam Failure. Initially, it is paramount that workers and the public located at low topographic elevations downstream of the potential failure, be evacuated immediately. The list of parties to be contacted by the Mine Manager and their responsibilities are found in Figure 17.

In Figure 18 areas that would be at risk of inundation and may have workers or public present are shown. High risk areas are underground workings (via B2 and B3 Pits), along Baker Creek and Trapper Creek, and along public mine access roads.

Once evacuation orders have been raised for underground and along Baker Creek, the next critical step is blocking further access to public roads. The Mine Manager would contact the RCMP and rely upon them setting up blockades. Suggested blockade points are shown in Figure 19, but adjustments to blockages could be required depending on specific circumstances.




Figure 17: Emergency Response Plan – Dam Failure






Figure 19: Emergency Response Plan – Road Blockade Points

10.5.2 Other Emergency Response Plans

Figure 20 shows Parsons' Emergency Response Communications Plan. The Parsons (2024) Emergency Management and Spill Response Plan (EMSRP) contains 29 specific incident action plans in response to the following categories:

- Medical Emergency
- Environmental Release (spill)
- Underground Emergency
- Fire or Explosion Hazards
- Power Failure
- Site Breach, Bomb Threat, Sabotage
- Earthquake
- Severe Weather
- Site Evacuation
- Vehicle Incident
- Wildfires




Figure 20: Parsons Emergency Response Communications Plan for Giant Mine Remediation Project

10.6 Incident Investigation Procedure

All dam safety incidents at Giant Mine must be reported to the Mine Manager or the Environmental Manager, who will then contact the EOR. The EOR may request that an incident investigation be initiated. The Mine Manager will be responsible for obtaining incident reports from their subcontractors, as aligned with the incident investigation sections of Parsons' EMSRP (Parsons 2024).

10.7 Call-out Procedure for Emergency Response

If a condition related to a potential failure mode is observed (Table 14) by the personnel conducting an inspection, the Mine Manager must be informed immediately. Members of the public may also report incidents either directly to Giant Mine or via other governmental services or Department for Environmental and Natural Resources.

This EPRP can be activated based on specific caution levels (Sections 7.6.2, 8.4.3, and 8.5.3) or exceedance thereof (Section 10.8) and at three levels of response following the identification of an incident on site. The response level of an incident may be raised or lowered following ongoing monitoring and management. The three levels of response are:

- Level 1. On-site incident with no potential for effect to neighboring communities.
- Level 2. External incident following the warning of a potentially critical situation.
- Level 3. External incident when failure is active or imminent.

Once the Mine Manager has determined whether the reported conditions meet the criteria for either the caution level or exceedance thereof, the Mine Manager may need to call emergency contacts and/or stakeholders and neighboring communities depending on emergency conditions. A list of contacts, including emergency contacts, are listed in Table 37.

10.8 Exceedance of Caution Warning Levels and Corresponding Actions

Broadly, notification and caution warning levels have been established for water elevations (Section 7.6), visual observations (Section 8.4.3), and instrumentation (Section 8.5.2) When caution warning levels are exceeded, responding actions are provided in Table 33. Unusual events and actions are presented in Table 34.

Table 33: Actions for Exceedance of Caution Warning Levels

Surveillance Criteria	Event Criteria	Actions by Site Technical Staff	Actions by Mine Manager	Actions by Site Owner (CIRNAC and PSPC)	Actions by Engineer of Record
Pond Levels (Section 7.6)	Combination of two criteria being met. 1. Water level or differential exceeds one of the following: a. Water level in Northwest Pond > 193.35 m b. Water level in Polishing Pond >174.8 m c. Water level in North Pond > Polishing Pond +1.7 m d. Water level in North Pond < Polishing Pond -1.7 m e. Water level at B2 Dam > 164.7 m 2. Flow into pond or Baker Creek is anticipated to stop or be reduced to a rate whereby water level can be reasonably expected to remain static or reduce with time.	- Perform and record visual inspection. Inspection to be filed as special inspection and separate to routine inspections. - Determine extent of potential failure mode. - Measure water levels in ponds and determine capacity to receive water (if not actioned at Notification Level). - Set up and start pumps and pipelines (if not already at Caution Level). - Start pumping system. - Inform Mine Manager of findings.	- Notify Engineer of Record for guidance. - Notify Site Owner. - Perform visual inspection. - Be available for consultation. - Be prepared to evacuate underground and affected areas.	- Be available for consultation. - Be prepared to notify stakeholders and neighboring communities.	Be available for consultation
	Combination of three criteria being met. 1. Water level or differential exceeds one of the following: a. Water level in Northwest Pond > 193.35 m b. Water level in Polishing Pond > 174.8 m c. Water level in North Pond > Polishing Pond +1.7 m d. Water level in North Pond < Polishing Pond -1.7 m e. Water level at B2 Dam > 164.7 m 2. Flow into pond or Baker Creek is anticipated to continue whereby an overtopping failure could potentially occur.	- Perform and record visual inspection. Inspection to be filed as special inspection and separate to routine inspections. - Determine extent of potential failure mode. - Measure water levels in ponds and determine capacity to receive water (if not actioned at Notification Level). - Set up and start pumps and pipelines (if not already at Caution Level). - Start pumping system. - Follow Mine Manager's instructions.	- Notify Engineer of Record for guidance. - Notify Site Owner. - Perform visual inspection. - Be available for consultation. - Initiate Emergency Response. - Evacuate underground and affected areas.	- Be available for consultation. - Notify stakeholders and neighboring communities.	Be available for consultation.
Visual (Section 8.4)	- water overtopping the dams or dykes - major cracks (>50 mm wide) - Large sink holes (>0.5 m) that are also associated with seepage and/or turbid water	- Perform and record visual inspection, if safe to do so. Inspection to be filed as special inspection and separate to routine inspections. - Determine extent of potential failure mode. - Inform Mine Manager of findings.	- Notify Engineer of Record for guidance. - Notify Site Owner. - Perform visual inspection. - Be prepared to evacuate underground and affected areas. - Be available for consultation.	- Be prepared to notify stakeholders and neighboring communities. - Be available for consultation.	- Review monitoring data, considering visual observations. - Be available for consultation.
Instrumentation (Section 8.5)	Mine Manager and Engineer of Record agree that potential for the occurrence of a failure mode exists (e.g., piping, foundation failure, overtopping) based on the observations and monitoring data available at the time.	Follow Mine Manager's instructions.	Be prepared to evacuate underground and affected areas.	Be prepared to notify stakeholders and neighboring communities.	- Notify Mine Manager and Site Owner of the interpreted potential failure mode. - Be available for consultation.

Table 34: Actions for Unusual Events

Unusual Event	Unusual Event Criteria	Actions by Site Technical Staff	Actions by Mine Manager	Actions by Site Owner (CIRNAC and PSPC)	Actions by Engineer of Record
Unusual Event – Earthquake ⁽¹⁾	- M>4.0 within 40 km 6.0>M≥5.0 within 80 km 7.0>M≥6.0 within 120 km 8.0>M≥7.0 within 200 km - M≥8.0 within 320 km	- Perform visual inspection within 24 hours. - For unusual events, determine effect of unusual event on the facility. - Inform Mine Manager of the findings.	- Notify Engineer of Record for guidance. - Notify Site Owner. - Perform visual inspection. - Be available for consultation. - Be prepared to notify stakeholders and neighboring communities.	Be available for consultation.	Be available for consultation.
Unusual Event – Storm	Rainfall >50 mm in 24 hours (1-in-10-year storm event)				

(1) USSD (2003).
M = earthquake magnitude.

10.9 Communication System and Procedures

If a condition related to a potential failure mode is observed on site (Table 14), the Mine Manager must be notified immediately, ideally via the fastest method available (e.g., emergency radio channel).

Once the Mine Manager has determined the potential risk to the facility and the associated possibility for a failure, the following emergency contacts may need to be notified as determined by the emergency response leader or designate. Table 35 provides contact numbers for emergency situations. As public relations are the responsibility of CIRNAC, contact details for various levels of government and First Nations, public broadcast institutions and media have been deliberately omitted from Table 35.

Table 35: Emergency Contact Information

Contact	Phone Number	Comments
Giant Mine Emergency Radio Channel	Repeater radio channel	Program the radio to the following: RX (receiver): 163.890 TD (transmitter): 163.170
	Underground Radio Channel	Program the radio to the following: RX (receiver): 147.325000 TD (transmitter): 173.750000
Northwest Territories Emergency Measures Office	1.867.920.2303	24-hour emergency call line
Northwest Territories 24-hour Spill Line	1.867.920.8103	
Northwest Territories Environmental Health	1.867.873.2183 or 1.837.767.9066	
Northwest Territories Fire Marshal	1.867.920.2303	
Fire Department	9-1-1	Yellowknife
Police Office	9-1-1	Yellowknife
Health and Social Services Authority	1.867.873.7224	Yellowknife

10.10 Preventive and Remedial Responses for Different Failure Modes

Preventive and remedial responses for different failure modes are described in Table 36.

Table 36: Preventive and Remedial Responses for Failure Modes

Failure Mode	Events/Conditions that may precede Failure	Preventative Maintenance	Detection Measures	Remedial Responses (after failure)
Over-topping	- Heavy rainfall/snowmelt. - Heavy winds. - Pond levels above maximum level(s). - Slope failure.	- Record instrumentation readings and check against warning levels. - Water treatment and discharge to lower pond level(s). - Pumps to reduce water levels within ponds.	Regular inspections to check water levels.	- Earthworks to re-establish dam and low permeability element. - Environment cleanup. - Pumps to reduce water levels within ponds.
Instability/ Collapse	- Seismic event. - Cracking. - Settlement. - Bulging. - Seepage. - Erosion (internal and external).	- Remedial earthwork in case of excessive erosion or detection of conditions that suggest incipient instability. - Instrumentation readings below warning levels.	Regular inspections to assess embankment stability; checking for cracks, settlement, bulging, rutting, etc.	- Earthworks to re-establish dyke. - Environment cleanup - Pumps to reduce water levels within ponds.
Piping	- Seepage, or contaminated water. - Wet spots downstream of dam toes, with or without turbid water. - Sinkholes and/or depressions. - Animal burrows.	- Water treatment and discharge to lower pond level(s). - Use only filter compatible materials for dam repairs. - Intercept/collect seepage and recycle or treat prior to environmental discharge.	- Regular inspections checking for seepage and pooled water at the toe of the dams. - Check for signs of turbid water. - Water quality testing of pooled water downstream of dams.	- Earthworks to contain seepage and piping. - Environment cleanup. - Pumps to reduce water levels within ponds. - Seepage interception and pump back systems for treatment prior to release

10.11 Available Resources

In response to an emergency, additional resources may be required, such as equipment, material, and other personnel. Types of equipment and materials likely to be required in response to an emergency, are listed below.

Materials

- Clay
- Granular crush materials of various sizes, with some example sizes of (listed below according to their maximum particle size):
 - 19 to 25 mm minus (¾ to 1-inch minus)
 - 150 mm minus (6-inch minus)
 - 300 mm minus (12-inch minus)
- Rock-fill (run-of-quarry)
- Pipe (e.g., HDPE or steel) or lay-flat hoses
- Geosynthetics (e.g., geotextile or geomembrane)

Equipment

- Bulldozer
- Excavator
- Haul trucks
- Loader
- Water pumps

Depending on the time of year and the work that is ongoing, Parsons and their subcontractors may have some of the listed equipment and materials located on site. However, procurement of equipment and materials from off site may be required. Table 37 lists the contact details for several Yellowknife based contractors who could provide equipment and materials.

Several sources or borrow material have been identified on site (Golder 2017b) that could be used. Figure 21 shows the locations of several fine grained borrow sources, where materials like clay/silt, sand, and gravel, and other fill mixtures can be obtained. At this time, only the C1 Clay Borrow area has been developed. To access other areas, development work such as access roads and topsoil stripping would be required. Coarse grained borrow sources shown in Figure 21 would require blasting and processing and therefore are not practical sources for use in an emergency.

Resources available to Giant are included in Table 37.

Table 37: Available Resources

Company	Contact	Comments
Ace Enterprises Ltd.	1.867.920.2082	Yellowknife-based contractor – specialized in earthworks
RTL Construction	1.867.873.6271	Yellowknife-based contractor – specialized in equipment rentals
Great Slave Helicopters	1.867.873.2081	Yellowknife
Matrix Helicopters	1.867.766.4953	Yellowknife
Nahanni Construction Ltd.	1.867.873.2975	Yellowknife-based contractor
Weatherby Trucking Ltd.	1.867.873.9801	Yellowknife-based contractor – specialized in earth moving




Figure 21: Potential Borrow Site

10.12 Assessment for On-site and Off-site Effects

DSR was completed in 2019 (SRK 2020). The potential effect of a dam failure is provided in Appendix C.

10.13 Emergency Preparedness and Response Plan Testing

Testing of the EPRP is completed annually. Testing includes:

- desktop drills
- site staff and drills
- wider community response drills.

The outcomes of drills are to be documented and kept on file. Any identified gaps such as missing resources, equipment, or procedures are to be rectified immediately and the EPRP updated.

Periodic testing of the emergency procedures with neighboring agencies and stakeholders is an integral part of emergency preparedness.

REFERENCES

- Andersland, O. B. and Ladanvi, B. 2004. Frozen Ground Engineering Second Edition.
- Arctic Foundations of Canada. 2020. Giant Mine Remediation Project Dam 1 – Stabilization Thermosyphon System. Elie, MB: Artic Foundations, Inc.
- CDA (Canadian Dam Association). 2013. Dam Safety Guidelines 2007, revised 2013. Library and Archives Canada, Ottawa, ON.
- CDA. 2016. Technical Bulletin: Dam Safety Reviews. Library and Archives Canada, Ottawa, ON.
- CDA. 2019. Technical Bulletin: Application of Dam Safety Guidelines to Mining Dams. Library and Archives Canada, Ottawa, ON.
- CIRNAC (Crown-Indigenous Relations and Northern Affairs Canada) and Government of the Northwest Territories (GNWT). 2021. Closure and Reclamation Plan – Giant Mine Remediation Project. March 2021.
- CIRNAC and GNWT. 2022. Giant Mine Remediation Project, Standard Operating Procedures and QA/QC Plan for Effluent and Water Sampling. Rev 3.0 September 2022.
- CIRNAC and GNWT. 2023. Giant Mine Remediation Project. Water Management and Monitoring Plan. Version 4.0. August 2023.
- Deton'Cho / Nuna (Deton'Cho / Nuna Joint Venture). Giant Mine ETP Operating Manual – 2008. SOP# - ETP – 01. February 2008.
- Geocon (Geocon INC.). 1975. Geotechnical Study – Phase II Tailings Disposal System, Giant Yellowknife Mines Limited, Yellowknife, Northwest Territories. Prepared for Falconbridge Nickel Mines Limited. Reference No. V8188. Dated April 8, 1975.
- Geological Survey of Canada. 1998. Living with frozen ground, a field guide to permafrost zone in Yellowknife, Northwest Territories. Ottawa ON: Canadian Government Publishing. 1998.
- Golder (Golder Associates Ltd.). 2013. 2012 Geotechnical Inspection of Giant Mine Tailings Dams. Prepared for Deton Cho / Nuna Joint Venture Ltd. Golder Ref. No. 1214270017-001-R-Rev0-2000. Dated February 27, 2013.
- Golder. 2017a. Giant Mine – Baker Creek Flood Hazard Assessment. Prepared for GMRP by Golder. November 2017.
- Golder. 2017b. Supplemental Borrow Source Identification Report. Prepared for Public Works and Government Services Canada. Golder Ref. No. 1313770115-061-R-Rev0-22000. February 16, 2017.
- Golder. 2019. Dam 1 Engineering Assessment. Prepared for Public Services and Procurement Canada. Golder Ref. No. 1313770115-184-R-Rev0-31000. March 14, 2019.
- Golder. 2020a. Giant Mine Remediation Project: Bathymetric Surveys of the North Pond, Northwest Pond, and Polishing Pond. Prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-042-TM-Rev0-34000. February 25, 2020.

- Golder. 2020b. Giant Mine Remediation Project: Dams, Stability Geotechnical Investigation Factual Report. Prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-031-R-Rev0. July 10, 2020.
- Golder. 2021a. 2020 Annual Geotechnical Inspection of Dams. Prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-101-R-Rev0-45000. May 25, 2021.
- Golder. 2021b. Dam 1 Remediation – Construction Record Report, Giant Mine Remediation Project. Prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-211-R-Rev0-41000A. July 23, 2021.
- Golder. 2022a. 2022 Annual Geotechnical Inspection of Dams, Giant Mine Remediation Project. Prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-532-R-Rev0-45000B. December 12, 2022.
- Golder. 2022b. Giant Mine Remediation Project Splitter Dyke slope stability assessment. Draft report prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-417-TM-RevA-45000B. May 4, 2022.
- Golder. 2022c. Geotechnical analysis and evaluation to support the Operation, Maintenance, and Surveillance manual update. Technical Memorandum prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-416-TM-Rev0-45000B. September 12, 2022.
- Golder. 2022d. Giant Mine Remediation Project. 2021 Geotechnical Investigation – Factual Report. Prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-323-R-Rev0-35000C. March 7, 2022.
- Hivon, E.G. and Dego, D.C. 1993. Distribution of saline permafrost in the Northwest Territories, Canada. Canadian Geotechnical Journal, 30: 506-514.
- John A. Brophy. 1991. Satellite Geological Mapping of Yellowknife Volcanic Belt. Arctic, Volume. 44. SUPP. 1 (1991) P. 102-107. [Accessed December 28, 2017]. <https://pubs.aina.ucalgary.ca/arctic/Arctic44-S-102.pdf>
- MAC (Mining Association of Canada). 2021a. Developing an Operation, Maintenance and Surveillance Manual for Tailings and Water Management Facilities, Version 2.1. March 2021.
- MAC. 2021b. A Guide to the Management of Tailings Facilities, Version 3.2. March 2021.
- McGill Redpath Museum. 2017. The Canadian Biodiversity Web site. Taiga Shield. [Accessed 28 December 2017]. <http://canadianbiodiversity.mcgill.ca/english/ecozones/taigashield/taigashield.htm>
- MVLWB (Mackenzie Valley Land and Water Board). 2021. Mackenzie Valley Resource Management Regulations. Type A Water Licence MV2007L8-0031. February 26, 2021.
- NHC (Northwest Hydraulic Consultants Ltd.). 2007. Baker Creek Channel Survey and Numerical Hydraulic Modelling. Prepared for SRK Consulting, Vancouver BC. March 2007.
- NRC (National Research Council). 2020. 2020 National Building Code of Canada.

Ollerhead (Ollerhead & Associates Ltd.). 2006. DTM QA, Best Fit Surface Transformation: Transformation Equations, Surface and Underground Control Coordinates. June 19, 2006.

Parsons (Parsons Inc.). 2022. Standard Operating Procedure, Ice Buildup and Freshet Management, Giant Mine Remediation Project. Prepared for Public Services and Procurement Canada. Rev 2. Revision Date 8 November 2022.

Parsons. 2024. Emergency Management and Spill Response Plan. Giant Mine Remediation Project. Yellowknife, NWT. Prepared for Public Services and Procurement Canada. June 6, 2024.

Silke R. 2009. The Operation History of Mines in the Northwest Territories.

SRK (SRK Consulting (Canada) Inc.) 2005. Giant Mine Remediation Plan – Tailings and Sludge Containment Areas. Prepared for Department of Indian Affairs and Northern Development. December 2005.

SRK. 2008. B2 Dam Reconstruction Design and As-built Report. Prepared for Indian and Northern Affairs Canada, Giant Mine Remediation Project. March 2008.

SRK. 2020. Giant Mine 2019 Dam Safety Review Report. Prepared for Crown-Indigenous Relations and Northern Affairs Canada. December 2020.

USSD (United States Society on Dams). 2003. Guidelines for Inspection of Dams After Earthquakes. March 2003.

WSP (WSP Canada Inc.). 2023. Giant Mine remediation Project, 2023 OMS Manual Update – Hydrological Assessment. Internal Technical Memorandum No. 18102211-649-TM-RevA-45000B. March 2023.

WSP. 2024a. Giant Mine Remediation Project. Mill Pond Structure Geotechnical Assessment. Prepared for Public Services and Procurement Canada. WSP Ref. No. 18102211-714-TM-Rev0-45000D. July 3, 2024.

WSP. 2024b. Summary of Datalogger and Instrumentation Installations at Dam 1 and Northwest TCA Dams. Prepared for Public Services and Procurement Canada. WSP Ref. No. 18102211-780-TM-Rev0-45000D. July 3, 2024.

APPENDIX A

Responsibility of Updating OMS

APPENDIX A – Responsibility of Updating OMS Manual

GMRP – OMS Manual (Version G)

OMS Manual – Table of Contents			Section Author		
Section No.		Section Title	Parsons	WSP	Overlap
1.0		Objective	-	◆	-
2.0		Document User Guide	◆	-	-
3.0		Roles and Responsibilities	-	-	◆
	3.1	Organization Chart	-	-	◆
	3.2	Responsibilities and Contact Information of Formally Assigned Individuals	-	-	◆
	3.3	Requirements for Competency and Training	-	◆	-
	3.4	Site Personnel	◆	-	-
	3.5	Responsibilities for Managing Change	◆	-	-
4.0		Site Facilities Description	<i>n/a</i>	<i>n/a</i>	<i>n/a</i>
	4.1	Site Overview	-	◆	-
	4.2	Tailings Transportation and Deposition	-	◆	-
	4.3	Access Roads and Security	◆	-	-
	4.4	Dam Consequence Classification	-	◆	-
5.0		Site Reference Data	<i>n/a</i>	<i>n/a</i>	<i>n/a</i>
	5.1	Applicable Guidance and Regulatory Requirements	-	-	◆
	5.2	Mine Operating Manuals	◆	-	-
	5.3	Horizontal Coordinate System and Maps	◆	-	-
	5.4	Regulatory Framework for Dam Safety	-	◆	-
6.0		Site Conditions	<i>n/a</i>	<i>n/a</i>	<i>n/a</i>
	6.1	Topography	-	◆	-
	6.2	Geology	-	◆	-
	6.3	Vegetation and Wildlife	-	◆	-
	6.4	Climate	-	◆	-
	6.5	Water Balance	-	◆	-
	6.6	Permafrost	-	◆	-
	6.7	Seismicity	-	◆	-
7.0		Operations	-	◆	-
	7.1	Water Management	◆	-	-
	7.2	Water Treatment	◆	-	-
	7.3	Pond Storage Capacity	-	◆	-
	7.4	Flood Storage Capacity	-	◆	-
	7.5	Minimum Freeboards	-	◆	-
	7.6	Pond Water Levels and Warning Levels	-	◆	-
	7.7	Environmental Protection	◆	-	-
	7.8	Change Management	◆	-	-
	7.9	Documentation	◆	-	-
	7.10	Reporting and Documentation	◆	-	-

APPENDIX A – Responsibility of Updating OMS Manual

GMRP – OMS Manual (Version G)

OMS Manual – Table of Contents			Section Author		
Section No.		Section Title	Parsons	WSP	Overlap
8.0		Surveillance	<i>n/a</i>	<i>n/a</i>	<i>n/a</i>
	8.1	Objectives	-	◆	-
	8.2	Training Requirements	◆	-	-
	8.3	Surveillance Procedures	-	◆	-
	8.4	Visual Inspection	-	◆	-
	8.5	Instrumentation	-	◆	-
	8.6	Water License Sampling and Testing	◆	-	-
	8.7	Survey and Bathymetry	-	◆	-
	8.8	Weather Stations	-	◆	-
	8.9	Annual Geotechnical Inspections of Dams	-	◆	-
	8.10	Frequency of Dam Safety Reviews	-	◆	-
	8.11	Event Driven Procedures	-	◆	-
	8.12	Triggers for Change of Operations	-	◆	-
	8.13	Documentation and Reporting	-	-	◆
9.0		Maintenance	<i>n/a</i>	<i>n/a</i>	<i>n/a</i>
	9.1	Objectives	-	◆	-
	9.2	Inventory of Components Requiring Maintenance	◆	-	-
	9.3	Maintenance Schedule and Triggers	◆	-	-
	9.4	Routing and Preventative Maintenance	◆	-	-
10.0		Emergency Preparedness and Response Plan	◆	-	-
	10.1	Requirements of Legislation, Codes of Practice, Commitments, etc.	-	◆	-
	10.2	Identification of all Jurisdictions, Agencies and Individuals Involved in Preparedness Response	-	-	◆
	10.3	Training Requirements	◆	-	-
	10.4	Public Relations Plan	-	-	◆
	10.5	Emergency Response Plans	-	-	◆
	10.6	Incident Investigation Procedure	◆	-	-
	10.7	Call-out Procedure for Emergency Response	◆	-	-
	10.8	Exceedance of Caution Warning Levels and Corresponding Actions	-	◆	-
	10.9	Communication System & Procedures	◆	-	-
	10.10	Preventive and Remedial Responses to Failure Modes	-	◆	-
	10.11	Available Resources	◆	-	-
	10.12	Assessment for On-site and Off-site Effects	-	◆	-
	10.13	EPRP Testing	◆	-	-

Note: ◆ = major responsibility contributing to the section. If it is an overlap, it means both Parsons and WSP contribute to the section.
 - = minor or no responsibility contributing to the section. n/a = not applicable (implies only a section title).

APPENDIX A – Responsibility of Updating OMS Manual

GMRP – OMS Manual (Version G)

OMS Manual – Appendices		Appendix Author		
Appendix No.	Appendix Title	Parsons	WSP	Overlap
A	Responsibility of Updating OMS Manual	-	-	◆
B	Dam Geometry & Foundation	-	◆	-
C	Dam Consequence Classifications	-	◆	-
D	Climate Data	-	◆	-
E	Water Balance	-	◆	-
F	Inspection Forms	-	-	◆
G¹	Instrumentation Installation Details and Instrument Calibration Certificates	-	◆	-

Note: ◆ = major responsibility contributing to the appendix. If it is an overlap, it means both Parsons and WSP contribute to the appendix. - = minor or no responsibility contributing to the appendix.

1) Contents are generally produced from third party.

APPENDIX B

Dam Geometry and Foundation

APPENDIX B – DAM OVERVIEW

GMRP – OMS Manual (Version G)

B-1 Original Tailings Containment Area

Between the early 1950's and the late 1980's, tailings were deposited to the north of the mill within an area referred to as the Original TCA. Prior to tailings deposition, the approximate area of the Original TCA comprised of two lakes (Bow Lake and Oran Lake) as well as several smaller ponds and bogs (SRK 2005). The Original TCA currently comprises of five separate ponds: Polishing Pond, Settling Pond, North Pond, Central Pond and South Pond.

Dams

Tailings and water within the Original TCA are retained by thirteen earthfill dams. Dams 1, 3, 8, 9, 11, and 12 are external tailings and/or water retention structures. Downstream of these areas are either the naturally occurring environment, land disturbed by mining, or seepage collection dams.

Dams 3C, 3D, and 7, although external, were constructed to collect and manage seepage from the Original TCA. Dams 2, 4 and 5 are internal dams that are contained within the original TCA. Dyke 6 is an internal dyke or causeway that was constructed over tailings.

A rockfill causeway, called Splitter Dyke, was constructed in the 1980's to form the present day Polishing and Settling Ponds. The dyke was constructed of mine muck (i.e., blasted run of mine waste, typically consisting of sand and gravel sized particles). The dyke was constructed to increase the retention time of treated water in the Settling Pond to improve water quality. In previous operations treated water was allowed to seep through the dyke and into the Polishing Pond. However current operations use pumps to transfer water from the Settling Pond to the Polishing Pond. The dyke is underlain by water treatment sludge and tailings, as such, fill materials placed on the upstream and downstream slopes were typically placed without compaction.

In November 2015, a small dyke, referred to as the Containment Berm was constructed to contain sludge and tailings excavated from the Settling Pond with the aim of increasing the storage capacity of the Settling Pond. The berm was constructed to the east of the Settling Pond and was constructed of a granular fill core placed to a height of approximately 1 m, with upstream filter zones and non-woven geotextile. Sludge in Settling Pond and part of the Containment Berm was partially excavated in 2022 to increase storage capacity of the Settling Pond.

Construction History

Mine construction started in 1937 and mining operations in 1948. Between the early 1950's and the late 1980's, tailings were deposited in the Original TCA.

- **1973:** Until at least 1973, tailings were deposited within two pre-existing lakes and were retained by Dams 1, 2, 3, and a portion of Dam 4 (Dam 4A), within the area of the present day Polishing, Settling, North, and Central Ponds (Golder 2005).
- **1965 to 1975:** Dams 3C and 3D were constructed between 1965 and 1975 to intercept seepage from Dam 3.

APPENDIX B – DAM OVERVIEW

GMRP – OMS Manual (Version G)

- **1974:** Dams 1, 2, 3, and a portion of Dam 4 (Dam 4A) were raised to provide additional storage. At this time these dams were also lined with clay and a granular filter installed on the upstream slope. (Golder 2005).
- **1980 to 1984:** Dams 4 (Dams 4B and 4C) through 10 were constructed and Dams 2 and 3 raised to provide further tailings storage (Geocon 1983). Dam 11 was constructed to create the South Pond.
- **1988 to 1990:** Tailings deposition in the Original TCA generally ceased following the construction of the Northwest TCA. Between 1988 and 1990, a Tailings Retreatment Plant was used to reprocess tailings from the North and Central Ponds for residual gold (SRK 2007). Effluent from the Tailings Retreatment Plant was discharged in the Northwest TCA.
- **1999:** Since the cessation of milling on site in 1999, Dam 1 has been raised in order to account for ongoing settlement of the dam crest and to maintain water storage capacity and freeboard.
- **2002:** Dam 1 was raised by approximately 1.5 m.
- **2020:** Thermosyphons were installed along the Dam 1 crest (2021a)
- **2022:** Dam 1 was raised by approximately 1.7 m along the dam upstream crest (Golder 2022a).

Dam Geometry and Foundations

A technical memo was issued by Golder (Golder 2021b) highlighting the dam dimensions mainly obtained from dam drawings based on 2018 LiDAR survey, and 2019 on-ground survey as part of site investigations for dams. These dam dimensions are to be used as reference moving forward. Details of dam geometry and foundation conditions are presented in Table B-1.

Site-specific data on the presence or extent of permafrost in the foundations of dams or the TCA boundaries, where encountered during geotechnical investigations, is provided in Figure B-1 and Figure B-2.

Table B-1: Original Tailings Containment Area: Overview of Dams

Dam/Dyke	Length ^(a) (m)	Height ^(a) (m)	Crest Width ^(a) (m)	Foundation / Construction ^{(b), (c)}
Splitter Dyke	230	5	4	■ Rockfill dyke over tailings
Dam 1	200	10	7 to 20	■ Foundation included, depending on location (Golder 2018): ■ tailings, ■ Organics, ■ Frozen soil and visible ice (up to 9.6 m thick) ■ Fluvial sand and gravel, ■ Plastic and low plasticity clay ■ Rockfill dam constructed with an upstream clay blanket
				■ Raised sections include filter zone of sand and gravel

APPENDIX B – DAM OVERVIEW

GMRP – OMS Manual (Version G)

Table B-1: Original Tailings Containment Area: Overview of Dams

Dam/Dyke	Length ^(a) (m)	Height ^(a) (m)	Crest Width ^(a) (m)	Foundation / Construction ^{(b), (c)}
Dam 2	470	14	15 to 30	- Foundation included 3 m of tailings over 1 m of peat over 4 to 6 m of silty clay at the centre of longitudinal section - Permafrost encountered between 14 and 15.2 m deep - Rockfill dam constructed with an upstream clay blanket and core - Raised sections include filter zone of sand and gravel - Upstream toe berm included for stability
Dam 3	460	15	7 to 12	- Founded on variable depths of peat over silty clay over silt at different cross-sections. - Upstream clay seal constructed - West side includes a toe berm - Last raises constructed of silty clay using upstream method - Raised sections include filter zone of sand and gravel
Dam 3C	60	1.5	5 to 6	- Foundation included 10 m of silty clay with visible ice over bedrock - Permafrost encountered at depth of 7 m - Rockfill structure with clay and tailings slimes on upstream
Dam 3D	60	4	5 to 6	- Foundation included silty sand or sandy till - Organics removed prior to construction - Rockfill dam with clay zone and granular filter on upstream slope
Dam 4	215	14 ^(d)	14	- Foundation included 1 to 5 m of silty clay over some silt with no visible ice over bedrock - No frozen soil was encountered in foundation during 2019 drillings - Rockfill dam constructed in 3 m lifts using downstream technique - Clay placed on upstream side in 1979
Dam 5	75	13 ^(d)	7.5	- Founded on variable depths of peat, silty clay, silt and sand - Upstream clay barrier and downstream clay cut-off constructed in 1981
Dyke 6	280	9	6 to 20	- Foundation included tailings over peat and soft clay over bedrock - Frozen tailings were known to exist in the foundation of the dyke (Geocon 1975). - Dam does not include a zone of low hydraulic conductivity

APPENDIX B – DAM OVERVIEW

GMRP – OMS Manual (Version G)

Table B-1: Original Tailings Containment Area: Overview of Dams

Dam/Dyke	Length ^(a) (m)	Height ^(a) (m)	Crest Width ^(a) (m)	Foundation / Construction ^{(b), (c)}
Dam 7	25	3	3	■ Foundation included silty clay over bedrock ■ No permafrost encountered ■ Silty clay core constructed ■ No toe drain constructed
Dam 8	110	3	4 to 5	■ Foundation was clay and bedrock (Geocon 1983). ■ Upstream clay zone placed in 1980. Clay blanket overlain by riprap was added to upstream side in 1981. ■ Modifications to flatten slopes completed in 1981.
Dam 9	95	11	4 to 7	■ Foundation was bedrock ■ Downstream shell of rockfill with upstream zone of silt or clay
Dam 10	50	3	5	■ Constructed on rockfill
Dam 11	465	18.5	15	■ Foundation included 3 to 4 m of silty clay over bedrock ■ Constructed with clay core ■ Mid and lower level berms on west and central sections
Dam 12	80	5	4	■ Foundation may include bedrock, clay or mine waste, depending on the location ■ Dam may have been constructed with mine rockfill with no seepage barrier

(a) Source: Golder 2021b.

(b) Source: Golder 2021c.

(c) Source: SRK 2020.

(d) It is the dam height after south pond tailings are removed.

B-2 Northwest Tailings Containment Area Construction History and Dam Geometry

Following the undertaking of a major tailings storage expansion project, the construction of Dams 21 (A through D) and Dam 22A and B, was initiated in 1986 to form the Northwest TCA (Golder 2005). Between 1986 and 1999 tailings were deposited in the Northwest TCA.

APPENDIX B – DAM OVERVIEW

GMRP – OMS Manual (Version G)

Dams

The six dams of the Northwest Containment Area are constructed of rockfill and include low permeability elements in the form of a clay core along with a granular filter, placed along the upstream slope. According to available design drawings, the clay core was designed to be keyed into bedrock (Geocon 1987). The downstream slopes of these dams are as steep as 1H:1V, but are typically buttressed by rockfill placed at the downstream toe. From 1986 to 1999, most tailings produced by the Mill and Tailings Retreatment Plant at Giant mine were deposited in the Northwest TCA.

Construction History

- **1986:** Construction of Dams 21 (A through D) and Dam 22A and B, was initiated to form the Northwest TCA (Golder 2005).
- **1986 to 1999:** Most tailings were deposited in the Northwest TCA, from both the mill and from the Tailings Retreatment Plant.

Dam Geometry and Foundations

Details of dam geometry and foundation conditions are presented in Table B-2.

Site-specific data on the presence or extent of permafrost in the foundations of dams or the TCA boundaries, where encountered during geotechnical investigations, is provided in Figure B-1.

Table B-2: Northwest Tailings Containment Area: Overview of Dams

Dam/Dyke	Length ^(a) (m)	Height ^(a) (m)	Crest Width ^(a) (m)	Foundation/Construction ^(b)
21A	100	8	15	■ Foundation included a layer of 0.5 m peat, 1.5 m silty clay and 0.3 m silt over bedrock. ■ Foundations were frozen during 2019 geotechnical investigation.
21B	350	20	15	■ Foundation included varying depths of peat followed by silty clay and clayey silt, followed by sand over bedrock. ■ Foundations were found frozen during 2019 geotechnical investigation, except for one borehole. ■ Some ice was observed within the rockfill as well. ■ No records of construction available
21C	300	14	15	■ Foundation included varying depths of silty clay, followed by silt and sand over bedrock. ■ Foundation was frozen and ice particles were observed in rockfill as well during 2019 geotechnical investigation. ■ Downstream slope has a single bench at mid height

APPENDIX B – DAM OVERVIEW

GMRP – OMS Manual (Version G)

Table B-2: Northwest Tailings Containment Area: Overview of Dams

Dam/Dyke	Length ^(a) (m)	Height ^(a) (m)	Crest Width ^(a) (m)	Foundation/Construction ^(b)
21D	460	13	15	■ Foundation included varying depths of peat, silty clay, followed by silt over bedrock. ■ Organic silt removed prior to construction ■ Downstream slope has a single bench at mid height ■ Dam raise was constructed in 2003. It increased clay core by 0.6 m, with rockfill shell on upstream slope extended. ■ Foundation was frozen and ice particles were observed in rockfill as well during 2019 geotechnical investigation.
22A	275	8	15	■ Foundation included varying depths of peat, silty clay, followed by silt and sand over bedrock. ■ Frozen soils were encountered in dam's foundation soils as well as rockfill, excluding in organic layer at downstream bench.
22B	175	11	15	■ Foundation included a discontinuous organic layer, topsoil underlain by varying depth of silty clay and silt over bedrock. A small deposit of encountered sand was interpreted to be discontinuous. Frozen soil was encountered in rockfill and dam's foundation, however not up to the top of bedrock.

(a) Source: Golder 2021b.

(b) Source: Golder 2021c.

B-3 B2 Dam Construction History and Dam Geometry

In order to divert Baker Creek and to eventually develop the B2 Pit, the B2 Dam was constructed in the 1980's. The dam was not constructed as an engineered structure and has had a history of poor performance, which includes dam breach and overtopping events (SRK 2008). In 2006, a significant seep of muddy water was observed to be emanating from the toe of the dam and was observed to flow onto the B2 Pit wall.

In response to the 2006 seepage event, the B2 Dam was reconstructed during the winter of 2008 using fill materials, non-woven geotextile, and bituminous liner. With Baker Creek frozen, a key trench was excavated at the upstream toe and creek bed and the liner was placed along the downstream slope, across the key trench, and in some locations, up the opposite slope of the creek bed (SRK 2008).

In 2022, a rockfill buttress was constructed at B2 Dam downstream side (Golder 2022b). This is to improve the slope stability of the downstream slope of the dam to meet CDA Guidelines (2013) under static loading condition.

Dam Geometry and Foundations

Details of dam geometry and foundation conditions are presented in Table B-3.

APPENDIX B – DAM OVERVIEW

GMRP – OMS Manual (Version G)

Site-specific data on the presence or extent of permafrost in the foundations of dams or the TCA boundaries, where encountered during geotechnical investigations, is provided in Figure B-1.

Table B-3: Overview of Dam B2

Dam/Dyke	Length ^(a) (m)	Height ^(a) (m)	Crest Width ^(a) (m)	Foundation/Construction ^(c)
B2	120	13	10 to 15	■ Foundation includes bedrock mainly overlain by 10 m thick silty clay. A 5 m thick silt and a discontinuous 0.1 m thick layer organics was encountered at some locations. ■ Frozen conditions were observed locally at some boreholes. ■ Records of construction available in SRK (2008)

(a) Source: Golder 2021b.

(b) Source: Golder 2021d.

B-4 Other Dams

A description of the other, minor, dams at the Giant mine site are included below for reference. Management of these dams is not included as part of this OMS manual.

M&M Dam

During the winter of 2011, Baker Creek froze to the creek bed. During the subsequent freshet (Spring 2011), the presence of anchored ice resulted in the upper Baker Creek diverting away from the original creek alignment. The M&M Dam was constructed to retain the flow of upper Baker Creek if a similar condition were to occur in the future. M&M Dam has an approximate maximum height of 1 m, crest length of 20 m and crest width of 3 m.

DWC Dam

Anecdotal evidence indicates that the DWC Dam was constructed sometime in the 1970's or 1980's to prevent surface water run-off from flowing into the A2 Pit. The dam retains water within a small bog. A high-density polyethylene pipe penetrates the dam with an intake located on the upstream slope. The pipe drains water from the pond for discharge east of the A2 Pit in the general vicinity of the outlet from Baker Creek into Yellowknife Bay. DWC Dam has an approximate maximum height of 2 m, crest length of 30 m, and width of 2 m.

C1 Clay Borrow Dam

The C1 Clay Borrow area is located due west of the mine offices (known as C-Dry). Soil was excavated from the area for use in on-going rehabilitation projects over several years. However, disturbance of this area has resulted in turbid surface water runoff, particularly during the spring freshet and high rainfall events. To manage the turbid water, prior to entering Baker Creek, two ponds were excavated in the borrow area to retain surface water runoff until suspended solids had settled. As an additional measure, a small dam, approximately 1 m high, was constructed downstream of one of the ponds as a freeboard structure. C1 Clay Borrow Dam has an approximate crest length of 50 m and crest width of 3 m.

APPENDIX B – DAM OVERVIEW

GMRP – OMS Manual (Version G)

Mill Pond Structure

The Mill Pond Structure is located west of the former mill/roaster complex, along the previous alignment of the Ingraham Trail highway which was re-routed outside of the Site boundary in 2014. Historically, the Mill Pond was used for disposal of wastes from the mill/roaster complex.

The Mill Pond Structure forms a barrier between the existing Mill Pond and Baker Creek. Baker Creek is located on the west side of the Mill Pond Structure, referred to as the downstream side of the structure. The Mill Pond, containing contaminated sediment and impacted water, is located on the east side of the Mill Pond Structure, referred to as the upstream side of the structure.

The Mill Pond Structure has an approximate crest length of 560 m and crest width of 9 m. The downstream slope ranges between about 1.8H:1V near the north end and 6H:1V near the south end of the structure. The upstream slope of the structure is generally more consistent and ranges between about 2H:1V and 3H:1V. As the Mill Pond Structure was constructed as a highway embankment rather than a water retention structure, the crest elevation is variable along its length. In addition, differential subsidence has occurred since the highway re-routing in 2014 (WSP 2024).

GMRP – OMS Manual (Version G)



APPENDIX B – DAM OVERVIEW

GMRP – OMS Manual (Version G)




Figure B-2: Dam 1 Overview – Frozen Soil Locations (from Golder 2018)

APPENDIX B – DAM OVERVIEW

GMRP – OMS Manual (Version G)

B-5 References

- CDA (Canadian Dam Association). 2013. Dam Safety Guidelines 2007, revised 2013. Library and Archives Canada, Ottawa, ON.
- Geocon (Geocon INC.). 1975. Geotechnical Study – Phase II Tailings Disposal System, Giant Yellowknife Mines Limited, Yellowknife, Northwest Territories. Prepared for Falconbridge Nickel Mines Limited. Reference No. V8188. Dated 8 April 1975.
- Geocon. 1983. Geotechnical Investigation – Existing Tailings Retention Structures. Prepared for Giant Yellowknife Mines Limited. Reference No. V8527C. Dated August 1983.
- Geocon. 1987. Detailed Design Study – Drawings No. D319, D320, D321. Dated 27 May 1987. Golder Associates Ltd. (Golder). 2005. Summary Geotechnical Aspects of Giant Mine Tailings Dams. Report prepared for SRK Consulting Ltd. Golder Doc. No. 03 1413 009.
- Golder (Golder Associates Ltd.). 2018. 2018 Annual Geotechnical Inspection of Dams – Giant Mine Remediation project. Prepared for PSPC. Golder Ref. No. 18102211-002-R-RevA-33000. 3 August 2018.
- Golder. 2021a. Dam 1 Remediation – Construction Record Report, Giant Mine Remediation Project. Prepared for Public Services and Procurement Canada. Golder Ref. No 18102211-211-R-Rev0-41000A. 23 July 2021.
- Golder. 2021b. Giant Mine Remediation Project – Review of Dam Dimension. Prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-329-TM-Rev0-45000A. 15 December 2021.
- Golder. 2021c. 2020 Annual Geotechnical Inspection of Dams. Prepared for Public Services and Procurement Canada. Golder Ref. No 18102211-101-R-Rev0-45000. 25 May 2021.
- Golder. 2021d. Giant Mine Remediation Project – B2 Dam Slope Stability Assessment Report. Prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-141-R-Rev0-34000. 29 January 2021.
- Golder. 2022a. Dam 1 Raise – Construction Record Report, Giant Mine Remediation Project. Prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-506-R-Rev0-41000C. 24 November 2022.
- Golder. 2022b. Giant Mine Remediation Project – B2 Dam Slope Remediation Construction Record. Prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-507-TM-Rev0-41000C. 7 November 2022.
- SRK (SRK Consulting Canada Inc.). 2005. Giant Mine Remediation Plan: Tailings and Sludge Containment Areas, Giant Mine Remediation Project. Document prepared for Department of Indian Affairs and Northern Development. SRK Project Number 1CP001.037. December 2005.
-

APPENDIX B – DAM OVERVIEW

GMRP – OMS Manual (Version G)

SRK. 2007. Giant Mine Remediation Plan, Giant Mine Remediation Project, Yellowknife, NWT. Report submitted to Indian and Northern Affairs Canada. July 2007

SRK. 2008. B2 Dam Reconstruction Design and As-built Report. Prepared for Indian and Northern Affairs Canada, Giant Mine Remediation Project. Dated March 2008.

SRK. 2020. Giant Mine 2019 Dam Safety Review Report. Prepared for Crown-Indigenous Relations and Northern Affairs Canada. December 2020.

WSP (WSP Canada Inc.). 2024. Giant Mine Remediation Project. Mill Pond Structure Geotechnical Assessment. Prepared for Public Services and Procurement Canada. WSP Ref. No. 18102211-714-TM-Rev0-45000C. 3 July 2024

APPENDIX C

Dam Consequence Classifications

APPENDIX C – DAM CONSEQUENCE CLASSIFICATIONS

GMRP – OMS Manual (Version G)

C-1 Introduction

There are a total of 23 dams at Giant Mine that have a dam consequence classification. The primary basis for the dam classifications is from a 2015 desktop review (Golder 2015). A Dam Break Analysis (DBA) was completed in 2020 for 10 dams, located in the Original and Northwest Tailings Containment Areas (TCAs) at Giant Mine (Golder 2021). An update to the consequence classification of 10 dams (Dam 1, Dam 2, Dam 3, Dam 11, Dam 21A, Dam 21B, Dam 21C, Dam 21D, Dam 22A and Dam 22B) was made following the results obtained in the 2020 DBA and 2021 AGI site visit.

C-2 Dam Consequence Classifications

Dam classifications were previously governed by Guidelines of CDA 2013, as per requirements of the water license. However, more recently, Global Tailings Review (GTR 2020), published the Global Industry Standard on Tailings Management (GISTM) which also provided dam consequence classification. While GISTM is closely aligned with CDA (2013), it does provide more detailed, and in some cases quantitative guidelines for the assessment of dam consequence guidelines. In cases where the GISTM provided useful additional guidance to that provided in CDA (2013), the GISTM guidance was used to inform Golder's assessment of consequence classifications (Golder 2021). For dams with multiple consequences, the consequence classification considered to drive the dam's current classification is shown in **bold text**.

Table C-1 summarizes the updated dam consequence classification and the supporting rational.

APPENDIX C – DAM CONSEQUENCE CLASSIFICATIONS

GMRP – OMA Manual (Version G)

Table C-1: Rational for Dam Consequence Classifications as per CDA (2013)

Dam	Potential Dam Failure Consequence/s	Classification	Classification Rationale
B2	May flood B2 Pit and underground workings via Pit B2 Portal which may: ■ Expose underground staff to risk of injury or fatality. ■ Damage the underground dewatering pumps which are important in preventing flooding of the Arsenic chambers.	Very High	Infrastructure and economics: Very high economic losses affecting important infrastructure or services (e.g., highway, industrial facility, storage facilities for dangerous substances), or employment
21A	Tailings may flow over the Ingraham Trail Highway which may: ■ Expose commuters on the highway to risk of injury or fatality. ■ Debris could flow north along Ingraham Trail as well. ■ Adversely impact water treatment. ■ Flooding of B3 pits would result in debris flowing into the underground mine via the portals. ■ Flooding of C1 and A2 pit. Some flow into B1 pit. ■ Debris could flow into Settling and Polishing Ponds, triggering Dam 1 failure.	Very High	Potential loss of life: 10-100. Infrastructure and economics: Very high economic losses affecting important infrastructure and services (e.g., highway, industrial facility, storage facilities for dangerous substances), or employment.
21B	Tailings may flow over the Ingraham Trail Highway and into Baker Creek which may: ■ Expose commuters on the highway to risk of injury or fatality. ■ Further contaminate Baker Creek ■ Adversely impact water treatment ■ Flooding of B2 and B3 pits would result in debris flowing into the underground mine via the UBC and 1-38 portals. ■ Flooding of B1, C1 and A2 pits.		
21C			
1	May flood B3 Pit and underground workings via 1-38 Portal which may: ■ Expose underground staff to risk of injury or fatality. ■ Adversely impact water treatment. ■ Flow into C1 pit is a possibility.	High	Loss of life: 10 or fewer.
2	Tailings may flow into the Polishing Pond which may: ■ Compromise the stability of Dam 1. This may lead to flooding of B3 Pit and underground workings via 1-38 Portal, and in turn expose the underground staff to risk of injury or fatality. ■ Adversely impact water treatment. ■ Some flow into B1 pit is a possibility. ■ Flow into C1 pit and consequently A2 pit is a possibility.		Loss of life: 10 or fewer if Dam 1 stability is compromised.
21D	Tailings may flow across the Vee Lake road, primarily into Trapper Lake, but also reaches Gar Lake. Debris flow from Trapper Creek into Baker Creek: ■ Expose travelers on the road to Vee Lake to risk of injury or fatality. ■ Further contaminate Trapper Lake and Trapper Creek. ■ Adversely impact water treatment. ■ Debris flow reaches all the way to Yellowknife Bay.	High	Loss of life: 10 or fewer
22A	Tailings may flow across the Vee Lake road, primarily into Trapper Lake, but also reaches Gar Lake. Debris flow from Trapper Creek into Baker Creek: ■ Expose travelers on the road to Vee Lake to risk of injury or fatality. ■ Further contaminate Trapper Lake and Trapper Creek. ■ Adversely impact water treatment. ■ Some plume of debris likely to reach Yellowknife Bay		
22B			
3	Hypothetical breach appears unlikely to result in flow failure because: ■ Ponding water at least 250 m away. ■ In case of breach, material would flow downstream but majority of debris unlikely to reach Yellowknife Bay.	Significant	Environmental and cultural values: No significant loss or deterioration of habitat. Potential contamination of livestock/ fauna water supply with no health effects.
11	Hypothetical breach appears unlikely to result in flow failure because: ■ Ponding water more than 300 m away. ■ Debris from the failure could reach the shore of Yellowknife Bay.		
Mill Pond Structure	Substantial water storage potential could potentially result in incremental loss of environmental and cultural values in the event of a breach.		Environmental and cultural values: Loss of marginal habitat only. Restoration or compensation in kind highly possible.
3C	Dams retaining tailings with no water on surface. Liquefaction potential considered low (SRK 2007). Limited impact expected downstream.	Low	Environmental and cultural values: Minimal short-term loss. No long term loss.
3D			
4			
5			
6			
7			
8			
9			
12	Dam retaining tailings with minor water on surface.	Low	Environmental and cultural values: minimal short-term loss. No long term loss. Infrastructure: low economic loss to operation.
Splitter Dyke	Breach would result in flow of water and sludge into Polishing Pond. The Polishing Pond has a larger surface area than the Settling Pond and should therefore be of sufficient size to contain failure if the Settling Pond is operated at or below its maximum operating level.	Low	Infrastructure and economics: Low economic losses; area contains limited infrastructure or service.
DWC Dam	Water (surface water runoff) would be contained within A2 Pit.	Low	Environmental: No short or long-term loss.
C1 Clay Borrow Dam	Water (surface water runoff) flows into Baker Creek, but remediation in kind feasible.	Low	Environmental: Minimal short-term loss. No long-term loss.
10	Not applicable	Not applicable	In its current state the dam has no implication on the operation of the North Pond. To be reviewed in the event of any operational changes.
M&M Dam	Not applicable	Not applicable	Dam was implemented as emergency response. No currently relied upon.

To assist the Mine Manager in determining the areas to evacuate and restrict access to, Table C-2 provides a high level summary of the significant areas that would be affected in the event of a dam failure.

Table C-2: Significant Areas Impacted by Dam Failure

TCA	Dam	Water Bodies				Public Roads		Mine Access Roads		Mine Infrastructure			
		Baker Creek	Yellowknife Bay	Gar & Trapper Lakes	Trapper Creek	Ingraham Trail (Hwy 4)	Vee Lake Road	UBC Bridge	Gatehouse Bridge	Open Pits		Portal to Underground	Water Treatment
										Flooded	Some Flow		
Original	1	X	X	-	-	X	-	X	X	B3	-	1-38	X
	2	X	X	-	-	X	-	X	X	B3 & C1	B1 & A2	1-38	X
	3	-	-	-	-	-	-	-	-	-	-	-	-
	11	-	X	-	-	-	-	-	-	-	-	-	-
Northwest	21A	X	X	-	-	X	X	X	X	B3, C1, & A2	B1	1-38	X
	21B	X	X	-	X	X	X	X	X	B3, B2, B1, C1, A2	-	1-38 & UBC	-
	21C	X	X	-	X	X	X	X	X	B3, B2, B1, C1, A2	-	1-38 & UBC	-
	21D	X	X	X	X	X	X	-	-	-	-	-	-
	22A	X	X	X	X	X	X	-	-	-	-	-	-
	22B	X	X	X	X	X	X	-	-	-	-	-	-

Source: Golder (2021)

APPENDIX C – DAM CONSEQUENCE CLASSIFICATIONS

GMRP – OMS Manual (Version G)

C-3 References

CDA (Canadian Dam Association). 2013. Dam Safety Guidelines – 2007 (Revised 2013).

Golder (Golder Associates Ltd.). 2015. Stability Review of Dams – Giant Mine Remediation Project. Prepared for Public Works and Government Services Canada. Golder Ref. No. 1314270004-042-R-Rev0-12000. Dated 19 October 2015.

Golder 2021. Giant Mine Dam Breach Analysis and Inundation Study. Prepared for Public Services and Procurement Canada. Golder Ref. No. 18102211-162-R-Rev0-45000A. 29 March 2021.

GTR (Global Tailings Review). 2020. Global Industry Standard on Tailings Management. August 2020.

SRK (SRK Consulting (Canada) Inc.). 2007. Giant Mine Remediation Plan: 2007 Seismic Studies Related to Tailings Dam Safety – Final. Report prepared for Giant Mine Remediation Project, Department of Indian Affairs and Northern Development. SRK Doc. No. 1CP001.037.A302. August 2007.

APPENDIX D

Climate Data

APPENDIX D – CLIMATE DATA

GMRP – OMS Manual (Version G)

D-1 Climate Station Reference

Climate data relevant to Giant Mine area are available from the Environment Canada climate station at Yellowknife A (Station ID 2204100 from 1942 to 2012, and 2204101 from 2013 to 2024). When historical data are not available from Yellowknife Airport, data from alternative stations, as shown in Table D-1, can be used.

Table D-1: Regional Climate Stations

Name	Environment Canada Station Number	Latitude	Longitude	Elevation ^(a) (masl)
Yellowknife A	2204100 / 2204101	62°27'47" N	114°26'25" W	205.7
Yellowknife CS	2204155	62°28'00" N	114°27'00" W	210.0
Yellowknife Hydro	2204200	62°40'00" N	114°15'00" W	159.4
Yellowknife Henderson	2204110	62°27'00" N	114°23'00" W	200.0

(a) Approximate general elevation of the site is 190.0 masl.

D-2 Adjustment of Precipitation Data

Daily rainfall and snowfall data, as recorded at the Yellowknife airport climate station, should be corrected for “under-catch” factors, based on the Adjusted Historical Canadian Climate Data (AHCCD) database (EC 2017a, Mekis and Hogg 1999). Adjustments should be applied to rainfall and snowfall separately.

Under-catch factors for use at Giant Mine are:

- Rainfall: 1.15
- Snowfall: 1.20

APPENDIX D – CLIMATE DATA

GMRP – OMS Manual (Version G)

D-3 Temperature

Yellowknife is located in a region with arid and subarctic continental climate characterized by long and cold winters and short and cool summers (Golder 2011). Air masses in the winter and spring originate in the Arctic and westerly air flows from the Pacific Ocean sweep over the site during the summer and fall months (Gibson and Reid 2009).

The monthly mean, minimum, maximum temperatures and corresponding annual values are shown in Table D-2.

Table D-2: Annual and Monthly Mean, Minimum and Maximum Temperature

Month	Monthly Temperature (°C)		
	Mean	Minimum	Maximum
January	-26.7	-37.0	-15.2
February	-24.2	-35.6	-15.9
March	-17.6	-27.6	-9.6
April	-6.4	-16.4	1.2
May	5.0	-1.5	11.8
June	13.2	9.4	16.3
July	16.6	13.3	19.4
August	14.3	10.3	17.2
September	7.3	2.5	11.2
October	-1.2	-6.2	2.7
November	-13.7	-24.4	-6.0
December	-23.1	-31.3	-13.2
Annual	-4.7	-37.0	-19.4

Source: Environment Canada Yellowknife A (Station ID 2204100 / 2204101), 1942 to 2023.

The mean annual temperature is -4.7°C. The coldest month is typically January, with a mean temperature of -26.7°C and the warmest month is typically July, with a mean temperature of 16.6°C.

The following assumptions can be made based on the available temperature data:

- During the winter months, November to March, temperatures remain below 0°C. Precipitation occurring during this period will predominately occur as snowfall and will accumulate on the ground as snow or ice.
- During the summer months, June to August, temperatures remain above 0°C. No snow accumulation on the ground will occur during this period and precipitation will contribute to surface runoff.
- During the fall freeze-up, September to October, or during the spring melt, April to May, precipitation may occur as rainfall or snow, depending on air temperature. Precipitation may accumulate on the ground as snow and rain-on-snow events may occur.

APPENDIX D – CLIMATE DATA

GMRP – OMS Manual (Version G)

D-4 Precipitation

Annual and Monthly Precipitation

Total annual precipitation adjust for under-catch is estimated to be 348.4 mm for a mean year, with the mean annual rainfall estimated to be 182.3 mm and the mean annual snowfall estimated to be 166.1 mm of snow, presented as snow water equivalent (SWE). In a mean year, approximately 52% of precipitation occurs as rain and 48% occurs as snow. Precipitation occurs primarily in the summer and fall months.

The majority of rain occurs between the months of May and October. The majority of snow occurs between October and April, with no snowfall recorded in the months of July and August.

Table D-3 presents the estimated mean monthly and annual rainfall, snowfall and total precipitation values, adjusted for under-catch.

Table D-3: Annual and Monthly Mean, Minimum and Maximum Precipitation

Month	Rainfall (mm)	Snowfall (SWE, mm)	Total Precipitation (mm)
January	0.2	22.8	23.1
February	0.0	18.9	19.0
March	0.1	17.9	18.0
April	2.3	11.3	13.6
May	14.7	4.1	18.8
June	27.7	0.1	27.8
July	42.2	0.0	42.2
August	46.1	0.0	46.1
September	33.5	3.2	36.8
October	14.4	23.2	37.6
November	0.6	38.1	38.7
December	0.2	26.1	26.3
Annual	182.3	166.1	348.4

Source: Environment Canada Yellowknife A (Station ID 2204100 / 2204101), 1942 to 2023.

Note:

Precipitation data adjusted for under-catch (see Section D-2).

Data presented does not include losses due to snow sublimation, snow redistribution.

The annual values may not total exactly due to rounding.

Annual extreme precipitation (rainfall and snowfall) quantities for different return periods are shown in Table D-4 for wet and dry year conditions.

APPENDIX D – CLIMATE DATA

GMRP – OMS Manual (Version G)

Table D-4: Annual Rainfall and Snowfall Extreme Quantities

	Return Period (years)	Rainfall (mm)	Snowfall (SWE, mm)
Dry	25	91.4	82.6
	5	132.0	125.2
Median	2	176.3	164.8
Wet	5	228.4	204.6
	10	258.7	225.4
	25	292.8	247.7
	50	315.3	262.1
	100	335.7	275.1
	200	354.1	287.1
	500	375.8	301.5

Source: Environment Canada Yellowknife A (Station ID 2204100 / 2204101), 1942 to 2023.

Note:

Rainfall and snowfall estimates were adjusted for under-catch.

Because extreme rainfall and snowfall conditions may not occur in the same year, these values may not be added to estimate total annual precipitation values for corresponding return periods.

Data presented does not include losses due to snow sublimation, snow redistribution.

Extreme Precipitation Events

24-hour rainfall events for various return periods, estimated using the Intensity-Duration-Frequency curves published by Environment Canada for Yellowknife A Station, Station ID 2204100, are presented in Table D-5. Extreme rainfall is typically not corrected for under-catch; thus, rainfall data provided below were not adjusted using factors provided in Section D-2.

Table D-5: 24-Hour Rainfall Depths at Yellowknife Airport Climate Station (1963-1996)

Return Period (years)	Rainfall (mm)
2	26.4
5	40.5
10	49.8
25	61.6
50	70.3
100	79.0
500	103.1

Source: Environment Canada Yellowknife A (Station ID 2204100), 1963 to 1996.

APPENDIX D – CLIMATE DATA

GMRP – OMS Manual (Version G)

Probable Maximum Precipitation

Values for a local Probable Maximum Precipitation event (point PMP) at Giant mine are provided in Table D-6. The point PMP values can be used for most of the areas of the site which are characterized by small to medium size watersheds. Extreme rainfall is typically not corrected for under-catch; thus, rainfall data provided below were not adjusted using factors provided in Section D-2.

Table D-6: Estimated Total Point Peak Maximum Precipitation Rainfall Depths for Various Durations at Yellowknife A

Duration (hours)	Point PMP Rainfall Depth (mm)
0.5	83
1	96
2	121
6	191
12	244
24	328
48	343
72	354

Source: Golder (2023).

D-5 Spring Snowpack and Snowmelt

Annual maximum series of bi-monthly (two-week periods, from mid-March to end of May) and annual snowpack were derived from historical snowfall and temperature data, using the degree day method (USDA 2004) to account for snowmelt during the period of spring freshet. A 34% reduction was applied to the snowpack to represent sublimation losses. This 34% reduction was based on a previous local study of surface water drainage infrastructure at Giant Mine (Golder 2011). The corresponding snow water equivalent (SWE) was computer assuming that one centimetre of snowfall would yield one millimetre of SWE. Spring snowmelt generally occurs between March to May.

A frequency analysis was preformed on the derived baseline snowpack annual maximum series to estimate the 2-, 10-, 50-, 100-, and 500-year snowpack events. Probable maximum snow accumulation (PMSA) was estimated as two times the 100-year snowpack, following the methods from the Guideline on Extreme Flood Analysis (AT 2004). The resulting snowpack and corresponding SWE are provided in Table D-7.

Table D-7: Derived Snowpack and SWE Data

Return Period	Snowpack (cm) or SWE (mm)					Annual
	Mar 19-31	Apr 1-15	Apr 16-30	May 1-15	May 16-31	
2-year	86	90	83	43	1	91
10-year	127	130	124	97	32	131
50-year	154	155	147	131	74	157
100-year	164	164	155	142	96	166
500-year	182	181	170	166	161	183
PMSA	328	327	309	285	192	332

Source: Based on Environment Canada Yellowknife A (Station ID 2204100), 1942 to 2023. Values adjusted for under-catch.

APPENDIX D – CLIMATE DATA

GMRP – OMS Manual (Version G)

D-6 Wind

Hourly wind speed and direction are available from the Yellowknife A (Station ID 2204100 and 2204101) from 1953 to 2023. During the open water season (i.e., June to October), the most frequent winds are from the east. A frequency analysis was performed on the wind data to estimate mean hourly wind speed and direction for various return periods as summarized in Table D-8.

Table D-8: Yellowknife A Climate Station Wind Speed and Directions Frequencies (1953-2023)

Return Period	Mean Hourly Wind Speed							
	N	NE	E	SE	S	SW	W	NW
2-year	47.0	40.4	40.4	41.0	42.0	30.9	41.8	47.3
10-year	58.0	50.9	46.9	49.2	49.7	40.1	52.9	59.3
50-year	66.0	59.8	51.2	54.2	54.1	47.5	60.5	69.2
100-year	69.1	63.5	52.8	56.0	55.6	50.6	63.2	73.3
200-year	72.1	67.3	54.3	57.6	57.0	53.6	65.6	77.4
500-year	75.9	72.3	56.2	59.5	58.6	57.6	68.5	82.9
1000-year	78.8	76.2	57.5	60.9	59.7	60.7	70.4	87.1
10,000-year	87.8	89.6	61.6	64.8	62.9	71.0	75.7	101.5

D-7 Evaporation

Lake evaporation was measured locally at Pocket Lake between 1991 and 2008 (Gibson and Reid 2009), as summarized in Table D-9.

Table D-9: Measured Lake Evaporation at Pocket Lake

Year	Annual Evaporation (mm)
1991	392
1992	339
1993	363
1994	460
1995	445
1996	414
1997	376
1998	463
1999	402
2000	435
2001	386
2002	361
2003	425
2004	337
2005	372
2006	431
2007	397
2008	379
Mean	397

APPENDIX D – CLIMATE DATA

GMRP – OMS Manual (Version G)

D-8 References

- Alberta Environment. 2011. Evaporation and Evapotranspiration Methods, Prepared by Golder for Alberta Environment Central Region, Red Deer. July 2011.
- EC (Environment Canada). 2010. Adjusted Historical Canadian Climate Data (AHCCD). Retrieved October 2010 from: <http://ec.gc.ca/dccha-ahccd/>.
- EC. 2017a. Adjusted and Homogenized Canadian Climate Data (AHCCD). <https://open.canada.ca/en>.
- EC. 2017b. Historical Climate Data. Available online at <https://climate.weather.gc.ca/>.
- Gibson, J.J. and Reid, R. 2009. Stable isotope fingerprint of open-water evaporation losses and effective drainage area fluctuation in a subarctic shield watershed. *Journal of Hydrology* 381, p. 142 – 150.
- Golder (Golder Associates Ltd.). 2011. Design Basis Memo for Surface Water Drainage Infrastructure. Technical Memorandum. Project 09-1427-0006/5100/5110. 2011.
- Golder. 2023. Giant Mine – Baker Creek Flood Hazard Assessment – 2023 Update. Reference No. 18102211-054-R-Rev2-35000.
- Mekis, E. and Hogg, W.D. 1999. Rehabilitation and analysis of Canadian daily precipitation time series. *Atmosphere-Ocean* 37:53-85.

APPENDIX E

Water Balance

APPENDIX E – WATER BALANCE

GMRP – OMS Manual (Version G)

E-1 North Pond Water Balance

A water balance model for the North Pond was completed using GoldSim software based on the available concurrent set of complete climate and hydrological data 1972 to 2016 as shown in Figure E-1 and Figure E-2. The water balance does not include inputs to the tailings containment area (TCA) from mine operations e.g., tailings deposition or pumping from underground.

The North Pond water balance provides details on average expected conditions for the North Pond based on the available concurrent set of complete climate and hydrological data 1972 to 2016 as shown in Figure E-1 and Figure E-2. The water balance does not include inputs to the TCA from mine operations e.g., tailings deposition or pumping from underground.

During fall and winter, when temperatures are below freezing, snowfall was modeled as accumulated snowpack which reports as snowmelt during the spring freshet. Based on the assumption that the ground is typically frozen and infiltration is minimal when snowmelt occurs, the snowmelt runoff coefficient was estimated to be 1.0, for all area types. Runoff coefficients were applied as follows:

- Natural Ground = 0.4
- Rock = 0.74
- Ponds = 1.0

Lake evaporation, infiltration to groundwater, and lateral infiltration to Yellowknife Bay were combined into a single term representing the water losses in the water balance. The following assumptions were made:

- Evaporation only occurs within the pond area which constitutes a relatively small percentage of the total watershed area of the North Pond.
- Infiltration to ground water was correlated with the amount of water lost to the underground mine, which is unsupported by direct field observations.
- Water losses to deep groundwater are not significant due to the local permafrost regime and are not included in the model. Lateral infiltration to Yellowknife Bay was assumed at 5% of the total runoff generated within the North and Central ponds watershed, and 25% of runoff generated within the South Pond watershed (Golder 2016).
- Discharge from the North Pond represents the excess water stored within the pond after accounting for losses.

The results of the water balance indicate that, during the model simulation period, water had been released from the North Pond every year, occurring predominantly during the open water season (Figure E-1). Seasonal variability of water volumes within the North Pond was observed, with the highest volumes observed during spring freshet (April and May). Water inputs to the pond occurred throughout the summer months (July through October) and were highly responsive to rainfall events. During winter months (November through March) water inputs to the pond were generally absent (Figure E-2).

APPENDIX E – WATER BALANCE

GMRP – OMS Manual (Version G)




Figure E-1: Daily Water Volumes at North Pond between 1972 and 2016




Figure E-2: Average Daily Water Volumes at North Pond for each Month (1972 to 2016)

APPENDIX E – WATER BALANCE

GMRP – OMS Manual (Version G)

E-2 Northwest Pond Water Balance

A water balance model for the Northwest Pond was completed using GoldSim software based on the available concurrent set of complete climate and hydrological data 1972 to 2016 as shown in Figures Figure E-3 and Figure E-4. The water balance does not include inputs to the TCA from mine operations e.g., tailings deposition or pumping from underground. This water balance provides details on average expected conditions for the Northwest Pond.

Water levels at the pond are highly influenced by water pumping activities from the underground into the pond and from the pond to the Effluent Treatment Plant. The model adopted the underground pumping rates to the Northwest Pond for the period between 2011 to 2016 (data prior to 2011 was not available).

During fall and winter, when temperatures are below freezing, snowfall was modeled as accumulated snowpack which reports as snowmelt during the spring freshet. Based on the assumption that the ground is typically frozen and infiltration is minimal when snowmelt occurs, the snowmelt runoff coefficient was estimated to be 1.0, for all area types. Runoff coefficients were applied as follows:

- Natural Ground = 0.4
- Rock = 0.74
- Ponds = 1.0


Lake evaporation, infiltration to groundwater, and lateral infiltration to Trapper Creek were combined into a single term representing the water losses in the water balance. The following assumptions were made:

- Evaporation only occurs within the pond area which constitutes a relatively small percentage of the total watershed area of the Northwest Pond.
- Infiltration to ground water was correlated with the amount of water lost to the underground mine, which is unsupported by direct field observations.
- Water losses to deep groundwater are not significant due to the local permafrost regime and are not included in the model.
- Lateral infiltration to Trapper Creek was determined using Darcy's Equation.

The results of the water balance indicate that, during the model simulation period, water had been released from the Northwest Pond every year and occurred predominantly during the open water season (Figure E-3). Seasonal variability of water volumes within the Northwest Pond was evident, with the highest volumes observed during spring freshet (April and May). Water inputs to the pond occurred throughout the summer months (July through October) and were highly dependent on rainfall events. During winter months (November through March) water inputs to the pond were generally absent (Figure E-4).

APPENDIX E – WATER BALANCE

GMRP – OMS Manual (Version G)



Note: 2011 to 2016 period includes pumping rates to the Northwest Pond from the underground mine.

Figure E-3: Modeled Daily Volumes at Northwest Pond between 1972 and 2016




Figure E-4: Derived Daily Average Volumes at Northwest Pond each Month (1972 to 2016)

APPENDIX E – WATER BALANCE

GMRP – OMS Manual (Version G)

E-3 References

Golder (Golder Associates Ltd.). 2016. Present-day Arsenic Loading to Baker Creek and Yellowknife Bay.
Prepared for Public Works and Government Services Canada, Yellowknife, NT, Canada.
November 30, 2016.

APPENDIX F

Inspection Forms

DAILY TCA INSPECTION										
Inspector:							Weather Conditions:			
Date:							Wildlife Sightings:			
	B2 Dam	Dam 1	Dam 2	Splitter Dyke	Dam 21A	Dam 21B	Dam 21C	Dam 21D	Dam 22A	Dam 22B
Classification Category	Very High	High	High	Low	Very High	Very High	Very High	High	High	High
Time										
Y= Yes, N=No										
Sinkholes										
Cracks										
Seeps										
Erosion										
Slope Failure										
Settlement										
Seepage at toe (cloudy/clear appearance)										
New Observation										

***IF ANY CONDITIONS ARE NEW OBSERVATIONS, MINE MANAGER SHOULD BE CONTACTED IMMEDIATELY

Additional Comments:

Changes in historical deficiencies?

No

Yes

Explain Below:

Inspector's Signature

Supervisor's Signature

Original Tailings Containment Area Weekly Inspection Record Form									
Date:				Inspected By:					
Weather:									
Review of Daily Inspections Completed Prior to Inspection:									
Instructions:	1) Carry out visual inspection of Original Tailings Containment Area starting at Dam 1 and proceeding clockwise 2) Note occurrence of features and provide description of any issues found (see visual reference guide) 3) Take photographic record 4) If at any point you observe unsafe conditions inform the Mine Manager immediately 5) On Completion this completed form should be returned to the Mine Manager's office for review and action (if required) 6) Very High and High Consequence Dams in RED . Significant Consequence Dams in ORANGE . Low Consequence Dams in BLUE								
Overall Comments:									
Dam 1									
Historic/Previous Issues:	Tension cracks and ongoing settlement of crest. Provide comparison of current and previous conditions. i.e. similar or increasing								
Estimated Freeboard:					Polishing Pond Elevation:				
Minimum Freeboard:	1.4 m (Max Elevation of Polishing Pond: 174.8 m)								
	Upstream Slope		Crest		Downstream Slope		Downstream Toe		
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Photographs:									
Comments:	Any changes in historical deficiencies? No Yes Explain Below:								
Splitter Dyke									
Historic/Previous Issues:									
DIFFERENTIAL 0m:					Settling Pond Elevation:				
Maximum Water Level:									
Maximum Freeboard:									
	Upstream Slope		Crest		Downstream Slope		Downstream Toe		
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Photographs:									
Comments:	Any changes in historical deficiencies? No Yes Explain Below:								

Original Tailings Containment Area
Weekly Inspection Record Form

Dam 2

Historic/Previous Issues:								
DIFFERENTIAL (max 1.7m):							North Pond Elevation:	
Minimum Freeboard:	North Pond - 1.7m							
Maximum Freeboard:	North Pond + 1.7m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:	Any changes in historical deficiencies? No Yes Explain Below:							

Dam 3 (Dam 3C and Dam 3D)

Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Original Tailings Containment Area
Weekly Inspection Record Form

Dam 11

Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Dam 4

Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Original Tailings Containment Area
Weekly Inspection Record Form

Dam 5

Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Dyke 6

Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Original Tailings Containment Area Weekly Inspection Record Form									
Dam 7									
Historic/Previous Issues:									
Estimated Freeboard:									
Minimum Freeboard:	1.0 m								
	Upstream Slope		Crest		Downstream Slope		Downstream Toe		
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Photographs:									
Comments:									
Dam 8									
Historic/Previous Issues:									
Estimated Freeboard:									
Minimum Freeboard:	1.0 m								
	Upstream Slope		Crest		Downstream Slope		Downstream Toe		
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Photographs:									
Comments:									

Original Tailings Containment Area
Weekly Inspection Record Form

Dam 9

Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Dam 12

Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Northwest Pond Tailings Containment Area Weekly Inspection Record Form									
Date:				Inspected By:					
Weather:									
Review of Daily Inspections Completed Prior to Inspection:									
	1) Carry out visual inspection of Northwest Pond Tailings Containment Area starting at Dam 21D and proceeding clockwise 2) Note occurrence or not of features and provide description of any issues found (see visual reference guide) 3) Take photographic record 4) If at any point you observe unsafe conditions inform the Mine Manager immediately 5) On Completion this completed form should be returned to the Mine Manager's office for review and action (if required) 6) Very High and High Consequence Dams in RED . Significant Consequence Dams in ORANGE . Low Consequence Dams in BLUE								
Overall Comments:	NW Pond Elevation:								
Dam 21A									
Historic/Previous Issues:									
Estimated Freeboard:				Maximum Water Level: 193.35m					
Minimum Freeboard:	0.9m								
	Upstream Slope		Crest		Downstream Slope		Downstream Toe		
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Photographs:									
Comments:									
Dam 21B									
Historic/Previous Issues:									
Estimated Freeboard:				Maximum Water Level: 193.35m					
Minimum Freeboard:	0.9m								
	Upstream Slope		Crest		Downstream Slope		Downstream Toe		
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Photographs:									
Comments:									

Northwest Pond Tailings Containment Area Weekly Inspection Record Form								
Dam 21C								
Historic/Previous Issues:								
Estimated Freeboard:			Maximum Water Level: 193.35m					
Minimum Freeboard:	0.9m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:	Any changes in historical deficiencies? No Yes Explain Below:							
Dam 21D								
Historic/Previous Issues:								
Estimated Freeboard:			Maximum Water Level: 193.35m					
Minimum Freeboard:	0.9m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:	Any changes in historical deficiencies? No Yes Explain Below:							

Northwest Pond Tailings Containment Area Weekly Inspection Record Form								
Dam 22A								
Historic/Previous Issues:								
Estimated Freeboard:			Maximum Water Level: 193.35m					
Minimum Freeboard:	0.9m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Northwest Pond Tailings Containment Area Weekly Inspection Record Form								
Dam 22B								
Historic/Previous Issues:	Historic Toe Seepage: Water pooling at Downstream Toe: _____ l/min							
Estimated Freeboard:			Maximum Water Level: 193.35m					
Minimum Freeboard:	0.9m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:	Any changes in historical deficiencies? No Yes Explain Below:							
Completed Form Received by Mine Manager's Office								
Name:					Date and Time:			
Completed Form Reviewed by Mine Manager								
Name:					Date and Time:			
Follow Up Actions Required:								


B2 Dam (Baker Pond) Weekly Inspection Record Form									
Date:					Inspected By:				
Weather:									
Review of Daily Inspections Completed Prior to Inspection:									
Instructions:	1) Carry out visual inspection of B2 Dam 2) Note occurrence or not of features and provide description of any issues found (see visual reference guide) 3) Take photographic record 4) Read Piezometers and Barometer weekly between April and August 5) If at any point you observe unsafe conditions inform the Mine Manager immediately 6) On Completion this completed form should be returned to the Mine Manager's office for review and action (if required) 7) Very High and High Consequence Dams in RED . Significant Consequence Dams in ORANGE . Low Consequence Dams in BLUE								
Overall Comments:									
B2 Dam									
Historic/Previous Issues:		Seepage at downstream toe. Note if present, estimated flow rates and if clear or with sediment.							
		Baker Creek Elevation:							
Estimated Freeboard:					Maximum Water Level: 164.7m				
Minimum Freeboard:		0.9m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe		
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Clear of Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Photographs:									
Comments:	Visible Seepage Into Pit? _____ Water in Sump(Clear or Turbid): _____								
	Changes in historical deficiencies? ☐ No ☐ Yes Explain Below:								
Vibrating Wire Piezometers									
	Readings								
	Piezometer (Lc) (B Units)	Thermistor (Tc) (°C)	Barometer (Bc) (kPa)						
PZ-1									
PZ-2									
PZ-3									
PZ-4									
PZ-5									
PZ-6									
PZ-7									
Completed Form Received by Mine Manager's Office									
Name:					Date and Time				
Completed Form Reviewed by Mine Manager									
Name:					Date and Time				
Follow Up Actions Required:									

Mill Pond Structure Weekly Inspection Record Form									
Date:				Inspected By:					
Weather:									
Review of Daily Inspections Completed Prior to Inspection:									
Instructions:	1) Carry out visual inspection of Mill Pond Structure 2) Note occurrence or not of features and provide description of any issues found (see visual reference guide) 3) Take photographic record 5) If at any point you observe unsafe conditions inform the Mine Manager immediately 6) On Completion this completed form should be returned to the Mine Manager's office for review and action (if required) 7) Very High and High Consequence Dams in RED . Significant Consequence Dams in ORANGE . Low Consequence Dams in BLUE								
Overall Comments:									
Mill Pond Structure									
Historic/Previous Issues:									
Estimated Water Level:									
Maximum Water Level:	160.3m								
	Upstream Slope		Crest		Downstream Slope		Downstream Toe		
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Clear of Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Photographs:									
Comments:									
Completed Form Received by Mine Manager's Office									
Name:				Date and Time					
Completed Form Reviewed by Mine Manager									
Name:				Date and Time					
Follow Up Actions Required:									

Appendix F2:
Weekly Inspection Forms
VISUAL REFERENCE GUIDE

INSPECTION ITEM	EXAMPLE IMAGE
Freeboard	
Longitudinal Cracks (Record Length, Width, and Depth)	
Transverse Cracks (Record Length, Width, and Depth)	

Appendix F2:
Weekly Inspection Forms
VISUAL REFERENCE GUIDE


INSPECTION ITEM	EXAMPLE IMAGE
Settlement (Record Length, Width, and Depth)	
Sinkhole (Record Size and Depth)	
Sloughing/Erosion (Record Size and Depth)	

Appendix F2: Weekly Inspection Forms

VISUAL REFERENCE GUIDE

INSPECTION ITEM	EXAMPLE IMAGE
Sliding (Record length of slip as well as vertical and lateral movement)	
Seepage / Wet Areas on Slopes (Estimate flow and note whether clear or dirty')	 Donated by Jeffery A. Farrar Available from Geosignpost.org Website http://www.geosignpost.org
Seepage / Wet Areas at Toe (Estimate flow and note whether clear or dirty')	

Appendix F2:
Weekly Inspection Forms
VISUAL REFERENCE GUIDE

INSPECTION ITEM	EXAMPLE IMAGE
Vegetation Growth on Dam (Record species and size)	
Animal Burrows (Record depth and size)	

Original Tailings Containment Area Monthly Inspection Record Form								
Date:					Inspected By:			
Weather:								
Review of Weekly and Daily Inspections Completed Prior to Inspection:								
Instructions:	1) Review Follow-up actions from previous inspections 2) Carry out visual inspection of Original Tailings Containment Area starting at Dam 1 and proceeding clockwise 3) Note occurrence or not of features and provide description of any issues found 4) Take photographic record 5) Review requirements for quarterly surveys of instruments 6) Review OMS Manual and EPRP 7) File completed inspection form and send copy to Consulting Geotechnical Engineer 8) Very High and High Consequence Dams in RED . Significant Consequence Dams in ORANGE . Low Consequence Dams in BLUE							
Review of Previous Actions:								
Overall Comments:								
Dam 1								
Historic/Previous Issues:	Tension cracks and ongoing settlement of crest. Provide comparison of current and previous conditions. i.e. similar or increasing							
Estimated Freeboard:					Polishing Pond Elevation:			
Minimum Freeboard:	1.4m (Max Elevation of Polishing Pond: 174.8m)							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:	Any changes in historical deficiencies? No Yes Explain Below:							
Settlement Plates (Measured Quarterly)								
Date of Last Survey:					Date of Next Survey:			
Survey Required:					Survey Scheduled Date:			
Survey Scheduled by:								
Survey Monuments (Measured Quarterly)								
Date of Last Survey:					Date of Next Survey:			
Survey Required:					Survey Scheduled Date:			
Survey Scheduled by:								

Original Tailings Containment Area
Monthly Inspection Record Form

Splitter Dyke								
Historic/Previous Issues:								
DIFFERENTIAL 0m:					Settling Pond Elevation:			
Maximum Water Level:								
Maximum Freeboard:	1.0m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:	Any changes in historical deficiencies? No Yes Explain Below:							

Dam 2								
Historic/Previous Issues:								
DIFFERENTIAL (max 1.7m):					North Pond Elevation:			
Minimum Freeboard:	North Pond - 1.7m							
Maximum Freeboard:	North Pond + 1.7m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:	Any changes in historical deficiencies? No Yes Explain Below:							

Original Tailings Containment Area Monthly Inspection Record Form								
Dam 3 (Dam 3C and Dam 3D)								
Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Dam 11								
Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Original Tailings Containment Area Monthly Inspection Record Form								
Dyke 6								
Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								
Dam 7								
Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Original Tailings Containment Area Monthly Inspection Record Form								
Dam 8								
Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								
Dam 9								
Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Original Tailings Containment Area Monthly Inspection Record Form								
Dam 12								
Historic/Previous Issues:								
Estimated Freeboard:								
Minimum Freeboard:	1.0 m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Settlement	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Sinkholes	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Erosion	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Sloughing, Slide, Bulging	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Wet or Seepage Areas	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Clear or Cloudy Seepage	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Vegetation Growth	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Animal Burrows	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Photographs:								
Comments:								
Review of Operational Maintenance and Surveillance Manual								
Date of Last Revision:					Reflects Current Conditions:			
Comments/Amendments Required								
Review of Emergency Preparedness and Response Plan								
Date of Last Revision:					Reflects Current Conditions:			
Comments/Amendments Required								
Completed Form Filed								
Name:					Date and Time:			
Follow Up Actions Required:								
Copy Sent to Consulting Geotechnical Engineer								
Name:					Date and Time:			

Northwest Pond Tailings Containment Area Monthly Inspection Record Form									
Date:					Inspected By:				
Weather:									
Review of Weekly and Daily Inspections Completed Prior to Inspection:									
Instructions:		1) Review Follow-up actions from previous inspections 2) Carry out visual inspection of Northwest Pond starting at Dam 21D and proceeding clockwise 3) Note occurrence or not of features and provide description of any issues found 4) Take photographic record 5) Review requirments for quarterly surveys of instruments 6) Review OMS Manual and EPRP 7) File completed inspection form and send copy to Consulting Geotechnical Engineer 8) Very High and High Consequence Dams in RED. Significant Consequence Dams in ORANGE. Low Consequence Dams in BLUE							
Review of Previous Actions:									
Overall Comments:									
NW Pond Elevation:									
Dam 21A									
Historic/Previous Issues:									
Estimated Freeboard:		Maximum Water Level: 193.35m							
Minimum Freeboard:		0.9m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe		
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Photographs:									
Comments:									

Northwest Pond Tailings Containment Area Monthly Inspection Record Form									
Dam 21B									
Historic/Previous Issues:									
Estimated Freeboard:			Maximum Water Level: 193.35m						
Minimum Freeboard:	0.9m								
	Upstream Slope		Crest		Downstream Slope		Downstream Toe		
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Photographs:									
Comments:									
Dam 21C									
Historic/Previous Issues:									
Estimated Freeboard:			Maximum Water Level: 193.35m						
Minimum Freeboard:	0.9m								
	Upstream Slope		Crest		Downstream Slope		Downstream Toe		
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Photographs:									
Comments:	Any changes in historical deficiencies? No Yes Explain Below:								

Northwest Pond Tailings Containment Area Monthly Inspection Record Form								
Dam 21D								
Historic/Previous Issues:	Cracking at downstream toe bench. Provide comparison of current and previous conditions. i.e. similar or increasing							
Estimated Freeboard:			Maximum Water Level: 193.35m					
Minimum Freeboard:	0.9m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:	Any changes in historical deficiencies? No Yes Explain Below:							

Northwest Pond Tailings Containment Area Monthly Inspection Record Form								
Dam 22A								
Historic/Previous Issues:								
Estimated Freeboard:			Maximum Water Level: 193.35m					
Minimum Freeboard:	0.9m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Clear or Cloudy Seepage	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No
Photographs:								
Comments:								

Northwest Pond Tailings Containment Area Monthly Inspection Record Form								
Dam 22B								
Historic/Previous Issues:	Historic Toe Seepage: Water pooling at Downstream Toe: _____ l/min							
Estimated Freeboard:			Maximum Water Level: 193.35m					
Minimum Freeboard:	0.9m							
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Settlement	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Sinkholes	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Erosion	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Sloughing, Slide, Bulging	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Wet or Seepage Areas	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Vegetation Growth	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Animal Burrows	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Photographs:								
Comments:	Any changes in historical deficiencies? ☐ No ☐ Yes Explain Below:							
Review of Operational Maintenance and Surveillance Manual								
Date of Last Revision:					Reflects Current Conditions:			
Comments/Amendments Required								
Review of Emergency Preparedness and Response Plan								
Date of Last Revision:					Reflects Current Conditions:			
Comments/Amendments Required								
Completed Form Received by Mine Manager's Office								
Name:					Date and Time:			
Completed Form Reviewed by Mine Manager								
Name:					Date and Time:			
Follow Up Actions Required:								

B2 Dam (Baker Pond) Monthly Inspection Record Form								
Date:				Inspected By:				
Weather:								
Review of Weekly and Daily Inspections Completed Prior to Inspection:								
Instructions:	1) Review Follow-up actions from previous inspections 2) Carry out visual inspection of B2 Dam 3) Carry out visual inspection of Baker Creek downstream of B2 Dam 4) Note occurrence of features and provide description of any issues found 5) Take photographic record 6) Review requirements for quarterly surveys of instruments 7) Review OMS Manual and EPRP 8) File completed inspection form and send copy to Consulting Geotechnical Engineer 9) Very High and High Consequence Dams in RED . Significant Consequence Dams in ORANGE . Low Consequence Dams in BLUE							
Review of Previous Actions:								
Overall Comments:								
B2 Dam								
Historic/Previous Issues:	Seepage at downstream toe. Note if present, estimated flow rates and if clear or with sediment. Baker Creek Elevation:							
Estimated Freeboard:	1.4m (Max Elevation of Polishing Pond: 174.8m)							
Minimum Freeboard:								
	Upstream Slope		Crest		Downstream Slope		Downstream Toe	
Cracks	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Settlement	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Sinkholes	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Erosion	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Sloughing, Slide, Bulging	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Wet or Seepage Areas	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Vegetation Growth	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Animal Burrows	O Yes	O No	O Yes	O No	O Yes	O No	O Yes	O No
Photographs:								
Comments:	Visible Seepage Into Pit? _____ Water in Sump(Clear or Turbid): _____							
	Changes in historical deficiencies?		☐ No ☐ Yes	Explain Below:				

B2 Dam (Baker Pond) Monthly Inspection Record Form				
Settlement Plates (Measured Quarterly)				
Date of Last Survey:		Date of Next Survey:		
Survey Required:		Survey Scheduled Date:		
Survey Scheduled by:				
	Readings			
	Piezometer (Lc) (B Units)	Thermistor (Tc) (°C)	Barometer (Bc) (kPa)	
PZ-1				
PZ-2				
PZ-3				
PZ-4				
PZ-5				
PZ-6				
PZ-7				
Downstream Baker Creek				
Historic/Previous Issues:				
	Creek Channel		Comments	
Sloughing, Slide, Bulging	☐ Yes	☐ No		
Obstructions	☐ Yes	☐ No		
Vegetation Growth	☐ Yes	☐ No		
Animals/ Burrows	☐ Yes	☐ No		
Erosion	☐ Yes	☐ No		
Silt in base	☐ Yes	☐ No		
Photographs:				
Completed Form Received by Mine Manager's Office				
Name:		Date and Time		
Completed Form Reviewed by Mine Manager				
Name:		Date and Time		
Follow Up Actions Required:				

Mill Pond Structure Monthly Inspection Record Form									
Date:				Inspected By:					
Weather:									
Review of Weekly and Daily Inspections Completed Prior to Inspection:									
Instructions:	1) Review Follow-up actions from previous inspections 2) Carry out visual inspection of Mill Pond Structure 3) Note occurrence of features and provide description of any issues found 4) Take photographic record 5) Review requirements for quarterly surveys of instruments 6) Review OMS Manual and EPRP 7) File completed inspection form and send copy to Consulting Geotechnical Engineer 8) Very High and High Consequence Dams in RED . Significant Consequence Dams in ORANGE . Low Consequence Dams in BLUE								
Review of Previous Actions:									
Overall Comments:									
Mill Pond Structure									
Historic/Previous Issues:									
Estimated Water Level:									
Maximum Water Level:	160.3m								
	Upstream Slope		Crest		Downstream Slope		Downstream Toe		
Cracks	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Settlement	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sinkholes	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Erosion	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Sloughing, Slide, Bulging	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Wet or Seepage Areas	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Vegetation Growth	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Animal Burrows	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	☐ Yes	☐ No	
Photographs:									
Comments:	Any changes in historical deficiencies? No Yes Explain Below:								
Completed Form Received by Mine Manager's Office									
Name:					Date and Time				
Completed Form Reviewed by Mine Manager									
Name:					Date and Time				
Follow Up Actions Required:									

C1 Clay Borrow and DWC Dam Containment Area Monthly Inspection Record Form				
C1 Clay Borrow Dam				
Historic/Previous Issues:				
Estimated Freeboard:				
Minimum Freeboard:				
	Creek Channel		Comments	
Sloughing, Slide, Bulging	☐ Yes	☐ No	Any changes in historical deficiencies? No Yes Explain Below:	
Obstructions	☐ Yes	☐ No		
Vegetation Growth	☐ Yes	☐ No		
Animal Burrows	☐ Yes	☐ No		
Erosion	☐ Yes	☐ No		
Silt in base	☐ Yes	☐ No		
Photographs:				
DWC Dam Containment				
Historic/Previous Issues:				
Estimated Freeboard:				
Minimum Freeboard:				
	Creek Channel		Comments	
Sloughing, Slide, Bulging	☐ Yes	☐ No	Any changes in historical deficiencies? No Yes Explain Below:	
Obstructions	☐ Yes	☐ No		
Vegetation Growth	☐ Yes	☐ No		
Animal Burrows	☐ Yes	☐ No		
Erosion	☐ Yes	☐ No		
Silt in base	☐ Yes	☐ No		
Photographs:				

APPENDIX G

**Instrumentation Installation Details
and Instrument Calibration
Certificates**

Table G-1: Instrumentation Installation Details

Dam	Instrument type	Instrument ID	Instrument Location	Installation					Serial No. and Logger			Note
				Instrument Depth (mbgs)*	Ground Surface Elevation (masl)	Instrument Elevation (masl)	Material Instrument Installed In	Installation Year	Instrument Serial No.	Datalogger Type	Datalogger Serial No.	
Dam 1	Vibrating Wire Piezometer	D1-SD-01	Downstream toe	12.2	166.14	153.95	Clay	2018	VW50779	-	-	Discontinued Monitoring 2024
		D1-SD-02	Central Downstream bench	7.9	172.02	164.10	Clay	2018	VW50780	DT2055b	16116	Functioning properly. Frozen
		D1-SD-03	North abutment	21.0	175.32	154.29	Sandy Silt	2018	VW50782	DT2055b	16112	Functioning properly
		D1-SD-05	South abutment	13.7	176.06	162.34	Sandy Silt	2018	VW50778	DT2055b	16115	Intermittent pressure readings
		D1-SD-06S	Max crest settlement area	14.3	173.77	159.44	Clay	2018	VW50781	DT2055b	15167	Functioning properly, except for temperature readings since August 2023
		D1-SD-06D	Max crest settlement area	20.4	173.77	153.35	Silty Gravel and Sand	2018	VW50783			Functioning properly, except for temperature readings since March 2023
		D1-SD-21	Third downstream bench	4.6	171.40	166.87	Fill-Sand	2020	VW70616	DT2040	2867	Discontinued Monitoring 2024
	Thermistor	D1-SD-22	Northern downstream bench	4.6	170.90	166.33	Fill-Silty Sand	2020	VW70615	DT2055b	16111	Discontinued Monitoring 2024
		D1-SD-09	Central Downstream bench	-0.3 to 18.5	172.19	Node 16 at 153.7	16 nodes in various soils	2018	TS4700	DT2040	2847	Functioning properly except for Bead 10
		D1-SD-10	In inclined casing along the crest	4.8 to 30.7	175.80	Node 16 at 145.15	16 nodes in various soils	2020	TS5273	DT2040	2848	Functioning properly except for Bead 9
		D1-SD-11	In inclined casing along the crest	-0.9 to 25	175.00	Node 16 at 149.97	16 nodes in various soils	2020	TS5272	DT2040	2803	Functioning properly
		D1-SD-12	In inclined casing along the crest	-0.2 to 25.8	175.10	Node 16 at 149.28	16 nodes in various soils	2020	TS5271	DT2040	3026	Functioning properly
		D1-SD-13	In inclined casing along the crest	-1.8 to 24.1	175.40	Node 16 at 151.29	16 nodes in various soils	2020	TS5268	DT2040	2866	Functioning properly
		D1-SD-14B	In inclined casing along the crest	10.4 to 36.3	175.80	Node 16 at 139.46	16 nodes in various soils	2020	TS5274	DT2040	2870	Functioning properly except for Bead 1
		D1-SD-15	In inclined casing along the crest	-0.2 to 25.7	175.10	Node 16 at 149.38	16 nodes in various soils	2020	TS5270	DT2040	2850	Functioning properly except for Bead 13
		D1-SD-16	In inclined casing along the crest	0.6 to 26.5	175.10	Node 16 at 148.62	16 nodes in various soils	2020	TS5269	DT2040	2851	Functioning properly
		D1-SD-17	In inclined casing along the crest	-1.8 to 24.1	175.20	Node 16 at 150.80	16 nodes in various soils	2020	TS5267	DT2040	2801	Functioning properly
		D1-SD-18	First southern downstream bench	-1 to 20.9	175.00	Node 16 at 154.14	16 nodes in various soils	2020	TS5266	DT2040	2845	Functioning properly
		D1-SD-19	First central downstream bench	-0.7 to 21.2	174.70	Node 16 at 153.48	16 nodes in various soils	2020	TS5265	DT2040	2849	Functioning properly
		D1-SD-20	First northern downstream bench	2 to 23.9	174.70	Node 16 at 150.82	16 nodes in various soils	2020	TS5264	DT2040	2804	Functioning properly except Bead 14
	Settlement Plate	D1-SD-21	Third downstream bench	-0.8 to 17.1	171.40	Node 16 at 154.35	16 nodes in various soils	2020	TS5263	DT2040	2867	Functioning properly
		SP1	Upstream slope	0.0	177.48	177.48	Ground Surface	2002	-	-	-	Decommissioned in July 2022
		SP2	Upstream slope	0.0	177.32	177.32	Ground Surface	2002	-	-	-	Decommissioned in July 2022
	Survey Monument	SP3	Downstream toe	0.0	167.70	167.70	Ground Surface	2002	-	-	-	Functioning properly
		T01	Upstream slope	0.0		175.98	Ground Surface	2016	-	-	-	Decommissioned in July 2022
		T02	Upstream slope	0.0		175.86	Ground Surface	2016	-	-	-	Decommissioned in July 2022
		T03	Upstream slope	0.0		175.96	Ground Surface	2016	-	-	-	Decommissioned in July 2022
		T04	Upstream slope near crest	0.0		176.59	Ground Surface	2016	-	-	-	Decommissioned in October 2020
		T05	On crest	0.0		176.48	Ground Surface	2016	-	-	-	Decommissioned in October 2020
		T06	On crest	0.0		176.37	Ground Surface	2016	-	-	-	Decommissioned in October 2020
		T07	On crest	0.0		176.69	Ground Surface	2016	-	-	-	Decommissioned in October 2020
		T08	On crest	0.0		176.97	Ground Surface	2016	-	-	-	Decommissioned in October 2020
		T22-01	On crest	0.0		177.76	Ground Surface	2022	-	-	-	Functioning properly
		T22-02	On crest	0.0		177.60	Ground Surface	2022	-	-	-	Functioning properly
		T22-03	On crest	0.0		177.61	Ground Surface	2022	-	-	-	Functioning properly
		T22-04	On crest	0.0		177.61	Ground Surface	2022	-	-	-	Functioning properly
		T22-05	On crest	0.0		177.59	Ground Surface	2022	-	-	-	Functioning properly
	Survey Anchor	D1-SD-08	Bench downstream of Dam's crest	14.0	174.23	160.23	Silty Clay	2018	-	-	-	Functioning properly
		D1-SD-23	On protection berm downstream of Thermosyphon alignment	17.4	175.45	158.05	Clay	2020	-	-	-	Functioning properly
	Inclinometer	D1-SD-05	South abutment		176.06		31 nodes in various soils	2018	-	-	-	Functioning properly.
		D1-SD-06	Max crest settlement area		173.77		47 nodes in various soils	2018	-	-	-	Discontinued monitoring 2022
		D1-SD-07	Max crest settlement area		174.19		47 nodes in various soils	2018	-	-	-	Discontinued monitoring 2022
Splitter Dyke	Survey Monument	T1	Downstream crest	0.0		177.0	Ground surface	2022				Functioning properly
		T2	Upstream crest	0.0		176.9	Ground surface	2022				Functioning properly
		T3	Downstream crest	0.0		177.0	Ground surface	2022				Functioning properly
		T4	Upstream crest	0.0		177.3	Ground surface	2022				Functioning properly
		T5	Downstream crest	0.0		177.4	Ground surface	2022				Functioning properly
		T6	Upstream crest	0.0		177.2	Ground surface	2022				Functioning properly

Dam	Instrument type	Instrument ID	Instrument Location	Installation					Serial No. and Logger			Note
				Instrument Depth (mbgs)*	Ground Surface Elevation (masl)	Instrument Elevation (masl)	Material Instrument Installed In	Installation Year	Instrument Serial No.	Datalogger Type	Datalogger Serial No.	
Dam 2	Standpipe Piezometer	D2-SD19-23	Upstream	4 to 7.0	186.72	182.7 to 179.7	Silty Clay / Clay	2019				Not monitored in 2020, 2021 and 2022. D2-SD19-26 is blocked near surface.
		D2-SD19-24	Crest	7.0 to 10.1	183.39	176.4 to 173.3	Sandy Silt / Gravel and Rockfill	2019				
		D2-SD19-25	Upstream	10.7 to 13.7	181.26	170.6 to 167.6	Tailings	2019				
		D2-SD19-26	Downstream	6.1 to 9.1	177.50	171.4 to 168.4	Tailings	2019				
		D2-SD19-27	Downstream	5.3 to 8.4	178.50	173.2 to 170.1	Fill Material / Tailings	2019				
	Thermistor	D2-SD19-25B	Upstream	5.0 to 20.4	181.10	Node 16 at 160.7	16 nodes in various soils	2019	TS4870	-	-	Discontinued Monitoring 2023
Dam 3	Standpipe Piezometer	D3-SD19-28	Upstream crest	22.6 to 25.6	187.83	165.2 to 162.2	Clayey Silt / Silty Clay	2019				Not monitored in 2020, 2021 and 2022
		D3-SD19-29	Upstream crest	14 to 17.1	188.10	174.1 to 117	Silty Clay / Gravel	2019				
		D3-SD19-31	Downstream	12.2 to 15.2	173.45	161.25 to 158.25	Silt / Silty Clay	2019				
Dam 4	Standpipe Piezometer	D4-SD19-01	South of the dam in South Pond	6.1 to 9.1	190.77	184.7 to 181.7	Gravel / Clayey Silt	2019				Not monitored in 2020, 2021 and 2022
		D4-SD19-02	Crest	6.1 to 9.1	190.52	184.4 to 181.4	Fill Material / Bedrock	2019				Not monitored in 2020, 2021 and 2022
		D4-SD19-03B	Crest	6.1 to 9.1	190.11	184 to 181	Fill Material / Bedrock	2019				Not monitored in 2020, 2021 and 2022
		D4-SD19-04	South of the dam in South Pond	8.4 to 11.5	188.62	180.2 to 177.1	Rockfill	2019				Not monitored in 2020, 2021 and 2022
		D4-SD19-21	South of the dam in South Pond	10.7 to 13.7	190.20	179.5 to 176.5	Fill Material	2019				Destroyed
Dam 5	Standpipe Piezometer	D5-SD19-05B	South of the dam in South Pond	6.1 to 9.1	191.10	185.0 to 182.0	Tailings / Silty Clay	2019				Not monitored in 2020, 2021 and 2022
Dam 11	Standpipe Piezometer	D11-SD19-19	Crest	7.0 to 10.1	190.62	183.6 to 180.5	Fill Material	2019				Not monitored in 2020, 2021 and 2022
		D11-SD19-20	Downstream of crest	8.5 to 11.6	184.66	176.2 to 173.1	Rockfill / Silty Clay	2019				
	Thermistor	D11-SD19-20	Downstream of crest	above ground to 11	184.66	Node 16 at 173.06	Node 9 to 16 in various Soils	2019	NA	-	-	Functioning properly
Dam 21A	Vibrating Wire Piezometer	D21A-SD19-32	Dam Crest	10.9	195.57	184.67	Bedrock	2023				Discontinued Monitoring 2024
	Standpipe Piezometer	D21A-SD19-32	Dam crest	6.1 to 9.1	195.57	189.47 to 186.47	Organic Silt / Silty Clay	2019				Not monitored in 2020, 2021 and 2022
		D21A-SD19-33	Downstream toe	2.7 to 5.8	191.42	188.72 to 185.62	Rockfill / Bedrock	2019				No reading in 2019. Not monitored in 2020, 2021 and 2022.
	Thermistor	D21A-SD19-32	Dam crest	Above ground to 1	195.57	Node 16 at 184.57	Node 9 to 16 in various Soils	2019	TS4872	DT2040	2865	Functioning properly except Bead 8
Dam 21B	Thermistor	D21B-SD-19-15		-0.7 to 13.6	184.15	Node 16 at 170.6	Node 2 to 16 in various Soils	2023	TS5750	DT2040	2869	Design Thermistor (TS5746) was damaged before install
		D21B-SD19-17	Dam Crest	-0.4 to 26.0	194.78	Node 16 at 168.8	Node 2 to 16 in various Soils	2023	TS5747	DT2040	2853	Functioning properly except Bead 15
	Standpipe Piezometer	D21B-SD19-15	Downstream bench	15.2 to 18.3	184.15	168.95 to 165.85	Silt / Silt and Sand	2019				Not monitored in 2020, 2021 and 2022
		D21B-SD19-16	Dam crest	12.2 to 15.2	195.04	182.84 to 179.84	Rockfill	2019				
		D21B-SD19-17	Dam crest	24.4 to 27.4	194.78	170.38 to 167.38	Silt / Sand and Silt	2019				
Dam 21C	Thermistor	D21C-SD19-14	Bench	-0.9 to 10.4	188.10	Node 16 at 177.7	Node 3 to 16 in various soils	2023	TS5748	DT2040	2868	Functioning properly, except for Bead 3 and 16
		D21C-SD19-18	Downstream crest	-0.2 to 15.1	194.94	Node 16 at 179.8	Node 2 to 16 in various Soils	2023	TS5749	DT2040	3025	
	Standpipe Piezometer	D21C-SD19-14	Bench	9.1 to 12.2	188.10	179.00 to 175.90	Clay / Silt and Sand	2019				Not monitored in 2020, 2021 and 2022
		D21C-SD19-18	Downstream crest	13.7 to 16.8	194.94	181.24 to 178.14	Peat / Bedrock	2019				
Dam 21D	Shape Array	D21D-SD19-11	Dam crest	1.60 to 15.6	194.32	192.73 to 178.73	Fill Material / Silt	2023	SAA478031	DTSAA	DT60406	
		D21D-SD19-12	Dam crest	1.25 to 15.2	194.39	193.14 to 179.14	Fill Material / Silty Clay	2023	SAA478032	DTSAA	DT60405	
	Thermistor	D21D-SD19-13	Bench	Above ground to 12.2	187.46	Node 16 at 175.26	Node 8 to 16 in various Soils	2019	TS4871	DT2040	2852	Functioning properly except Bead 11
Dam 22A	Thermistor	D22A-SD19-09	Dam Crest	-0.8 to 10.5	194.79	Node 16 at 184.3	Node 3 to 16 in various soils	2023	TS5752	-	-	Functioning properly
		D22A-SD19-10	Downstream bench	-0.9 to 4.9	188.16	Node 16 at 183.2	Node 4 to 16 in various soils	2023	TS5753	-	-	Functioning properly, except for Bead 15
	Standpipe Piezometer	D22A-SD19-09	Dam Crest	9.1 to 12.2	194.79	185.69 to 182.59	Silty Clay / Silty Sand	2019				Not monitored in 2020, 2021 and 2022
		D22A-SD19-10	Downstream bench	3.8 to 6.9	188.16	184.36 to 181.26	Silty Clay / Bedrock	2019				
Dam 22B	Standpipe Piezometer	D22B-SD19-07	Downstream bench	10.7 to 13.7	188.22	177.52 to 174.52	Sandy Silt / Bedrock	2019				Not monitored in 2020, 2021 and 2022
		D22B-SD19-08	Dam Crest	13.7 to 16.8	194.27	180.57 to 177.47	Silt / Bedrock	2019				
	Thermistor	D22B-SD19-07	Downstream bench	-0.7 to 11.6	188.22	Node 16 at 176.6	Node 3 to 16 in various soils	2023	TS5754	-	-	Functioning properly
		D22B-SD19-08	Dam Crest	1.7 to 17.0	194.27	Node 16 at 177.27	16 nodes in various Soils	2019	TS4868	DT2040	2846	Functioning properly except Bead 16

Dam	Instrument type	Instrument ID	Instrument Location	Installation					Serial No. and Logger			Note
				Instrument Depth (mbgs)*	Ground Surface Elevation (masl)	Instrument Elevation (masl)	Material Instrument Installed In	Installation Year	Instrument Serial No.	Datalogger Type	Datalogger Serial No.	
Dam B2	Vibrating Wire Piezometer	B2-PZ-01	Upstream	2.9	165.25	162.37	Rockfill	2006	VW6219	-	-	Functioning properly
		B2-PZ-02	Upstream	2.6	164.75	162.19	Rockfill	2006	VW6216	-	-	Functioning properly
		B2-PZ-03	Upstream	2.7	164.50	161.81	Silty Clay	2006	VW6223	-	-	Functioning properly
		B2-PZ-04	Upstream	2.6	164.00	161.45	Silty Clay	2006	VW6217	-	-	Functioning properly
		B2-PZ-05	Upstream	2.8	165.00	162.17	Clay fill	2006	VW6222	-	-	Functioning properly
		B2-PZ-06	Upstream	4.5	165.00	160.53	Silty Clay	2006	VW6218	-	-	Functioning properly
		B2-PZ-07	Upstream	4.2	165.00	160.78	Silty Clay	2006	VW6220	-	-	Functioning properly
		B2-PZ-08	Upstream	0.7	163.30	162.65	Silty Clay	2006	VW6221	-	-	Not functioning since 2015
	Settlement Plate	S01	Downstream toe	0.3	167.50	167.20	Rockfill	2007				Functioning properly.
		S02	Downstream toe	0.3	167.12	166.82	Rockfill	2007				Functioning properly.
		S03	Downstream toe	0.3	166.77	166.47	Rockfill	2007				Functioning properly.
		S04	Downstream toe	0.3	166.60	166.30	Rockfill	2007				Functioning properly.
		S05	Downstream toe	0.3	166.55	166.25	Rockfill	2007				Functioning properly.
		S06	Downstream toe	0.3	166.77	166.47	Rockfill	2007				Functioning properly.
		S13	Upstream crest	0.3	168.05	167.75	Rockfill	2007				Functioning properly.
		S14	Upstream crest	0.3	167.84	167.54	Rockfill	2007				Functioning properly
		S15	Upstream crest	0.3	167.52	167.22	Rockfill	2007				Functioning properly
		S16	Upstream crest	0.3	167.51	167.21	Rockfill	2007				Functioning properly
		S17	Upstream crest	0.3	168.07	167.77	Rockfill	2007				Functioning properly
		S18	Upstream crest	0.3	168.28	167.98	Rockfill	2007				Functioning properly
		S19	Upstream crest	0.3	168.62	168.32	Rockfill	2007				Functioning properly
		S20	Upstream crest	0.3	168.94	168.64	Rockfill	2007				Functioning properly
		S21	Upstream toe	0.3	165.47	165.17	Rockfill	2007				Functioning properly.
		S22	Upstream toe	0.3	165.30	165.00	Rockfill	2007				Functioning properly.
		S23	Upstream toe	0.3	165.28	164.98	Rockfill	2007				Functioning properly.
	Survey Monument	S07	Upstream crest	0.0		167.64	Ground surface	2016				Functioning properly
		S08	Upstream crest	0.0		167.65	Ground surface	2016				Functioning properly
		S09	Upstream crest	0.0		167.64	Ground surface	2016				Functioning properly
		S10	Upstream crest	0.0		167.62	Ground surface	2016				Functioning properly
		S11	Upstream crest	0.0		167.70	Ground surface	2016				Functioning properly
		S12	Upstream crest	0.0		167.77	Ground surface	2016				Functioning properly
		S27	Downstream toe	0.0		166.43	Ground surface	2017				Functioning properly
		S28	Downstream toe	0.0		166.85	Ground surface	2017				Functioning properly
		S29	Downstream toe	0.0		166.69	Ground surface	2017				Functioning properly
		S30	Downstream toe	0.0		166.99	Ground surface	2017				Functioning properly
		S31	Downstream toe	0.0		167.41	Ground surface	2017				Functioning properly.
		S32	Downstream toe	0.0		167.78	Ground surface	2017				Functioning properly
		S33	Downstream toe	0.0		168.13	Ground surface	2017				Functioning properly
		S34	Downstream toe	0.0		168.47	Ground surface	2017				Pin bent due to heavy equipment, not monitored
		S24	Upstream toe	0.0		164.28	Ground surface	2007				Destroyed
		S25	Upstream toe	0.0		164.40	Ground surface	2007				Destroyed
		S26	Upstream toe	0.0		164.93	Ground surface	2007				Destroyed
		B2RP01	Upstream crest	0.0		167.51	Ground surface	2024				NEW Functioning properly
		B2RP02	Upstream crest	0.0		166.54	Ground surface	2024				NEW Functioning properly
		B2RP03	Downstream toe	0.0		167.48	Ground surface	2024				NEW Functioning properly
		B2RP04	Downstream toe	0.0		167.24	Ground surface	2024				NEW Functioning properly
Mill Pond Structure	Standpipe Piezometer	BC-BH21-17	Downstream toe (UBC Bridge)	4.13 to 7.13	163.08	159.0 to 156.0	Silty Clay to Clay	2021				Functioning properly
		MPB-BH21-18	Crest	6.1 to 6.9	164.75	158.7 to 157.9	Silty Clay	2021				Functioning properly
		MPB-BH21-23	Crest	4.7 to 7.4	164.72	160.0 to 157.3	Silty Clay	2021				Functioning properly
		B1-BH21-02	Crest	2.13 to 5.79	166.09	164.0 to 160.3	Fill / Rock Fill	2021				Functioning properly



innovation in
geotechnical
instrumentation

Calibration Record

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Vibrating Wire Piezometer

Customer: Golder Associates Ltd.
Model: VW2100-0.7
Serial Number: VW50778
Mfg Number: P101579
Range: 700.0 kPa
Temperature: 23.0 °C
Barometric Pressure: 1018.3 millibars
Work Order Number: 217383
Cable Length: 20 meters
Cable Markings: 527770 m - 527789 m
Cable Colour Code: Red / Black (Coil) Green / White (Thermistor)
Cable Type: EL380004
Thermistor Type: 3 kΩ

Applied Pressure (kPa)	First Reading (B units)	Second Reading (B units)	Average Reading (B units)	Calculated Linear (kPa)	Linearity Error (% FS)	Calculated Polynomial (kPa)	Polynomial Error (% FS)
0.0	9243	9236	9239	-1.3	-0.19	0.3	0.05
140.0	8547	8542	8544	139.9	-0.02	139.6	-0.06
280.0	7852	7847	7849	281.0	0.14	279.7	-0.04
420.0	7159	7155	7157	421.5	0.22	420.3	0.04
560.0	6473	6470	6472	560.8	0.11	560.5	0.07
700.0	5795	5796	5796	698.0	-0.28	699.6	-0.05
Max. Error (%):					0.28		0.07

Linear Calibration Factor: CF = 2.0307E-01 kPa/B unit
Temperature Correction Factor: Tk = 1.0407E-01 kPa/°C rise

Polynomial Gage Factors:

A = 1.0200E-06 kPa/(B unit)² B = -2.1841E-01 kPa/B unit C = _____ kPa

Pressure is calculated with the following equations:

Linear: $P = CF(L_0 - L) - Tk(T_0 - T) + (S_0 - S)$

Polynomial: $P = A(L^2) + B(L) + C - Tk(T_0 - T) + (S_0 - S)$

Users must establish site zero readings for calculation purposes

Polynomial C = - [A(L₀²) + B(L₀)]

L₀, L = initial (installation) and current readings, in B units

T₀, T = initial (installation) and current temperature, in °C

S₀, S = initial (installation) and current barometric pressure readings, in kPa

B units = B scale output of VW 2102, VW 2104, VW 2106 and DT 2011 readouts


B units = Hz²/1000 ie: 1700 Hz = 2890 B units

	Date (dd/mm/yy)	VW Reading (B units)	Temperature (°C)	Baro (mbar)
Shipped Zero Readings:	5-Jun-18	9240	21.5	1016.0

This instrument has been calibrated using standards traceable to the NIST in compliance with ANSI Z540-1

Technician: I. Kurchavov *IK*

Date: 5-Jun-18





innovation in
geotechnical
instrumentation

Calibration Record

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Vibrating Wire Piezometer

Customer: Golder Associates Ltd.
Model: VW2100-0.7
Serial Number: VW50779
Mfg Number: P101580
Range: 700.0 kPa
Temperature: 23.0 °C
Barometric Pressure: 1017.5 millibars
Work Order Number: 217303
Cable Length: 20 meters
Cable Markings: 527790 m - 527809 m
Cable Colour Code: Red / Black (Coil) Green / White (Thermistor)
Cable Type: EL380004
Thermistor Type: 3 kΩ

Applied Pressure (kPa)	First Reading (B units)	Second Reading (B units)	Average Reading (B units)	Calculated Linear (kPa)	Linearity Error (% FS)	Calculated Polynomial (kPa)	Polynomial Error (% FS)
0.0	8906	8894	8900	0.8	0.11	0.1	0.02
140.0	8145	8136	8140	139.7	-0.04	139.9	-0.02
280.0	7381	7374	7378	279.3	-0.09	279.9	-0.02
420.0	6615	6608	6612	419.5	-0.07	420.1	0.01
560.0	5846	5841	5844	560.1	0.01	560.2	0.03
700.0	5076	5076	5076	700.5	0.07	699.9	-0.02
Max. Error (%):					0.11		0.03

Linear Calibration Factor: CF = 1.8301E-01 kPa/B unit
Temperature Correction Factor: Tk = 3.7975E-02 kPa/°C rise

Polynomial Gage Factors:

A = -3.3680E-07 kPa/(B unit)² B = -1.7831E-01 kPa/B unit C = _____ kPa

Pressure is calculated with the following equations:

Linear: $P = CF(L_0 - L) - Tk(T_0 - T) + (S_0 - S)$

Polynomial: $P = A(L^2) + B(L) + C - Tk(T_0 - T) + (S_0 - S)$

Users must establish site zero readings for calculation purposes

Polynomial C = - [A(L₀²) + B(L₀)]

L₀, L = initial (installation) and current readings, in B units

T₀, T = initial (installation) and current temperature, in °C

S₀, S = initial (installation) and current barometric pressure readings, in kPa

B units = B scale output of VW 2102, VW 2104, VW 2106 and DT 2011 readouts


B units = Hz²/1000 ie: 1700 Hz = 2890 B units

	Date (dd/mm/yy)	VW Reading (B units)	Temperature (°C)	Baro (mbar)
Shipped Zero Readings:	5-Jun-10	8898	21.5	1016.0

This instrument has been calibrated using standards traceable to the NIST in compliance with ANSI Z540-1

Technician: I. Kurchavov *IK*

Date: 5-Jun-18





innovation in
geotechnical
instrumentation

Calibration Record

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Vibrating Wire Piezometer

Customer: Golder Associates Ltd.
Model: VW2100-0.7
Serial Number: VW50780
Mfg Number: P101581
Range: 700.0 kPa
Temperature: 23.0 °C
Barometric Pressure: 1017.5 millibars
Work Order Number: 217383
Cable Length: 20 meters
Cable Markings: 527750 m - 527769 m
Cable Colour Code: Red / Black (Coil) Green / White (Thermistor)
Cable Type: EL380004
Thermistor Type: 3 kΩ

Applied Pressure (kPa)	First Reading (B units)	Second Reading (B units)	Average Reading (B units)	Calculated Linear (kPa)	Linearity Error (% FS)	Calculated Polynomial (kPa)	Polynomial Error (% FS)
0.0	9084	9077	9081	1.4	0.20	0.2	0.02
140.0	8303	8297	8300	139.5	-0.07	139.8	-0.03
280.0	7516	7510	7513	278.9	-0.16	279.9	-0.02
420.0	6723	6718	6721	419.1	-0.14	420.1	0.01
560.0	5926	5923	5924	560.0	0.00	560.2	0.03
700.0	5126	5127	5126	701.1	0.16	699.8	-0.02
Max. Error (%):					0.20		0.03

Linear Calibration Factor: CF = 1.7695E-01 kPa/B unit
Temperature Correction Factor: Tk = 1.0573E-01 kPa/°C rise

Polynomial Gage Factors:

A = -6.1688E-07 kPa/(B unit)² B = -1.6819E-01 kPa/B unit C = _____ kPa

Pressure is calculated with the following equations:

Linear: $P = CF(L_0 - L) - Tk(T_0 - T) + (S_0 - S)$

Polynomial: $P = A(L^2) + B(L) + C - Tk(T_0 - T) + (S_0 - S)$

Users must establish site zero readings for calculation purposes

Polynomial C = $- [A(L_0^2) + B(L_0)]$

L_0 , L = initial (installation) and current readings, in B units

T_0 , T = initial (installation) and current temperature, in °C

S_0 , S = initial (installation) and current barometric pressure readings, in kPa

B units = B scale output of VW 2102, VW 2104, VW 2106 and DT 2011 readouts


B units = Hz²/1000 ie: 1700 Hz = 2890 B units

	Date (dd/mm/yy)	VW Reading (B units)	Temperature (°C)	Baro (mbar)
Shipped Zero Readings:	5-Jun-18	9083	21.6	1016.0

This instrument has been calibrated using standards traceable to the NIST in compliance with ANSI Z540-1

Technician: I. Kurchavov *IK*

Date: 5-Jun-18





innovation in
geotechnical
instrumentation

Calibration Record

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Vibrating Wire Piezometer

Customer: Golder Associates Ltd.
Model: VW2100-0.7
Serial Number: VW50781
Mfg Number: P101582
Range: 700.0 kPa
Temperature: 23.0 °C
Barometric Pressure: 1017.5 millibars
Work Order Number: 217383
Cable Length: 25 meters
Cable Markings: 527724 m - 527749 m
Cable Colour Code: Red / Black (Coil) Green / White (Thermistor)
Cable Type: EL380004
Thermistor Type: 3 kΩ

Applied Pressure (kPa)	First Reading (B units)	Second Reading (B units)	Average Reading (B units)	Calculated Linear (kPa)	Linearity Error (% FS)	Calculated Polynomial (kPa)	Polynomial Error (% FS)
0.0	8829	8819	8824	0.0	0.00	0.2	0.03
140.0	8121	8114	8118	139.8	-0.03	139.8	-0.03
280.0	7414	7407	7410	279.9	-0.02	279.7	-0.04
420.0	6704	6699	6701	420.3	0.04	420.1	0.02
560.0	5995	5991	5993	560.5	0.07	560.5	0.06
700.0	5291	5291	5291	699.5	-0.07	699.7	-0.04
Max. Error (%):					0.07		0.06

Linear Calibration Factor: CF = 1.9801E-01 kPa/B unit
Temperature Correction Factor: Tk = 6.5839E-02 kPa/°C rise

Polynomial Gage Factors:

$$A = 1.1083E-07 \text{ kPa/(B unit)}^2$$

$$B = -1.9958E-01 \text{ kPa/B unit}$$

$$C = \text{_____ kPa}$$

Pressure is calculated with the following equations:

Linear: $P = CF(L_0 - L) - Tk(T_0 - T) + (S_0 - S)$

Polynomial: $P = A(L^2) + B(L) + C - Tk(T_0 - T) + (S_0 - S)$

Users must establish site zero readings for calculation purposes

$$\text{Polynomial } C = -[A(L_0^2) + B(L_0)]$$

L_0 , L = initial (installation) and current readings, in B units

T_0 , T = initial (installation) and current temperature, in °C

S_0 , S = initial (installation) and current barometric pressure readings, in kPa

B units = B scale output of VW 2102, VW 2104, VW 2106 and DT 2011 readouts


B units = Hz²/1000 ie: 1700 Hz = 2890 B units

	Date (dd/mm/yy)	VW Reading (B units)	Temperature (°C)	Baro (mbar)
Shipped Zero Readings:	5-Jun-18	8822	21.5	1016.0

This instrument has been calibrated using standards traceable to the NIST in compliance with ANSI Z540-1

Technician: I. Kurchavov *IK*

Date: 5-Jun-18





innovation in
geotechnical
instrumentation

Calibration Record

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Vibrating Wire Piezometer

Customer: Golder Associates Ltd.
Model: VW2100-0.7
Serial Number: VW50782
Mfg Number: P101583
Range: 700.0 kPa
Temperature: 23.0 °C
Barometric Pressure: 1017.5 millibars
Work Order Number: 217383
Cable Length: 25 meters
Cable Markings: 527699 m - 527723 m
Cable Colour Code: Red / Black (Coil) Green / White (Thermistor)
Cable Type: EL380004
Thermistor Type: 3 kΩ

Applied Pressure (kPa)	First Reading (B units)	Second Reading (B units)	Average Reading (B units)	Calculated Linear (kPa)	Linearity Error (% FS)	Calculated Polynomial (kPa)	Polynomial Error (% FS)
0.0	8913	8904	8909	-0.1	-0.01	0.1	0.02
140.0	8206	8199	8202	139.9	-0.02	139.9	-0.02
280.0	7499	7492	7496	280.0	0.00	279.8	-0.02
420.0	6790	6786	6788	420.2	0.03	420.1	0.01
560.0	6083	6080	6081	560.3	0.04	560.3	0.04
700.0	5378	5378	5378	699.6	-0.05	699.8	-0.02
Max. Error (%):					0.05		0.04

Linear Calibration Factor: CF = 1.9818E-01 kPa/B unit
Temperature Correction Factor: Tk = 4.6077E-02 kPa/°C rise

Polynomial Gage Factors:

A = 1.1091E-07 kPa/(B unit)² B = -1.9977E-01 kPa/B unit C = kPa

Pressure is calculated with the following equations:

Linear: $P = CF(L_0 - L) - Tk(T_0 - T) + (S_0 - S)$

Polynomial: $P = A(L^2) + B(L) + C - Tk(T_0 - T) + (S_0 - S)$

Users must establish site zero readings for calculation purposes

Polynomial C = - [A(L₀²) + B(L₀)]

L₀, L = initial (installation) and current readings, in B units

T₀, T = initial (installation) and current temperature, in °C

S₀, S = initial (installation) and current barometric pressure readings, in kPa

B units = B scale output of VW 2102, VW 2104, VW 2106 and DT 2011 readouts


B units = Hz²/1000 ie: 1700 Hz = 2890 B units

	Date (dd/mm/yy)	VW Reading (B units)	Temperature (°C)	Baro (mbar)
Shipped Zero Readings:	5-Jun-18	8906	21.5	1016.0

This instrument has been calibrated using standards traceable to the NIST in compliance with ANSI Z540-1

Technician: I. Kurchavov

Date: 5-Jun-18





innovation in
geotechnical
instrumentation

Calibration Record

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Vibrating Wire Piezometer

Customer: Golder Associates Ltd.
Model: VW2100-0.7
Serial Number: VW50783
Mfg Number: P101584
Range: 700.0 kPa
Temperature: 23.0 °C
Barometric Pressure: 1018.3 millibars
Work Order Number: 217383
Cable Length: 30 meters
Cable Markings: 526169 m - 526198 m
Cable Colour Code: Red / Black (Coil) Green / White (Thermistor)
Cable Type: EL380004
Thermistor Type: 3 kΩ

Applied Pressure (kPa)	First Reading (B units)	Second Reading (B units)	Average Reading (B units)	Calculated Linear (kPa)	Linearity Error (% FS)	Calculated Polynomial (kPa)	Polynomial Error (% FS)
0.0	9103	9089	9096	1.7	0.24	0.0	0.00
140.0	8299	8289	8294	139.7	-0.05	140.0	0.00
280.0	7491	7483	7487	278.6	-0.20	279.9	-0.01
420.0	6677	6669	6673	418.7	-0.19	420.0	0.00
560.0	5856	5851	5853	559.7	-0.04	560.1	0.01
700.0	5029	5029	5029	701.6	0.23	699.9	-0.01
Max. Error (%):					0.24		0.01

Linear Calibration Factor: CF = 1.7209E-01 kPa/B unit
Temperature Correction Factor: Tk = 1.0325E-02 kPa/°C rise

Polynomial Gage Factors:

A = -7.4691E-07 kPa/(B unit)² B = -1.6154E-01 kPa/B unit C = _____ kPa

Pressure is calculated with the following equations:

Linear: $P = CF(L_0 - L) - Tk(T_0 - T) + (S_0 - S)$

Polynomial: $P = A(L^2) + B(L) + C - Tk(T_0 - T) + (S_0 - S)$

Users must establish site zero readings for calculation purposes

Polynomial C = $-[A(L_0^2) + B(L_0)]$

L_0, L = initial (installation) and current readings, in B units

T_0, T = initial (installation) and current temperature, in °C

S_0, S = initial (installation) and current barometric pressure readings, in kPa

B units = B scale output of VW 2102, VW 2104, VW 2106 and DT 2011 readouts


B units = Hz²/1000 ie: 1700 Hz = 2890 B units

	Date (dd/mm/yy)	VW Reading (B units)	Temperature (°C)	Baro (mbar)
Shipped Zero Readings:	5-Jun-18	9095	21.6	1016.0

This instrument has been calibrated using standards traceable to the NIST in compliance with ANSI Z540-1

Technician: I. Kurchavov *IK*

Date: 5-Jun-18



Calibration Record

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Vibrating Wire Piezometer

Customer:	DI-CORP -CALGARY
Sales Order:	225862
Customer ID:	
Model:	VW2100-1.0
Serial Number:	VW70616
Mfg Number:	P122291
Range:	1.0 MPa
Cable Length:	35 meters
Cable Marking:	984570 m to 984605 m
Cable Type:	EL380004HDL
Cable Colour Code:	Red/Black (Coil) Green/White (Thermistor)
Thermistor Type:	3K

Applied Pressure (MPa)	First Reading (B units)	Second Reading (B units)	Average Reading (B units)	Calculated Linear (MPa)	Linearity Error (%FS)	Calculated Polynomial (MPa)	Polynomial Error (%FS)
0.000	8859	8860	8860	0.001	0.09	0.000	0.03
0.200	8112	8113	8112	0.200	-0.05	0.200	-0.04
0.400	7360	7361	7361	0.399	-0.08	0.400	-0.02
0.600	6606	6607	6606	0.600	-0.03	0.600	0.02
0.800	5851	5852	5852	0.800	0.02	0.800	0.04
1.000	5098	5099	5099	1.000	0.04	1.000	-0.03
Max Error (%)					0.09		0.04

Linear Calibration Factor: CF = 2.6574×10^{-4} MPa/B unit
Temperature Correction Factor: Tk = -8.2379×10^{-5} MPa/°C rise

Polynomial Gauge Factor: $A = -3.4391\text{e-}10$ MPa/(B unit)² $B = -2.6094\text{e-}04$ MPa/B unit $C = \text{calculate (see below)}$ MPa

Users must establish site zero readings for calculation purposes
Polynomial C = $-(A(L_0^2) + B(L_0))$

Pressure is calculated with the following equations:

$$\text{Linear: } P = CF(L_0 - L) - Tk(T_0 - T) + (S_0 - S)$$

Polynomial: $P = A(L^2) + B(L) + C - Tk(T_0 - T) + (S_0 - S)$

L_0 , L = initial (installation) and current readings, in B units

T_0 , T = initial (installation) and current temperature, in $^{\circ}\text{C}$

S_0 , S = initial (installation) and current barometric pressure readings, in MPa

B units = $\text{Hz}^2/1000$ ie: 1700 Hz = 2890 B units

Shipped Zero Readings:	Date	VW Reading (B Units)	Temperature (°C)	Baro (mbar)
	29 Oct 2020	8846	21.7	1020.4

This instrument has been calibrated using standards traceable to the NIST in compliance with ANSI Z540-1

Technician: Kailah Toews Date: 29/10/2020

Approved: Ora Nygren Date: 29/10/2020



Monitor
with
Confidence

Calibration Record

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Vibrating Wire Piezometer

Customer: DI-CORP -CALGARY
Sales Order: 225862
Customer ID:
Model: VW2100-1.0
Serial Number: VW70615
Mfg Number: P121262
Range: 1.0 MPa
Cable Length: 35 meters
Cable Marking: 984606 m to 984641 m
Cable Type: EL380004HDL
Cable Colour Code: Red/Black (Coil) Green/White (Thermistor)
Thermistor Type: 3K

Applied Pressure (MPa)	First Reading (B units)	Second Reading (B units)	Average Reading (B units)	Calculated Linear (MPa)	Linearity Error (%FS)	Calculated Polynomial (MPa)	Polynomial Error (%FS)
0.000	8748	8750	8749	-0.000	-0.02	0.000	0.04
0.200	7958	7958	7958	0.200	-0.04	0.200	-0.05
0.400	7164	7165	7164	0.400	0.01	0.400	-0.03
0.600	6371	6371	6371	0.601	0.06	0.600	0.02
0.800	5578	5579	5579	0.801	0.08	0.801	0.07
1.000	4794	4795	4794	0.999	-0.10	1.000	-0.04
Max Error (%)					0.10		0.07

Linear Calibration Factor: CF = $2.5269\text{e-}04$ MPa/B unit
Temperature Correction Factor: Tk = $-1.2729\text{e-}04$ MPa/°C rise

Polynomial Gauge Factor:

A = $2.6559\text{e-}10$ MPa/(B unit)² B = $-2.5628\text{e-}04$ MPa/B unit C = calculate (see below) MPa

Users must establish site zero readings for calculation purposes

Polynomial C = $-[A(L_0^2) + B(L_0)]$

Pressure is calculated with the following equations:

Linear: $P = CF(L_0 - L) - Tk(T_0 - T) + (S_0 - S)$

Polynomial: $P = A(L^2) + B(L) + C - Tk(T_0 - T) + (S_0 - S)$

L_0 , L = initial (installation) and current readings, in B units

T_0 , T = initial (installation) and current temperature, in °C

S_0 , S = initial (installation) and current barometric pressure readings, in MPa

B units = Hz²/1000 ie: 1700 Hz = 2890 B units

Shipped Zero Readings:	Date	VW Reading (B Units)	Temperature (°C)	Baro (mbar)
	29 Oct 2020	8735	21.7	1020.4

This instrument has been calibrated using standards traceable to the NIST in compliance with ANSI Z540-1

Technician: Kailah Toews Date: 29/10/2020

Approved: Ora Nygren Date: 29/10/2020



Monitor
with
Confidence

Calibration Record

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Vibrating Wire Piezometer

Customer: -
Sales Order: -
Customer ID: -
Model: VW2100-0.35-L30
Serial Number: VW148057
Mfg Number: P148057
Range: 350 kPa
Cable Length: 30 meters
Cable Marking: 274195 m to 274226 m
Cable Type: EL380004
Cable Colour Code: Red/Black (Coil) Green/White (Thermistor)
Thermistor Type: 3K

Applied Pressure (kPa)	First Reading (B units)	Second Reading (B units)	Average Reading (B units)	Calculated Linear (kPa)	Linearity Error (%FS)	Calculated Polynomial (kPa)	Polynomial Error (%FS)
0.0	9199	9198	9199	-0.6	-0.18	0.1	0.03
70.0	8527	8527	8527	70.0	-0.00	69.8	-0.05
140.0	7857	7856	7857	140.5	0.14	139.9	-0.02
210.0	7189	7189	7189	210.7	0.20	210.1	0.03
280.0	6528	6527	6527	280.3	0.07	280.1	0.04
350.0	5872	5872	5872	349.2	-0.24	349.9	-0.03
Max Error (%)					0.24		0.05

Linear Calibration Factor: CF = 1.0515e-01 kPa/B unit
Temperature Correction Factor: Tk = -1.9023e-01 kPa/°C rise

Polynomial Gauge Factor:
A = 4.9002e-07 kPa/(B unit)² B = -1.1253e-01 kPa/B unit C = calculate (see below) kPa

Users must establish site zero readings for calculation purposes
Polynomial C = $-[A(L_0^2) + B(L_0)]$

Pressure is calculated with the following equations:

Linear: $P = CF(L_0 - L) - Tk(T_0 - T) + (S_0 - S)$

Polynomial: $P = A(L^2) + B(L) + C - Tk(T_0 - T) + (S_0 - S)$

L_0 , L = initial (installation) and current readings, in B units

T_0 , T = initial (installation) and current temperature, in °C

S_0 , S = initial (installation) and current barometric pressure readings, in kPa

B units = Hz²/1000 ie: 1700 Hz = 2890 B units

Shipped Zero Readings:	Date	VW Reading (B Units)	Temperature (°C)	Baro (mbar)
	05 Jul 2022	9190	21.9	1014.7

This instrument has been calibrated using standards traceable to the NIST in compliance with ANSI Z540-1

Technician: Dong Trang Date: 05/07/2022
Approved: Phillip Pham Date: 05/07/2022



MIG0106C



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: Boart Longyear Inc.
Work Order: 220453
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 25 m

This is to certify that Thermistor Strings S/N: TS4868 - TS4873 meet the RST Instruments specifications for the product.

Technician: M. Miftode MM Date: 4 April 2019

THM0008B

19-PIN Connector

Wire Colour

Thermistor Cable (EL380013P)

A	PT1	9.7	ORG (ORG/WHT) WHT (ORG/WHT)
B	PT2	10.0	PUR (PUR/WHT) WHT (ORG/WHT)
C	PT3	10.3	YEL (YEL/WHT) WHT (YEL/WHT)
D	PT4	10.6	BLK (BLK/WHT) WHT (YEL/WHT)
E	PT5	10.9	BLU (BLU/WHT) WHT (BLU/WHT)
F	PT6	11.2	GRN (GRN/WHT) WHT (BLU/WHT)
G	PT7	11.5	RED (RED/WHT) WHT (RED/WHT)
H	PT8	13.0	GRY (GRY/WHT) WHT (RED/WHT)
J	PT9	14.5	BRN (BRN/WHT) WHT (BRN/WHT)
K	PT10	16.0	PNK (PNK/WHT) WHT (BRN/WHT)
L	PT11	17.5	ORG (PUR/ORG) WHT (PNK/WHT)
N	PT12	19.0	PUR (PUR/ORG) WHT (PNK/WHT)
P	PT13	20.5	ORG (YEL/ORG) WHT (TAN/WHT)
R	PT14	22.0	YEL (YEL/ORG) WHT (TAN/WHT)
S	PT15	23.5	TAN (TAN/WHT) WHT (TAN/WHT)
T	PT16	25.0	WHT (PUR/WHT) WHT (BLK/WHT)
M	COMMON		

(Unit: M)

PT1 9.7

PT2 10.0

PT3 10.3

PT4 10.6

PT5 10.9

PT6 11.2

PT7 11.5

PT8 13.0

PT9 14.5

PT10 16.0
(Unit: M)

3K Thermistors

PT16 25.0

PT15 23.5

PT14 22.0

PT13 20.5

PT12 19.0

PT11 17.5
(Unit: M)

S/N: TS4868-TS4873



Co:	RST INSTRUMENTS LTD		
Title:	THERMISTOR CABLE-16PT/25M		
J/N:	THW0349/WO220453	Revision:	A
Author:	JP	Size:	A
Date:	2019-03-14	Sheet	1 of 1

Resistance versus Temperature Relationship 3000 Ohm NTC Thermistors

Ohms	Temp	Ohms	Temp	Ohms	Temp	Ohms	Temp	Ohms	Temp
201.1K	-50	16.60K	-10	2417	30	525.4	70	153.2	110
187.3K	-49	15.72K	-9	2317	31	507.8	71	149.0	111
174.5K	-48	14.90K	-8	2221	32	490.9	72	145.0	112
162.7K	-47	14.12K	-7	2130	33	474.7	73	141.1	113
151.7K	-46	13.39K	-6	2042	34	459.0	74	137.2	114
141.6K	-45	12.70K	-5	1959	35	444.0	75	133.6	115
132.2K	-44	12.05K	-4	1880	36	429.5	76	130.0	116
123.5K	-43	11.44K	-3	1805	37	415.6	77	126.5	117
115.4K	-42	10.86K	-2	1733	38	402.2	78	123.2	118
107.9K	-41	10.31K	-1	1664	39	389.3	79	119.9	119
101.0K	-40	9796	0	1598	40	376.9	80	116.8	120
94.48K	-39	9310	1	1535	41	364.9	81	113.8	121
88.46K	-38	8851	2	1475	42	353.4	82	110.8	122
82.87K	-37	8417	3	1418	43	342.2	83	107.9	123
77.99K	-36	8006	4	1363	44	331.5	84	105.2	124
72.81K	-35	7618	5	1310	45	321.2	85	102.5	125
68.30K	-35	7252	6	1260	46	311.3	86	99.9	126
64.09K	-33	6905	7	1212	47	301.7	87	97.3	127
60.17K	-32	6576	8	1167	48	282.4	88	94.9	128
56.51K	-31	6265	9	1123	49	283.5	89	92.5	129
53.10K	-30	5971	10	1081	50	274.9	90	90.2	130
49.91K	-29	56.92	11	1040	51	266.6	91	87.9	131
46.94K	-28	5427	12	1002	52	258.6	92	85.7	132
44.16K	-27	5177	13	965	53	250.9	93	83.6	134
39.13K	-25	4714	15	895.8	55	236.2	95	79.6	135
36.86K	-24	4500	16	863.3	56	229.3	96	77.6	136
34.73K	-23	4297	17	832.2	57	222.6	97	75.8	137
32.74K	-22	4105	18	802.3	58	216.1	98	73.9	138
30.87K	-21	3922	19	773.7	59	209.8	99	72.2	139
29.13K	-20	3748	20	746.3	60	203.8	100	70.4	140
27.49K	-19	3583	21	719.9	61	197.9	101	68.8	141
25.95K	-18	3426	22	694.7	62	192.2	102	67.1	142
24.51K	-17	3277	23	670.4	63	186.8	103	65.5	143
23.16K	-16	3135	24	647.1	64	181.5	104	64.0	144
21.89K	-15	3000	25	624.7	65	176.4	105	62.5	145
20.70K	-14	2872	26	603.3	66	171.4	106	61.1	146
19.58K	-13	2750	27	582.6	67	166.7	107	59.6	147
18.52K	-12	2633	28	562.8	68	162.0	108	58.3	148
17.53K	-11	2523	29	543.7	69	157.6	109	56.8	149
								55.6	150

Temperature calculated using:

Steinhart-Hart Linearization

$$T_c = \frac{1}{C_0 + C_1(\ln R) + C_3(\ln R)^3} - 273.15$$

3000 Ohm @ 25C NTC Thermistor

C₀= 0.0014051

C₁= 0.0002369

C₃= 0.0000001019

lnR= Natural Log of Resistance

T_c= Temperature in °C



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: Golder Associates Ltd.
Work Order: 217425
Thermistor Type: 3 k Ω


Number of Points: 18
Length: 27 m

This is to certify that Thermistor String S/N: TS4700 meets the RST Instruments specifications for the product.

Technician: J. Berg 

Date: 15 June 2018

THM0008B



Resistance versus Temperature Relationship 3000 Ohm NTC Thermistors

Ohms	Temp	Ohms	Temp	Ohms	Temp	Ohms	Temp	Ohms	Temp
201.1K	-50	16.60K	-10	2417	30	525.4	70	153.2	110
187.3K	-49	15.72K	-9	2317	31	507.8	71	149.0	111
174.5K	-48	14.90K	-8	2221	32	490.9	72	145.0	112
162.7K	-47	14.12K	-7	2130	33	474.7	73	141.1	113
151.7K	-46	13.39K	-6	2042	34	459.0	74	137.2	114
141.6K	-45	12.70K	-5	1959	35	444.0	75	133.6	115
132.2K	-44	12.05K	-4	1880	36	429.5	76	130.0	116
123.5K	-43	11.44K	-3	1805	37	415.6	77	126.5	117
115.4K	-42	10.86K	-2	1733	38	402.2	78	123.2	118
107.9K	-41	10.31K	-1	1664	39	389.3	79	119.9	119
101.0K	-40	9796	0	1598	40	376.9	80	116.8	120
94.48K	-39	9310	1	1535	41	364.9	81	113.8	121
88.46K	-38	8851	2	1475	42	353.4	82	110.8	122
82.87K	-37	8417	3	1418	43	342.2	83	107.9	123
77.99K	-36	8006	4	1363	44	331.5	84	105.2	124
72.81K	-35	7618	5	1310	45	321.2	85	102.5	125
68.30K	-35	7252	6	1260	46	311.3	86	99.9	126
64.09K	-33	6905	7	1212	47	301.7	87	97.3	127
60.17K	-32	6576	8	1167	48	282.4	88	94.9	128
56.51K	-31	6265	9	1123	49	283.5	89	92.5	129
53.10K	-30	5971	10	1081	50	274.9	90	90.2	130
49.91K	-29	56.92	11	1040	51	266.6	91	87.9	131
46.94K	-28	5427	12	1002	52	258.6	92	85.7	132
44.16K	-27	5177	13	965	53	250.9	93	83.6	134
39.13K	-25	4714	15	895.8	55	236.2	95	79.6	135
36.86K	-24	4500	16	863.3	56	229.3	96	77.6	136
34.73K	-23	4297	17	832.2	57	222.6	97	75.8	137
32.74K	-22	4105	18	802.3	58	216.1	98	73.9	138
30.87K	-21	3922	19	773.7	59	209.8	99	72.2	139
29.13K	-20	3748	20	746.3	60	203.8	100	70.4	140
27.49K	-19	3583	21	719.9	61	197.9	101	68.8	141
25.95K	-18	3426	22	694.7	62	192.2	102	67.1	142
24.51K	-17	3277	23	670.4	63	186.8	103	65.5	143
23.16K	-16	3135	24	647.1	64	181.5	104	64.0	144
21.89K	-15	3000	25	624.7	65	176.4	105	62.5	145
20.70K	-14	2872	26	603.3	66	171.4	106	61.1	146
19.58K	-13	2750	27	582.6	67	166.7	107	59.6	147
18.52K	-12	2633	28	562.8	68	162.0	108	58.3	148
17.53K	-11	2523	29	543.7	69	157.6	109	56.8	149
								55.6	150

Temperature calculated using:

Steinhart-Hart Linearization

$$T_c = \frac{1}{C_0 + C_1(\ln R) + C_3(\ln R)^3} - 273.15$$

3000 Ohm @ 25C NTC Thermistor

C₀= 0.0014051

C₁= 0.0002369

C₃= 0.0000001019

lnR= Natural Log of Resistance

T_c= Temperature in °C

19-PIN Connector

Wire Colour

A	PT1	3.0	ORG (ORG/WHT) WHT (ORG/WHT)
B	PT2	3.5	PUR (PUR/WHT) WHT (ORG/WHT)
C	PT3	4.0	YEL (YEL/WHT) WHT (YEL/WHT)
D	PT4	4.5	BLK (BLK/WHT) WHT (YEL/WHT)
E	PT5	5.0	BLU (BLU/WHT) WHT (BLU/WHT)
F	PT6	11.0	GRN (GRN/WHT) WHT (BLU/WHT)
G	PT7	13.0	RED (RED/WHT) WHT (RED/WHT)
H	PT8	15.0	GRY (GRY/WHT) WHT (RED/WHT)
J	PT9	17.0	BRN (BRN/WHT) WHT (BRN/WHT)
K	PT10	19.0	PNK (PNK/WHT) WHT (BRN/WHT)
L	PT11	20.0	ORG (PUR/ORG) WHT (BLK/WHT)
N	PT12	21.0	PUR (PUR/ORG) WHT (BLK/WHT)
P	PT13	22.0	ORG (YEL/ORG) WHT (TAN/WHT)
R	PT14	23.0	YEL (YEL/ORG) WHT (TAN/WHT)
S	PT15	24.0	TAN (TAN/WHT) WHT (TAN/WHT)
T	PT16	25.0	WHT (PNK/WHT) WHT (PUR/WHT)
U	PT17	26.0	WHT (GRY/WHT) WHT (PUR/WHT)
V	PT18	27.0	WHT (GRN/WHT) WHT (PUR/WHT)
M	COMMON		

(Unit: M)

Thermistor Cable (EL380013P)

PT1 3.0

PT2 3.5

PT3 4.0

PT4 4.5

PT5 5.0

PT6 11.0

PT7 13.0

PT8 15.0

PT9 17.0

PT10 19.0

3K Thermistors

PT18 27.0

PT17 26.0

PT16 25.0

PT15 24.0

PT14 23.0

PT13 22.0

PT12 21.0

PT11 20.0

(Unit: M)

(Unit: M)

S/N: TS4700



Co:	RST INSTRUMENTS LTD		
Title:	THERMISTOR CABLE-18PT/27M		
J/N:	THW0312/W0217425	Revision:	A
Author:	BL	Size:	A
Date:	2018-06-04	Sheet	1 of 1



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: DI-Corp
Work Order: 225862
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 23 m

This is to certify that Thermistor String S/N: TS5263 meets the RST Instruments specifications for the product.

Technician: J. Monsalvez J.M

Date: 29 October 2020



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: DI-Corp
Work Order: 225862
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 27 m

This is to certify that Thermistor Strings S/N: TS5264 – TS5266 meet the RST Instruments specifications for the product.

Technician: J. Monsalvez J.M

Date: 29 October 2020



THM0008B



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: DI-Corp
Work Order: 225862
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 31 m

This is to certify that Thermistor Strings S/N: TS5267 – TS5270 meet the RST Instruments specifications for the product.

Technician: J. Monsalvez J.M

Date: 29 October 2020

THM0008B



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: DI-Corp
Work Order: 225862
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 35 m

This is to certify that Thermistor Strings S/N: TS5271 – TS5273 meet the RST Instruments specifications for the product.

Technician: J. Monsalvez J.M

Date: 29 October 2020

THM0008B





innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: DI-Corp
Work Order: 225862
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 41 m

This is to certify that Thermistor String S/N: TS5274 meets the RST Instruments specifications for the product.

Technician: J. Monsalvez J.M


Date: 29 October 2020

THM0008B



Wire Colour

PT1, PT2, PT3 marked with red heat shrink
ORG (PUR/ORG) marked with black heat shrink




Serial Number(s):	TS5263
Cable Type:	EL380013P
No. of Points:	16
Thermistor Value:	3kOhm +/- 0.1degC

	Co: RST INSTRUMENTS LTD			
	Title: THERMISTOR CABLE - 16PT/23m			
	J/N: THW0425/SO225862			Revision: A
	Author: OU	CHK'D	APPR'D	Size: A
	Date: 2020-10-02			

Wire Colour

PT1, PT2, PT3 marked with red heat shrink
ORG (PUR/ORG) marked with black heat shrink




Serial Number(s):	TS5264-TS5266
Cable Type:	EL380013P
No. of Points:	16
Thermistor Value:	3kOhm +/- 0.1degC

	Co: RST INSTRUMENTS LTD			
	Title: THERMISTOR CABLE - 16PT/27m			
	J/N: THW0422/S0225862			Revision: A
	Author: OU	CHK'D	APPR'D	Size: A
	Date: 2020-10-02			

Wire Colour

PT1, PT2, PT3 marked with red heat shrink
ORG (PUR/ORG) marked with black heat shrink



(Unit: m)


(Unit: m)

Serial Number(s):	TS5267-TS5270
Cable Type:	EL380013P
No. of Points:	16
Thermistor Value:	3k0hm +/- 0.1degC

	Co: RST INSTRUMENTS LTD			
	Title: THERMISTOR CABLE - 16PT/31m			
	J/N: THW0421/SO225862			Revision: A
	Author: OU	CHK'D	APPR'D	Size: A
	Date: 2020-10-02			

Wire Colour

PT1, PT2, PT3 marked with red heat shrink
ORG (PUR/ORG) marked with black heat shrink




Serial Number(s):	TS5271-TS5273
Cable Type:	EL380013P
No. of Points:	16
Thermistor Value:	3k0hm +/- 0.1degC

	Co: RST INSTRUMENTS LTD			
	Title: THERMISTOR CABLE - 16PT/35m			
	J/N: THW0423/SO225862			Revision: A
	Author: OU	CHK'D	APPR'D	Size: A
	Date: 2020-10-02			

Wire Colour

PT1, PT2, PT3 marked with red heat shrink
ORG (PUR/ORG) marked with black heat shrink



Serial Number(s):	TS5274
Cable Type:	EL380013P
No. of Points:	16
Thermistor Value:	3kOhm +/- 0.1degC


	Co: RST INSTRUMENTS LTD			
	Title: THERMISTOR CABLE - 16PT/41m			
	J/N: THW0424/S0225862			Revision: A
	Author: OU	CHK'D	APPR'D	Size: A
	Date: 2020-10-02			

!!! CABLE INSTRUCTIONS !!!

Please follow the labeling instructions provided in excel doc.

The last thermistor point is on outer side of the reel.

!!! 0.2m SPACING FOR SOME POINTS !!!



Note: RST will terminate the string with 19-PIN connector

Leave Kevlar Full Length

Serial Number(s):	TS5746	Arrangement:	Standard
Cable Type:	EL380013P	Cable Length:	22m
No. of Points:	16	Strip Jacket Style:	Connector
Thermistor Value:	3kOhm +/- 0.1degC		




See Mechanical Drawing for Further Detail

Co:	RST INSTRUMENTS LTD		
Title:	THERMISTOR CABLE - 16PT/22m		
J/N:	THW0570/S0231872	Revision:	B
Author:	OU	CHK'D	JR
		APPRVD	OU
Date:	2022-06-13		
		Size:	A

!!! CABLE INSTRUCTIONS !!!

Please follow the labeling instructions provided in excel doc.
The last thermistor point is on outer side of the reel.

!!! 0.2m SPACING FOR SOME POINTS !!!



Note: RST will terminate the string with 19-PIN connector
Leave Kevlar Full Length

See Mechanical Drawing for Further Detail


Serial Number(s):	TS5746		
Cable Type:	EL380013P	Arrangement:	Standard
No. of Points:	16	Cable Length:	22m
Thermistor Value:	3k0hm +/- 0.1degC	Strip Jacket Style:	Connector

	Co:	RST INSTRUMENTS LTD		
	Title:	THERMISTOR CABLE - 16PT/22m		
	J/N:	THW0570/S0231872	Revision:	B
	Author:	OU	CHK'D	JR
	APPRV'D	OU	Size:	A
Date: 2022-06-13				

!!! CABLE INSTRUCTIONS !!!

Please follow the labeling instructions provided in excel doc.
The last thermistor point is on outer side of the reel.

!!! 0.2m SPACING FOR SOME POINTS !!!



Note: RST will terminate the string with 19-PIN connector

Leave Kevlar Full Length


Serial Number(s):	TS5747		
Cable Type:	EL380013P	Arrangement:	Standard
No. of Points:	16	Cable Length:	31m
Thermistor Value:	3k0hm +/- 0.1degC	Strip Jacket Style:	Connector

See Mechanical Drawing for Further Detail			
Co: RST INSTRUMENTS LTD			
Title: THERMISTOR CABLE - 16PT/31m			
J/N: THW0571/S0231872			
Revision: B			
Author: OU	CHK'D JR	APPR'VD OU	Size: A
Date: 2022-06-13			

!!! CABLE INSTRUCTIONS !!!

Please follow the labeling instructions provided in excel doc.
The last thermistor point is on outer side of the reel.

!!! 0.2m SPACING FOR SOME POINTS !!!



Note: RST will terminate the string with 19-PIN connector

Leave Kevlar Full Length

Serial Number(s):	TS5748		
Cable Type:	EL380013P	Arrangement:	Standard
No. of Points:	16	Cable Length:	16m
Thermistor Value:	3k0hm +/- 0.1degC	Strip Jacket Style:	Connector


See Mechanical Drawing for Further Detail			
Co:	RST INSTRUMENTS LTD		
Title:	THERMISTOR CABLE - 16PT/16m		
J/N:	THW0572/S0231872	Revision:	B
Author:	OU	CHK'D	JR
		APPR'D	OU
Date:	2022-06-13	Size:	A



!!! CABLE INSTRUCTIONS !!!

Please follow the labeling instructions provided in excel doc.
The last thermistor point is on outer side of the reel.

!!! 0.2m SPACING FOR SOME POINTS !!!



Note: RST will terminate the string with 19-PIN connector

Leave Kevlar Full Length

See Mechanical Drawing for Further Detail


Serial Number(s):	TS5749		
Cable Type:	EL380013P	Arrangement:	Standard
No. of Points:	16	Cable Length:	20m
Thermistor Value:	3k0hm +/- 0.1degC	Strip Jacket Style:	Connector

	Co:	RST INSTRUMENTS LTD		
	Title:	THERMISTOR CABLE - 16PT/20m		
	J/N:	THW0573/S0231872	Revision:	B
	Author:	OU	CHK'D	JR
	Date:	2022-06-13	APPRV'D	OU

!!! CABLE INSTRUCTIONS !!!

Please follow the labeling instructions provided in excel doc.
The last thermistor point is on outer side of the reel.

!!! 0.2m SPACING FOR SOME POINTS !!!



Note: RST will terminate the string with 19-PIN connector

Leave Kevlar Full Length


Serial Number(s):	TS5750		
Cable Type:	EL380013P	Arrangement:	Standard
No. of Points:	16	Cable Length:	19m
Thermistor Value:	3k0hm +/- 0.1degC	Strip Jacket Style:	Connector

See Mechanical Drawing for Further Detail			
Co: RST INSTRUMENTS LTD			
Title: THERMISTOR CABLE - 16PT/19m			
J/N: THW0574/S0231872		Revision: B	
Author: OU	CHK'D: JR	APPRV'D: OU	Size: A
Date: 2022-06-13			

!!! CABLE INSTRUCTIONS !!!

Please follow the labeling instructions provided in excel doc.
The last thermistor point is on outer side of the reel.

!!! 0.2m SPACING FOR SOME POINTS !!!



Note: RST will terminate the string with 19-PIN connector

Leave Kevlar Full Length


Serial Number(s):	TS5751		
Cable Type:	EL380013P	Arrangement:	Standard
No. of Points:	16	Cable Length:	19m
Thermistor Value:	3k0hm +/- 0.1degC	Strip Jacket Style:	Connector

See Mechanical Drawing for Further Detail			
Co:	RST INSTRUMENTS LTD		
Title:	THERMISTOR CABLE - 16PT/19m		
J/N:	THW0575/S0231872	Revision:	B
Author:	OU	CHK'D	JR
		APPRV'D	OU
Date:	2022-06-13	Size:	A

!!! CABLE INSTRUCTIONS !!!

Please follow the labeling instructions provided in excel doc.
The last thermistor point is on outer side of the reel.

!!! 0.2m SPACING FOR SOME POINTS !!!



Note: RST will terminate the string with 19-PIN connector
Leave Kevlar Full Length

See Mechanical Drawing for Further Detail


Serial Number(s):	TS5752		
Cable Type:	EL380013P	Arrangement:	Standard
No. of Points:	16	Cable Length:	16m
Thermistor Value:	3k0hm +/- 0.1degC	Strip Jacket Style:	Connector

	Co:	RST INSTRUMENTS LTD		
	Title:	THERMISTOR CABLE - 16PT/16m		
	J/N:	THW0576/S0231872	Revision:	B
	Author:	OU	CHK'D	JR
	APPRV'D	OU	Size:	A
Date: 2022-06-13				

!!! CABLE INSTRUCTIONS !!!

Please follow the labeling instructions provided in excel doc.
The last thermistor point is on outer side of the reel.

!!! 0.2m SPACING FOR SOME POINTS !!!



Note: RST will terminate the string with 19-PIN connector

Leave Kevlar Full Length


Serial Number(s):	TS5753		
Cable Type:	EL380013P	Arrangement:	Standard
No. of Points:	16	Cable Length:	10.5m
Thermistor Value:	3kOhm +/- 0.1degC	Strip Jacket Style:	Connector

See Mechanical Drawing for Further Detail			
Co:	RST INSTRUMENTS LTD		
Title:	THERMISTOR CABLE - 16PT/10.5m		
J/N:	THW0577/S0231872	Revision:	B
Author:	OU	CHK'D:	JR
		APPRV'D:	OU
Date:	2022-06-13	Size:	A

!!! CABLE INSTRUCTIONS !!!

Please follow the labeling instructions provided in excel doc.
The last thermistor point is on outer side of the reel.

!!! 0.2m SPACING FOR SOME POINTS !!!



Note: RST will terminate the string with 19-PIN connector

Leave Kevlar Full Length

Serial Number(s):	TS5754		
Cable Type:	EL380013P	Arrangement:	Standard
No. of Points:	16	Cable Length:	17m
Thermistor Value:	3kOhm +/- 0.1degC	Strip Jacket Style:	Connector

See Mechanical Drawing for Further Detail			
rst INSTRUMENTS		Co:	RST INSTRUMENTS LTD
		Title:	THERMISTOR CABLE - 16PT/17m
		J/N:	THW0578/SO231872
		Author:	OU
		CHK'D:	JR
		APPR'D:	OU
		Size:	A
		Date:	2022-06-13



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: Deton'Cho / Nuna Joint Venture
Work Order: 231872
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 22 m

This is to certify that Thermistor String S/N: TS5746 meets the RST Instruments specifications for the product.

Technician: PHUONG NGUYEN

A handwritten signature in blue ink, appearing to read 'Phuong'.

Date: 18 July 2022

THM0008B



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: Deton'Cho / Nuna Joint Venture
Work Order: 231872
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 31 m

This is to certify that Thermistor String S/N: TS5747 meets the RST Instruments specifications for the product.

Technician: PHUONG NGUYEN

A handwritten signature in blue ink, appearing to read 'Phuong'.

Date: 18 July 2022

THM0008B



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: Deton'Cho / Nuna Joint Venture
Work Order: 231872
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 16 m

This is to certify that Thermistor String S/N: TS5748 meets the RST Instruments specifications for the product.

Technician: PHUONG NGUYEN

A handwritten signature in blue ink, appearing to read 'Phuong'.

Date: 18 July 2022

THM0008B



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: Deton'Cho / Nuna Joint Venture
Work Order: 231872
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 20 m

This is to certify that Thermistor String S/N: TS5749 meets the RST Instruments specifications for the product.

Technician: PHUONG NGUYEN

A handwritten signature in blue ink, appearing to read 'Phuong'.

Date: 18 July 2022

THM0008B



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: Deton'Cho / Nuna Joint Venture
Work Order: 231872
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 19 m

This is to certify that Thermistor String S/N: TS5750 meets the RST Instruments specifications for the product.

Technician: PHUONG NGUYEN

A handwritten signature in blue ink, appearing to read 'Phuong'.

Date: 18 July 2022

THM0008B



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: Deton'Cho / Nuna Joint Venture
Work Order: 231872
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 19 m

This is to certify that Thermistor String S/N: TS5751 meets the RST Instruments specifications for the product.

Technician: PHUONG NGUYEN

A handwritten signature in blue ink, appearing to read 'Phuong', written over a horizontal line.

Date: 18 July 2022

THM0008B



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: Deton'Cho / Nuna Joint Venture
Work Order: 231872
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 16 m

This is to certify that Thermistor String S/N: TS5752 meets the RST Instruments specifications for the product.

Technician: PHUONG NGUYEN

A handwritten signature in blue ink, appearing to read 'Phuong'.

Date: 18 July 2022

THM0008B



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: Deton'Cho / Nuna Joint Venture
Work Order: 231872
Thermistor Type: 3 k Ω

Number of Points: 16
Length: 10.5m

This is to certify that Thermistor String S/N: TS5753 meets the RST Instruments specifications for the product.

Technician: PHUONG NGUYEN

A handwritten signature in blue ink, appearing to read 'Phuong'.

Date: 18 July 2022

THIM0008B



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Thermistor Strings

Customer: Deton'Cho / Nuna Joint Venture
Work Order: 231872
Thermistor Type: 3 kΩ

Number of Points: 16
Length: 17m

This is to certify that Thermistor String S/N: TS5754 meets the RST Instruments specifications for the product.

Technician: PHUONG NGUYEN

A handwritten signature in blue ink, appearing to read 'Phuong'.

Date: 18 July 2022

THM0008B



Innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Model DT2055B Vibrating Wire Data Logger

FW Ver: 4.04

This is to certify that s/n 16114 meets RST Instruments specifications for this product.

Technician: K.Nguyen

Date: March 3, 2023

ELL02208



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Model DT2055B Vibrating Wire Data Logger


FW Ver: 4.04

This is to certify that s/n 16115 meets RST Instruments specifications for this product.

Technician: K.Nguyen

Date: March 3, 2023

ELL0208



Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Model DT2055B Vibrating Wire Data Logger

FW Ver: 4.04

This is to certify that s/n 16111 meets RST Instruments specifications for this product.

Technician: K. Nguyen

Date: March 3, 2023

ELL0220B



Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Model DT2055B Vibrating Wire Data Logger

FW Ver: 4.04

This is to certify that s/n 16112 meets RST Instruments specifications for this product.

Technician: K. Nguyen

Date: March 3, 2023

ELL0220B



Innovation in
geotechnical
Instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Model DT2055B Vibrating Wire Data Logger

FW Ver: 4.04

This is to certify that s/n 16116 meets RST Instruments specifications for this product.

Technician: K. Nguyen

Date: March 3, 2023

ELL02208



innovation in
geotechnical
instrumentation

Certificate of Compliance

RST Instruments Ltd., 11545 Kingston St., Maple Ridge, British Columbia, Canada V2X 0Z5
Tel: 604 540 1100 • Fax: 604 540 1005 • Toll Free: 1 800 665 5599 (North America only)
e-mail: info@rstinstruments.com • Website: www.rstinstruments.com

Model DT2055B Vibrating Wire Data Logger

FW Ver: 4.04

This is to certify that s/n 15167 meets RST Instruments specifications for this product.

Technician: B. Ranibar *B.P.*

Date: October 3, 2022

ELI02208

